Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03161110 Call Order: 010 Proposal: E3Q37 District:03

Counties: DIST/ST-WIDE, SANTA ROSA

Road Name: MILTON OPERATIONS ROUTINE MAINTENANCE

Limits: 57002000

Project(s): 42214227267(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	120
Total Bridge Length:	0.000 Miles	Letting Date:	11/10/16
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: $1,400,000.00

Please read the full advertisement

Description:

The work under this Site-Specific Contract consists of rehabilitation of existing pipe by forming a lining on the host pipes interior, thereby allowing debilitated pipe to regain strength and performance capabilities. Desilting of pipe in advance of pipe lining and/or removing blockages from existing pipes, as well as cleaning and sealing manholes and pipe inlets will be required. All structures are located in Santa Rosa County, on State Road 87 South, from Nevada Street, south to Laredo Street, as shown in the Appendices. Maintenance of Traffic and Mobilization shall be incidental to other pay items listed. A Contractor Experience Form (850-070-05), Experience in Drainage Repair, is required to be submitted with bid.

Call Order: 010 Proposal: E3Q37

ALT	Item	Description	Unit	Quantity
Section 0001 CLEAN DRAINAGE STRUCTURES (LF)				
	0425- 74- 1	MANHOLES & INLETS CLEANING & SEALING, <10'	EA	12.000
	0425- 74- 2	MANHOLES & INLETS CLEANING & SEALING, >10'	EA	12.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	2,484.000
	0430- 94- 3	DESILTING PIPE, 37 - 48"	LF	362.000
	0431- 1- 2	PIPE LINER, OPTIONAL MATERIAL, 25-36"	LF	2,484.000
	0431- 1- 3	PIPE LINER, OPTIONAL MATERIAL, 37-48"	LF	362.000
	0432- 3- 5	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 30"	EA	103.000
	0432- 3- 6	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 36"	EA	98.000
	0432- 3- 7	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 42"	EA	115.000
	0433- 1-	CHEMICAL GROUT REPAIR, MANHOLE / INLET	EA	12.000