

FLORIDA DEPARTMENT OF TRANSPORTATION  
 BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES  
 (NOT FOR BIDDING PURPOSES)

LETTING ID: 04150403      CALL ORDER: 009      PROPOSAL ID: E4Q93      (Construction)  
 DISTRICT : 04      COUNTIES : BROWARD , , ,

ROAD NAME : SR-A1A FR. SR-816/OAKLAND PARK BLVD. TO FLAMINGO AVE.  
 LIMITS :

FINPROJ NO(S):      FEDERAL AID NO(S):  
 43120415201 (\*)      N/A  
 43120415601      N/A

TOTAL ROADWAY LENGTH: 0.000      MILES      CONTRACT DAYS: 648  
 TOTAL BRIDGE LENGTH: 0.000      MILES      LETTING DATE : 04/03/15  
 TOTAL PROPOSAL LENGTH: 0.000      MILES      CONTRACT EXECUTION DAYS:  
 SPECIAL START DATE: N/A  
 BUDGET AMOUNT: \$ 9,384,908.00      ACQUIS./FLEXIBLE START TIME : 30 Days (Acq. Time)

Please read the full advertisement

DESCRIPTION: Not Used  
 The Improvements under this Contract consist of roadway reconstruction, drainage, signing and pavement markings, signalization, lighting, and hardscape improvements on SR-A1A/North Ocean Boulevard from Oakland Park Boulevard to Flamingo Avenue, in Broward County.

PRE-QUALIFICATION: CONTRACTOR MUST BE PRE-QUALIFIED

ACQUISITION TIME: 30 days after Notice to Proceed to allow for submittal and approval of Contractor's Quality Control (QC) Plan

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<<		SECTION 0001 ROADWAY		>>>>>>>>>>>>
	0000200 1	ROADWAY DESIGN GROUP- GENERIC PAY ITEM 1	ZZ	708.000
	0101 1	MOBILIZATION (43120415201)	LS	1.000
	0102 1	MAINTENANCE OF TRAFFIC (43120415201)	LS	1.000
	0102 2 1	SPECIAL DETOUR 1 (43120415201)	LS	1.000
	0102 2 2	SPECIAL DETOUR 2 (43120415201)	LS	1.000
	0102 2 3	SPECIAL DETOUR 3 (43120415201)	LS	1.000
	0102 2 4	SPECIAL DETOUR 4 (43120415201)	LS	1.000
	0102 3	COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	CY	139.500
	0102 14	TRAFFIC CONTROL OFFICER	MH	672.000
	0102 60	WORK ZONE SIGN	ED	31,582.000
	0102 61	BUSINESS SIGN	EA	34.000
	0102 71 14	BARRIER WALL, TEMPORARY, F&I, TYPE K	LF	8,650.000
	0102 71 24	BARRIER WALL, TEMPORARY, RELOCATE, TYPE K	LF	7,115.000
	0102 74 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	100,523.000
	0102 74 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	14,277.000
	0102 74 5	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	29,978.000
	0102 75 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	8,929.000
	0102 76	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	3,584.000
	0102 77	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	13,621.000
	0102 78	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	2,861.000
	0102 89 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	69.000
	0102 99	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,352.000
	0102104	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	3,888.000
	0102107 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	3,888.000
	0104 10 3	SEDIMENT BARRIER	LF	391.000
	0104 15	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104 18	INLET PROTECTION SYSTEM	EA	62.000
	0107 1	LITTER REMOVAL	AC	52.750
	0107 2	MOWING	AC	13.900
	0110 1 1	CLEARING & GRUBBING (43120415201)	LS	1.000
	0110 15 1	ARBORIST WORK, TREE TRIMMING- LIMBS/ROOTS	EA	5.000
	0120 1	REGULAR EXCAVATION	CY	20,745.000
	0120 4	SUBSOIL EXCAVATION	CY	3,623.000
	0120 6	EMBANKMENT	CY	888.000

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
	0121 70	FLOWABLE FILL	CY	7.000
	0160 4	TYPE B STABILIZATION	SY	43,003.900
	0162 1 12	PREPARED SOIL LAYER, FINISH SOIL LAYER, 12"	SY	410.000
	0285706	OPTIONAL BASE, BASE GROUP 06	SY	40,177.500
	0285709	OPTIONAL BASE, BASE GROUP 09	SY	1,894.100
	0327 70 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	1,670.900
	0334 1 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	4,627.900
	0337 7 40	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22, PMA	TN	2,313.900
	0339 1	MISCELLANEOUS ASPHALT PAVEMENT	TN	80.700
	0425 1201	INLETS, CURB, TYPE 9, <10'	EA	1.000
	0425 1205	INLETS, CURB, TYPE 9, PARTIAL	EA	1.000
	0425 1351	INLETS, CURB, TYPE P-5, <10'	EA	15.000
	0425 1355	INLETS, CURB, TYPE P-5, PARTIAL	EA	1.000
	0425 1361	INLETS, CURB, TYPE P-6, <10'	EA	5.000
	0425 1365	INLETS, CURB, TYPE P-6, PARTIAL	EA	2.000
	0425 1451	INLETS, CURB, TYPE J-5, <10'	EA	1.000
	0425 1521	INLETS, DT BOT, TYPE C, <10'	EA	4.000
	0425 1561	INLETS, DT BOT, TYPE F, <10'	EA	4.000
	0425 1711	INLETS, GUTTER, TYPE V, <10'	EA	1.000
	0425 1905	INLETS, SPECIAL, PARTIAL	EA	10.000
	0425 2 41	MANHOLES, P-7, <10'	EA	2.000
	0425 2 43	MANHOLES, P-7, PARTIAL	EA	21.000
	0425 2 71	MANHOLES, J-7, <10'	EA	2.000
	0425 5 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0425 6	VALVE BOXES, ADJUST	EA	35.000
	0425 10	YARD DRAIN	EA	1.000
	0430175115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	26.000
	0430175118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	1,299.000
	0430175124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	43.000
	0430963 2	PVC PIPE FOR BACK OF SIDEWALK, NON STANDARD DIAMETER	LF	34.000
	0520 1 10	CONCRETE CURB & GUTTER, TYPE F	LF	15,361.000
	0520 2 4	CONCRETE CURB, TYPE D	LF	5,277.000
	0522 1	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,647.000
	0522 2	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,801.000
	0523 1	PATTERNED PAVEMENT, VEHICULAR AREAS	SY	1,481.800
	0526 1 1	PAVERS, ARCHITECTURAL, ROADWAY	SY	120.300
	0526 1 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	5,028.800
	0527 2	DETECTABLE WARNINGS	SF	796.000
	0542 70	BUMPER GUARDS, CONCRETE	EA	22.000
	0570 1 1	PERFORMANCE TURF	SY	5,461.000
	0590 70	IRRIGATION SYSTEM (43120415201)	LS	1.000
	0591 1 19	IRRIGATION SLEEVE, 6" DIAMETER, PROJECT NUMBER 431204-1-52-01	LF	1,893.000
	0591 1 20	IRRIGATION SLEEVE, 4" DIAMETER, PROJECT NUMBER 431204-1-52-01	LF	187.000
	0591 1 21	IRRIGATION SLEEVE, 2" DIAMETER, PROJECT NUMBER 431204-1-52-01	LF	2,376.000
	0700 1 50	SINGLE POST SIGN, RELOCATE	AS	35.000
	0710 11111	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	NM	8.694
	0710 11122	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	LF	330.000
	0710 11123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,174.000
	0710 11124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	838.000
	0710 11125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,199.000
	0710 11131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.607
	0710 11151	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	LF	5,899.000
	0710 11160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	147.000
	0710 11170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	53.000
	0710 11211	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	NM	3.753
	0710 11224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	116.000

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
	0710 11251	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, DOTTED/ GUIDELINE/6-10 GAP EXTENSION, 6"	LF	593.000
	0999 16	PARTNERING, DO NOT BID (43120415201)	LS	1.000
	0999 25	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43120415201)	LS	1.000
		SECTION 0002 SIGNING		>>>>>>>>>>>>>
	0700 1 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	95.000
	0700 1 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700 1 50	SINGLE POST SIGN, RELOCATE	AS	13.000
	0700 1 60	SINGLE POST SIGN, REMOVE	AS	70.000
	0700 2 11	MULTI- POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	4.000
	0700 2 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700 2 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	2.000
	0700 2 60	MULTI- POST SIGN, F&I GROUND MOUNT, REMOVE	AS	7.000
	0710 90	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43120415201)	LS	1.000
	0711 14160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	39.000
	0711 14170	THERMOPLASTIC, PREFORMED, WHITE, ARROWS	EA	40.000
		SECTION 0003 LIGHTING		>>>>>>>>>>>>>
	0630 2 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	8,618.000
	0630 2 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,501.000
	0635 2 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	154.000
	0715 1 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	69,991.000
	0715 1 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	21,113.000
	0715 1 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	21,647.000
	0715 4400	LIGHT POLE COMPLETE, RELOCATE	EA	1.000
	0715 4600	LIGHT POLE COMPLETE, REMOVE	EA	61.000
	0715 7 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715500 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	122.000
	0715511330	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, CONCRETE, 30'	EA	7.000
	0715512315	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, DOUBLE ARM SHOULDER MOUNT, CONCRETE, 15'	EA	51.000
	0715512330	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, DOUBLE ARM SHOULDER MOUNT, CONCRETE, 30'	EA	64.000
		SECTION 0004 SIGNALIZATION		>>>>>>>>>>>>>
	0630 2 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,478.000
	0630 2 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	684.000
	0632 7 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0632 7 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	3,744.000
	0632 7 4	SIGNAL CABLE, ADJUST	PI	5.000
	0633 8 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	649.000
	0634 4600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	1.000
	0635 2 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	49.000
	0639 1123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	1.000
	0639 2 1	ELECTRICAL SERVICE WIRE	LF	1,239.000
	0639 3 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0641 2 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0641 2 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	4.000
	0646 1 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	30.000
	0646 1 40	ALUMINUM SIGNALS POLE, RELOCATE	EA	3.000
	0646 1 60	ALUMINUM SIGNALS POLE, REMOVE	EA	19.000
	0649 31103	MAST ARM,F&I, WIND SPEED-150, SINGLE ARM,W/0 LUMINAIRE-60	EA	2.000
	0649 31105	MAST ARM,F&I, WIND SPEED-150,SINGLE ARM,W/0 LUMINAIRE-78	EA	1.000
	0649 31111	MAST ARM,F&I, WIND SPEED-150,DOUBLE ARM,W/0 LUMINAIRE, 36-46	EA	1.000
	0649 31117	MAST ARM,F&I, WIND SPEED-150,DOUBLE ARM,W/0 LUMINAIRE, 60-60	EA	1.000
	0649 36300	MAST ARM, REMOVE SHALLOW FOUNDATION, BOLT ON ATTACHMENT	EA	1.000
	0650 1 14	TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	16.000

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
	0650 1 19	TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	3.000
	0650 1 60	TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	12.000
	0650 1 70	TRAFFIC SIGNAL, RELOCATE	AS	14.000
	0653 1 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	32.000
	0653 1 40	PEDESTRIAN SIGNAL, RELOCATE	AS	3.000
	0653 1 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	26.000
	0660 4 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660 4 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	4.000
	0660 4 41	VEHICLE DETECTION SYSTEM- VIDEO, RELOCATE CABINET EQUIPMENT	EA	4.000
	0660 4 42	VEHICLE DETECTION SYSTEM- VIDEO, RELOCATE ABOVE GROUND EQUIPMENT	EA	9.000
	0665 1 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	22.000
	0665 1 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	10.000
	0665 1 40	PEDESTRIAN DETECTOR, RELOCATE	EA	5.000
	0665 1 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	28.000
	0670 5140	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL MODEL 2070	AS	7.000
	0670 5600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	6.000
	0700 3201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700 5 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
	0700 5 50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	3.000
	0700 5 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	4.000
	0746 76	TMS CABINET, REMOVE	EA	1.000
<<<<<<<<<<<		SECTION 0005 UTILITIES		>>>>>>>>>>>
	0425 5 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0425 6	VALVE BOXES, ADJUST	EA	35.000