

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 04151204 Call Order: 004 Proposal: E4R19 District:04
Counties: DIST/ST-WIDE
Road Name: DISTRICTWIDE "ON-CALL" BRIDGE REPAIR CONTRACT
Limits: Midpoint
Project(s): 23040695201(*) Federal Aid No: N/A
Total Roadway Length: 0.000 Miles Contract Days: 730
Total Bridge Length: 0.000 Miles Letting Date: 12/04/15
Total Proposal Length: 0.000 Miles Contract Execution Days:
Special Start Date: N/A
Aquis/Flexible Start Time: 15 Days (Acq. Time)
Proposal Budget Estimate: \$316,240.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of removal of existing identified pile jackets and subsequent construction of proposed structural pile jackets with lengths as specified in the Plans, in various locations throughout District 4. The summary of pay items for this project is listed in the Plans.

This is a PUSHBUTTON CONTRACT: The award and contract performance bond shall be based on the Pushbutton budgeted amount of \$316,240.00 and not the Contractor's bid total.

PRE-QUALIFICATION: Contractor must be prequalified by FDOT in Repair and Rehab of Minor Bridge.

MANDATORY PRE-BID MEETING: A Pre-Bid Meeting has been scheduled for November 18, 2015 from 8:30 a.m. to 10:00 a.m. in the D4-DO1 Administration Conference Room at 3400 West Commercial Boulevard, Fort Lauderdale, FL, 33309

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 004 Proposal: E4R19

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0102- 14-	TRAFFIC CONTROL OFFICER	MH	608.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	402.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURE	SF	110.000
	0121- 70-	FLOWABLE FILL	CY	365.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT:	LF	10,000.000
	0400- 2- 4	CONC CLASS II, SUPERSTRUCTURE	CY	110.000
	0400- 2- 5	CONCRETE CLASS II, SUBSTRUCTURE	CY	110.000
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY	110.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	25,000.000
	0400-145-	CLEANING CONCRETE SURFACE	SF	13,000.000
	0401- 70- 1	RESTORE SPALLED AREAS, EPOXY	CF	146.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	110.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	15.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	110.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	730.000
	0457- 1- 22	STANDARD INTEGRAL PILE JACKET, STRUCTURAL, 16.1 to 30.0"	LF	146.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	4,100.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	438.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	493.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	256.000