# Florida Department of Transportation
## Bid Solicitation Notice and Approximate Quantities

Letting: 04161007 Call Order: 002 Proposal: E4S04 District:04

Counties: BROWARD

Road Name: SR-810/HILLSBORO BLV

Limits: SR-810/HILLSBORO BLV OVER SR-91 TURNPIKE

Project(s): 43110715201(*) Federal Aid No: N/A

| | | | |
|---|---|---|---|
| Total Roadway Length: | 0.042 Miles | Contract Days: | 102 |
| Total Bridge Length: | 0.041 Miles | Letting Date: | 10/07/16 |
| Total Proposal Length: | 0.083 Miles | Contract Execution Days: | |
| | | Special Start Date: | N/A |
| | | Aquis/Flexible Start Time: | 60 Calendar Days |

Proposal Budget Estimate: $302,705.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of removing existing pedestrian enclosure and fascia curb at the north and south sides of the bridge and installation of a new concrete parapet and new enclosed pedestrian fencing at the north and south sides of the bridge as well as vertical fencing at the approaches in Broward County.

Pre-Qualified: Contractor must be pre-qualified.

**Call Order: 002 Proposal: E4S04**

| ALT | Item | Description | Unit | Quantity |
|---|---|---|---|---|
| **Section 0001 Structures** | | | | |
| | 0110- 3- | REMOVAL OF EXISTING STRUCTURES/BRIDGES (43110715201) | LS | 1.000 |
| | 0400-143- | CLEANING & COATING CONCRETE SURFACE, CLASS 5 | SF | 289.000 |
| | 0521- 6- 11 | CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT | LF | 434.000 |
| | 0550- 10-325 | FENCING, TYPE R, 5.1-6.0', VERTICAL | LF | 31.000 |
| | 0550- 10-343 | FENCING, TYPE R, 7.1-8.0, W/FULL ENCLOSURE | LF | 428.000 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (43110715201) | LS | 1.000 |
| **Section 0002 Roadway** | | | | |
| | 0101- 1- | MOBILIZATION (43110715201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (43110715201) | LS | 1.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 4,201.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 11,526.000 |
| | 0102- 74- 2 | CHANNELIZING DEVICE, TYPE III, 6' | ED | 884.000 |
| | 0102- 74- 6 | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | ED | 408.000 |
| | 0102- 76- | ARROW BOARD / ADVANCE WARNING ARROW PANEL | ED | 340.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 232.000 |
| | 0104- 18- | INLET PROTECTION SYSTEM | EA | 8.000 |
| | 0107- 1- | LITTER REMOVAL | AC | 3.000 |