FLORIDA DEPARTMENT OF TRANSPORTATION
BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 05141104 CALL ORDER: 001 PROPOSAL ID: E5T69 (Maintenance)
DISTRICT : 05 COUNTIES : BREVARD , , ,

ROAD NAME : INSIDE PAVED SHOULDERS
LIMITS : VARIOUS LOCATIONS

FINPROJ NO(S): FEDERAL AID NO(S):
42202527202 (*) N/A

TOTAL ROADWAY LENGTH: 0.000 MILES CONTRACT DAYS: 130
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 11/04/14
TOTAL PROPOSAL LENGTH: 0.000 MILES CONTRACT EXECUTION DAYS:
SPECIAL START DATE: N/A
BUDGET AMOUNT: $ 530,000.00 ACQUIS./FLEXIBLE START TIME : 14 days

Please read the full advertisement

DESCRIPTION:
STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION DISTRICT 5

Proposal ID: E5T69

FINANCIAL PROJECT NO. 422025-2-72-02 Fiscal Year: 2015

Counties: Brevard Calendar Days: 130 Lead Time: 14 days

This is a Maintenance Streamline Plan Quantity project. For this Contract, all pay items are plan quantity items as defined in Subarticle 9-1.3.2.

INTENT AND SCOPE: The improvements under this Contract consist of constructing inside shoulder pavement (excluding turn lane bays), Type E curb and gutter, shoulder rework, install performance sod, and refurbish edge lines with paint on SR 5/US 1, SR 405 ramps, and SR 3, in Brevard County.

EXPERTISE REQUIRED: For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Asphalt Paving projects , or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Hot Plant Mix Bituminous Course " will suffice to meet the above requirements.

ALT	ITEM NO.	D E S C R I P T I O N	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<<		SECTION 0001 ASPHALT REPAIR (MECHANICAL) (TN)		>>>>>>>>>>>>
	0101 1	MOBILIZATION	LS	1.000
	0102 1	MAINTENANCE OF TRAFFIC	LS	1.000
	0120 1	REGULAR EXCAVATION	CY	1,780.000
	0285704	OPTIONAL BASE, BASE GROUP 04	SY	8,450.000
	0334 1 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	634.000
	0520 1 7	CONCRETE CURB & GUTTER, TYPE E	LF	388.000
	0570 1 2	PERFORMANCE TURF, SOD	SY	31,670.000
	0710 11211	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	NM	7.200
	E577 70 1	REWORKING SHOULDERS (SPOT REPAIRS)	SY	31,670.000