FLORIDA DEPARTMENT OF TRANSPORTATION
BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 05150106 CALL ORDER: 002 PROPOSAL ID: E5T42 (Maintenance)
DISTRICT : 05 COUNTIES : VOLUSIA , , ,

ROAD NAME : Williamson Canal Maint
LIMITS : SR 9Volusia County

FINPROJ NO(S): FEDERAL AID NO(S):
43525917201 (*) N/A

TOTAL ROADWAY LENGTH: 0.000 MILES CONTRACT DAYS: 140
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 01/06/15
TOTAL PROPOSAL LENGTH: 0.000 MILES CONTRACT EXECUTION DAYS:
SPECIAL START DATE: N/A
BUDGET AMOUNT: $ 960,000.00 ACQUIS./FLEXIBLE START TIME : 30 days

Please read the full advertisement

DESCRIPTION: Not Used
FDOT District 5

Proposal ID: E5T42

FINANCIAL PROJECT NO. 435259-1-72-01 Fiscal Year: 2015

Counties: Volusia Calendar Days: 140 Lead Time: 30 days

This is a Streamline Plan Quantity project.

INTENT AND SCOPE: The improvements under this Contract consist of restoration of the Williamson Canal to its original design profile. Clean and repair of the existing drainage structures, specifically, an existing concrete box culvert and a sheet pile weir, and soil stabilization measures along the canal side slopes located in Daytona Beach, FL.

EXPERTISE REQUIRED: For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Drainage Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements. The experience/expertise form is apart of the bid package and must be turned in completed by the contractor the day that the bids are due.

ALT	ITEM NO.		D E S C R I P T I O N	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<<			SECTION 0001 CLEAN DRAINAGE STRUCTURES (LF)		>>>>>>>>>>>>
	0101 1		MOBILIZATION	LS	1.000
	0102 1		MAINTENANCE OF TRAFFIC	LS	1.000
	0104 7		SEDIMENT BASIN / CONTAINMENT SYSTEM	EA	3.000
	0104 9		SEDIMENT BASIN / CONTAINMENT SYSTEM- CLEANOUT	EA	3.000
	0104 11		FLOATING TURBIDITY BARRIER	LF	1,000.000
	0104 15		SOIL TRACKING PREVENTION DEVICE	EA	5.000
	0104 20		CHEMICAL TREATMENT - FLOC LOGS, DRUMS	EA	10.000
	0110 1	1	CLEARING & GRUBBING	LS	1.000
	0120 5		CHANNEL EXCAVATION	CY	10,878.000
	0120 6		EMBANKMENT	CY	39,213.000
	0430950		DESILTING CONCRETE BOX CULVERT	CY	1.000
	0524 1	1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	56.300
	0524 1	4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	24.100
	0547 70	2	RIPRAP FABRIC-FORMED CONCRETE, 10" FILTER POINTS	SY	1,802.000
	0561 2		COATING EXISTING STRUCTURAL STEEL	SF	1.000
	0570 1	2	PERFORMANCE TURF, SOD	SY	45,634.000
	0999 25		INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000