FLORIDA DEPARTMENT OF TRANSPORTATION
BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 05150602 CALL ORDER: 001 PROPOSAL ID: E5W86 (Construction)
DISTRICT : 05 COUNTIES : VOLUSIA , , ,

ROAD NAME : SR 600 (US 92) FROM MIDWAY AVE TO ADAMS ST
LIMITS :

FINPROJ NO(S): FEDERAL AID NO(S):
43488315201 (*) N/A

TOTAL ROADWAY LENGTH: 1.800 MILES CONTRACT DAYS: 120
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 06/02/15
TOTAL PROPOSAL LENGTH: 1.800 MILES CONTRACT EXECUTION DAYS:
SPECIAL START DATE: N/A
BUDGET AMOUNT: $ 628,549.00 ACQUIS./FLEXIBLE START TIME : 150 Days (Acq. Time)

Please read the full advertisement

DESCRIPTION:
43488315201 SCOPE OF WORK INTENT OF CONTRACT. (REV 8-19-09) (FA 8-24-09) (1-15) ARTICLE 4-1 is expanded by the following: The Improvements under this Contract consist of (installation of mast arm signalization at existing signalized intersections of Midway Ave. and Adams St. on US 92 to include sidewalk FPID: 434883-1-52-01 -5- and curb ramp upgrades, median traffic separator modification, and pavement markings in Daytona Beach, Florida in Volusia County.). The summary of pay items for this project is listed in the Plans.

PREQUALIFICATION REQUIRED

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<<		SECTION 0001 ROADWAY		>>>>>>>>>>>>
	0101 1	MOBILIZATION (43488315201)	LS	1.000
	0102 1	MAINTENANCE OF TRAFFIC (43488315201)	LS	1.000
	0102 60	WORK ZONE SIGN	ED	1,010.000
	0102 74 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,370.000
	0102 76	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	52.000
	0102 77	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	384.000
	0102104	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	240.000
	0102107 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	240.000
	0110 1 1	CLEARING & GRUBBING (43488315201)	LS	1.000
	0285709	OPTIONAL BASE, BASE GROUP 09	SY	33.000
	0334 1 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	5.400
	0337 7 73	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22, ARB	TN	1.800
	0520 1 10	CONCRETE CURB & GUTTER, TYPE F	LF	254.000
	0520 70	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	2.000
	0522 1	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	333.000
	0527 2	DETECTABLE WARNINGS	SF	83.000
	0570 1 2	PERFORMANCE TURF, SOD	SY	262.000
	0999 25	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43488315201)	LS	1.000
<<<<<<<<<<<<		SECTION 0002 SIGNING		>>>>>>>>>>>>
	0700 1 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0700 3602	SIGN PANEL, REMOVE, 12-20 SF	EA	8.000
	0700 5 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	8.000
	0700 5 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	1.000
	0711 11123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	531.000
	0711 11125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	580.000
	0711 17	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS	SF	1,249.000
<<<<<<<<<<<<		SECTION 0003 SIGNALIZATION		>>>>>>>>>>>>

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
	0630 2 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	797.000
	0630 2 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	542.000
	0630 2 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	40.000
	0632 7 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0632 7 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	2.000
	0633 1121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	110.000
	0633 1420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	65.000
	0633 2 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	52.000
	0633 3 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	6.000
	0633 3 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	2.000
	0633 3 41	FIBER OPTIC CONNECTION HARDWARE, RELOCATE SPLICE ENCLOSURE	EA	2.000
	0633 8 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	1,483.000
	0634 4600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	2.000
	0635 2 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	31.000
	0635 2 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0635 2 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	2.000
	0639 1123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	2.000
	0639 2 1	ELECTRICAL SERVICE WIRE	LF	424.000
	0641 2 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	2.000
	0641 2 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	4.000
	0641 2 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	4.000
	0641 2 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	2.000
	0646 1 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	12.000
	0649 31201	MAST ARM,F&I, WIND SPEED-130,SINGLE ARM,W/0 LUMINAIRE-36	EA	1.000
	0649 31202	MAST ARM,F&I, WIND SPEED-130,SINGLE ARM,W/0 LUMINAIRE-46	EA	2.000
	0649 31203	MAST ARM,F&I, WIND SPEED-130,SINGLE ARM,W/0 LUMINAIRE-60	EA	1.000
	0649 31211	MAST ARM,F&I, WIND SPEED-130,DOUBLE ARM,W/0 LUMINAIRE, 36-46	EA	1.000
	0649 31299	MAST ARM,F&I, WIND SPEED-130, CUSTOM	EA	2.000
	0650 1 24	TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE W/ALUM TOP, 3 SECTION, 1 WAY	AS	27.000
	0650 1 60	TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	23.000
	0653 1 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	14.000
	0653 1 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	10.000
	0665 1 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	6.000
	0665 1 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	8.000
	0665 1 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	10.000
	0671 2 50	TRAFFIC CONTROLLER, RELOCATE- WITHOUT CABINET	EA	2.000
	0676 1116	TRAFFIC SIGNAL CONTROLLER CABINET, FURNISH & INSTALL WITHOUT CONTROLLER, NEMA SIZE6, 44" W X 52" H X 24" D	EA	2.000
	0676 1600	TRAFFIC SIGNAL CONTROLLER CABINET, REMOVE	EA	2.000
	0680 1400	SYSTEM CONTROL EQUIPMENT, RELOCATE	EA	8.000
	0682 1 40	ITS CCTV CAMERA, RELOCATE	EA	1.000
	0715 4600	LIGHT POLE COMPLETE, REMOVE	EA	1.000
	0715 5 12	LUMINAIRE & BRACKET ARM, F&I, GALVANIZED STEEL	EA	1.000