

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05150901 Call Order: 007 Proposal: E5T67 District:05
 Counties: ORANGE, SEMINOLE
 Road Name: DRAINAGE REPAIR VARIOUS LOCATIONS
 Limits: Orange & Seminole Counties
 Project(s): 42563827204(*) Federal Aid No: N/A
 Total Roadway Length: 0.000 Miles Contract Days: 100
 Total Bridge Length: 0.000 Miles Letting Date: 09/01/15
 Total Proposal Length: 0.000 Miles Contract Execution Days:
 Special Start Date: N/A
 Aquis/Flexible Start Time: 14 Days

Proposal Budget Estimate: \$549,999.00

Please read the full advertisement

Description:

DEPARTMENT OF TRANSPORTATION DISTRICT 5 Proposal ID: E5T67 FINANCIAL PROJECT NO. 425638-2-72-04 Fiscal Year: 2016 County: Orange and Seminole Calendar Days: 100 Lead Time: 14 days. This is a Maintenance Plan Quantity Project. INTENT AND SCOPE: The Improvements under this Contract consist of desilting of pipes, providing color video before and after improvements, sealing joints with internal joint seals and lining storm drains on various State Roads in Orange and Seminole Counties according to attached plans. EXPERTISE REQUIRED: For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Drainage Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

Call Order: 007 Proposal: E5T67

ALT	Item	Description	Unit	Quantity
Section 0001 CLEAN DRAINAGE STRUCTURES (LF)				
	0102- 1-	MAINTENANCE OF TRAFFIC	DA	1.000
	0425- 74- 2	MANHOLES & INLETS CLEANING & SEALING, >10'	EA	4.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	475.000
	0430- 94- 3	DESILTING PIPE, 37 - 48"	LF	160.000
	0430- 94- 4	DESILTING PIPE, 49 - 60"	LF	220.000
	0430-821- 43	CLEANING & SEALING EXISTING PIPE JOINT, 60", STORM SEWER	EA	61.000
	0430-821- 61	CLEANING & SEALING EXISTING PIPE JOINT, >60", STORM SEWER	EA	71.000
	0431- 1- 2	PIPE LINER, OPTIONAL MATERIAL, 25-36"	LF	475.000
	0431- 1- 3	PIPE LINER, OPTIONAL MATERIAL, 37-48"	LF	160.000
	0431- 1- 4	PIPE LINER, OPTIONAL MATERIAL, 49 - 60"	LF	220.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000