

**ADDENDUM ONE**  
**CONTRACT: E-5J17**  
**FINANCIAL PROJECT #: 420094-1-72-01**  
**DESCRIPTION: REMOVING AND REPLACING CONCRETE SIDEWALKS, RAMPS, ETC.**  
**LETTING DATE: 10/04/2006**

**QUESTION:**

We need clarification for an item of work on the above referenced project;

On Attachment Sheet (Locations & Quantities), Site #21, you have Concrete Pavement Removal - 733 SY and also Remove Flexible Pavement - 733 SY. Are we to Remove the Concrete inside the Curbed Median or are we to Remove the Flexible Pavement from between the Turn Lane and the Curbed Median? There is a Pay Item for both, at the same location, for the same quantity. Please clarify!

Thank you,  
James Owens  
Vice President/Estimator  
L-J Construction Co. of Central Florida  
Phone: 863-984-4412  
Fax: 863-984-9605  
E-Mail: [ljconstructionco@AOL.com](mailto:ljconstructionco@AOL.com)

**ANSWER:**

Site #21 SR 40 Concrete Median on west side of I-95, Ormond Beach

The intent is to prepare the median for landscaping. The concrete median was poured on top of asphalt pavement. The Call-Out on the Detail reads:

"REMOVE MEDIAN INTERIOR CONCRETE, TEMPORARY ASPHALT PAVEMENT AND BASE MATERIAL.  
INSTALL FINISH SOIL LAYER AND SOD. SEE KEY THIS SHEET."

The estimated quantity of concrete removal, flexible pavement [old temp asphalt] and sod are all 733 SY. The depth of the base material may vary widely.

Thanks.  
Rick Snow  
Field Maintenance Administrator  
DeLand Operations  
386-740-3414 office  
386-405-2028 cell

---

Company

---

Signature

---

Date

