



Florida Department of Transportation

CHARLIE CRIST
GOVERNOR

719 S Woodland Blvd
DeLand, FL 32720

Stephanie C. Kopelousos
Secretary

May 20, 2009
Addendum No. 1

TO: ALL PLANS AND/OR PROPOSAL HOLDERS
FINANCIAL ITEM NUMBER: 42640615201
CONTRACT NUMBER: E5N41
CALL ORDER: 009
LETTING DATE: JUNE 2, 2009
COUNTY: BREVARD

DESCRIPTION: Improvements under this Contract consist of Installing a vegetative buffer along the south side of SR 528 between SR 3 and Banana River Drive in Brevard County. The following revisions have been made.

There are NO palms to be relocated on this project. See revised Plan Sheet to strike the words “palm relocation” from sheet LD-2 note 5.

Please sign the Addendum in the space provided and email, mail, or fax back verifying receipt.

If you have any further questions please contact Vickie Wyche at (386) 943-5525 or by email at vickie.wyche@dot.state.fl.us

Sincerely,

Vickie H. Wyche
District Contracts Administration
District Five

Received by: _____
Company: _____

Date: _____
Fax to: (386) 943-5405

0001 SUMMARY OF LANDSCAPE / PERIPHERAL		PAY ITEMS		QUANTITY TOTAL
ITEM NUMBER	ITEM DESCRIPTION	UNIT	42640615201	
10999 - 2-	LUMP SUM CONTRACT, ALTERNATIVE BIDDING (42640615201)	L/S	1.000	1.000
10999 - 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42640615201)	L/S	1.000	1.000
-----				-----
			1.000	1.000

PAY ITEM NOTES

999-2 Payment for this item includes:

1. Landscape Complete - Large Plants
 - a. Tree planting is to occur in areas designated on the plans. Several of these areas have been recently cleared or contain existing trees. Existing trees are to remain and be protected.
 - b. Hand dig when installing plantings within the drip line of existing trees.
 - c. Tree locations must be flagged for approval by FDOT District Landscape manager prior to planting and may be field adjusted.
 - d. After planting apply (1) application of an approved granular pre-emergent herbicide as per manufacturer's recommendations prior to mulching.
 - e. Mulch beds with a 3" layer of pine straw mulch. Mulch shall be inspected and certified by the Florida Department of Agriculture and Consumer Services, Division of Plant Industry.

2. Pre-emergent granular herbicide shall be applied to all mulched plantings in beds and individual mulch rings. The herbicide active ingredients shall be suitable for control of annual and perennial broadleaf weeds and grasses. The granular herbicide shall be applied by hand after planting and before placing mulch. The herbicide shall be applied at a rate recommended by the manufacturer.

3. Water for plant establishment shall be provided per FDOT Specifications and shall be applied by hand. The contractor may, at his expense, design and install a temporary low volume/drip irrigation system to aid in plant establishment. The contractor shall provide shop drawings for approval of said system. No water wells may be drilled on FDOT R.O.W.

4. Mycorrhizal Inoculant shall be applied per manufacturer's directions to all proposed plants at the following rates:
 - 6 oz. per 15 gallon plant
 - 12 oz. per 30 gallon plant
 - 14 oz. per 45 gallon plant
 The inoculant shall be a 'cocktail' that shall include at a minimum the following mycorrhizal:
 - Endomycorrhizal Fungus
 - Ectomycorrhizal Fungus
 - Fungic Acid
 - Trichoderma
 - Phosphate Solubilizing, Nitrogen Fixing and Growth Promoting Bacteria
 - Humic Acid Derived from Leonardite
 - Sea Kelp Extract (Ascophyllum nodosum)
 - Yucca Plant Extract (Yucca schottigera)
 - Water holding Polymer (Cross linked acrylamide and potassium acrylate)
 - Particle size: 0.8 mm to 2.0mm)
 - Percent soluble: less than 0.05%
 - Absorption rate: 300-400 times in distilled water.
 Mix product with back fill in the first 8-10 inches of planting hole adjacent to the root ball for larger plants, and the first 4-6 inches for smaller plants making sure that the product is in contact with the root ball. Do not put product on top or in bottom of hole. Contractor shall provide written specification of proposed mix. Diehard, 1-800-777-7645, or approved equal.

5. All costs associated with permitting, pollution protection, tree protection, landscape installation, ~~plant~~ ~~planting~~ existing landscape maintenance within the project limits and the 365 day establishment period shall be included in the lump sum price bid.

REVISIONS		DATE		DESCRIPTION	
DATE	BY	DATE	BY	DESCRIPTION	
5-18-09	JED			Revised Per Bid Question	

Landscape Architect of Record: PBSA Certification of No. 24		Susan L. Prell RLA #000107 725 S Woodlawn Blvd. Oakland, FL 32720 386-736-7275 www.pbsa.com	
DEPARTMENT OF TRANSPORTATION ROAD NO. SR 528		STATE OF FLORIDA COUNTY BREVARD FINANCIAL PROJECT ID 426406-1-52-01	
SR 528 BETWEEN SR. 3 AND BANANA RIVER DRIVE SUMMARY OF PAY ITEMS		SHEET NO. LD-2	