

**CR 314 Sharpes Ferry Bridge Replacement  
From M.P. 3.580 to M.P. 4.716  
in Marion County**

**Design/Build Contract**

**Financial Projects Number(s): 415256-1-52-01  
Federal Aid Project Number(s): SFT2-157-R  
Contract Number: E-5N67**

**Revisions to RFP  
Addendum No. 4**

1. Page no. 32, under Section V; Design and Construction Criteria; B. Geotechnical Services, add the following sub section sentences immediately after the "B. Geotechnical Services".

**Settlement prone areas**

*"The Design/Build Team shall establish soil improvement methods and establish construction sequences for roadways, walls, and bridges located within settlement prone areas to satisfy the following requirement:*

*Soil improvements and construction sequences to densify and strengthen weak settlement prone subsoil sufficiently to limit movement within the approach slab to no more than 2 inches during the design life of the bridge".*

2. Page no. 40, Section V; Sub-Section D; Design Analysis; 1. Drainage Analysis, the second paragraph shall be modified as follows:

*"The exact number of drainage basins, outfalls, and water management facilities (retention/detention areas, weirs, etc.) will be the Design/Build Firm's responsibility. The two (2) proposed stormwater ponds shall be constructed such that the flowline of the inflow mitered end sections (MES's) are located at the pond bottom elevation".*

3. Page No. 44, Section VI – Design and Construction Criteria, Subsection 2 – Criteria, Item M, should be replaced with the following:

*"A ten (10) foot horizontal opening shall be provided at each end span of the proposed bridge to allow for wildlife to cross. Both wildlife crossings shall be above the Normal High Water (NHW) elevation of 40.13 ft. NGVD as indicated in the permitted plans from the SJRWMD and Army Corps of Engineers".*

4. Page No. 17, under Section V; Project Provisions and Requirements for Work; sub-section D; Environmental Permits, install the paragraph below after the first paragraph labeled “1. Storm Water and Surface Water:”

*1a. Indigenous plantings and Warranty:*

*“Indigenous herbaceous plantings/ground-cover vegetation shall be installed in the areas in front of the retaining wall systems on both the north and south sides of the vehicle and pedestrian bridges (also known as the Marion County easements).. These plantings shall be suitable for the soil conditions encountered in these areas and shall not be the type of plantings that require any mowing. The plants used in these areas shall have a warranty of one year from the time the construction project is complete, and the specifications addressing the installation, watering, etc. shall be under the standard specification 580. The plantings must be coordinated with the District Permits Coordinator (Hannah Henandez at 386-943-5601) before any planting is to occur”.*

**Please respond upon receipt, and direct any questions to Geoffrey Garapic at (386) 943-5531, or at [geoffrey.garapic@dot.state.fl.us](mailto:geoffrey.garapic@dot.state.fl.us)**

Posted: October 15, 2010 11:15AM

**Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.**