Centennial FDOT 1915 ★ 2015

Florida Department of Transportation

RICK SCOTT
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

JIM BOXOLD
SECRETARY

June 9, 2015

ADDENDUM NO. 3

To: PROSPECTIVE BIDDERS

FINANCIAL PROJECT NUMBER: 238693-1-52-01
CONTRACT NUMBER: E5W78
COUNTY: Marion
DESCRIPTION: SR 35 (SE 58th Ave./Baseline Rd.) Improvements

CHANGE IN REQUEST FOR PROPOSAL

The Request for Proposal (RFP) has been modified, see attached Addendum No. 3 for details on the modifications.

The entire modified RFP dated June 8, 2015 with the added attachments will replace the previous RFP. This document will be labeled as E5W78UpdatedRFP in the Contract Proposal Processing (CPP) system.

Please go to the online ordering website, https://www3.dot.state.fl.us/ContractProposalProcessingOnlineOrdering/ to download the documentation titled E5W78Addendum2 and E5W78UpdatedRFP.

Please sign the Addendum in the space provided and email, mail or fax back verifying receipt. If you have any further questions please contact Jamie Carter at (386) 943-5525 or by email at jamie.carter@dot.state.fl.us. Fax to: (850) 412-8092.

Sincerely,

Roger Masten
District Contracts Administrator
District Five

Received by: _____

Company: _____

Date: _____

Addendum No. 3

SR 35 (SE 58th Avenue/Baseline Rd) Improvements from SE 96th Place to south of SR/CR 464
Financial Project Number: 238693-1-52-01
Contract Number: E-5W78

The Request for Proposal is amended to include the following:

1.) Page Numbering – the Number of Pages has increased from 42 to 43

2.) Reference Documents on Page iv
The following documents have been added to the listing of Reference Documents:

Eastern Indigo Snake Clearance Letter
Sand Skink Clearance Letter
SR 35 Median Opening at SE 68th Street Concept Plan

3.) Section VI, D. Roadway Plans on Page 30
The following paragraphs have been added to subsection 3. Pavement Design Package:

The minimum milling and resurfacing on all roadways within the project limits shall be 1.5" mill and 1.5" FC 12.5 PG 76-22 (PMA) paving.

For all sidestreets the minimum new construction/widening pavement design shall be OBG 06, 1" of Structural Course SP-C and 1.5" of FC 12.5 PG 76-22 (PMA).

The following sidestreets are not required to have a friction course: Larch Course, Larch Track, Dogwood Trail Drive, Dogwood Trail Place and paved turnouts to the water retention areas.

4.) Section VI, E. Geometric on Page 32
The following row in table E.1 has been revised to the following:

637+50	SE 68th Street	SB Directional with left turn ingress and egress; See Note 1 for additional requirements.	1	230

5.) Section VI, E. Geometric on Page 33

The following note has been added to table E.1:

Note 1: A directional median opening will be required at SE 68th Street that accommodates WB-62FL truck movements. This opening shall accommodate a southbound left turn directional ingress and a westbound left turn egress. No U-turns shall be allowed at this opening and a raised curbed triangular splitter island shall be used to delineate the southbound ingress and the westbound egress. The SR 35 Median Opening at SE 68th Street Concept Plan included as a reference document to the RFP provides an example layout for the directional median opening at SE 68th Street. The requirements for the SR 35 and 68th Street intersection detailed in Table E.1 and Note 1 of this RFP shall modify the requirements included in the SR 35 Access Management Report included as an attachment to this RFP.