1

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PPROJQTY 02/28/06

PROPOSAL: E5J15
FINPROJ : 41994137201 COUNTY/SECTION: COUNTY: BREVARD MANDIST: 05

0412 SUMMARY OF Asphalt Repair (Mechanical) PAY ITEMS

S P C ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41994137201 Non-Participating	41994137201 Participating	QUANTITY TOTAL
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	0.000	1.000	1.000
	0327- 70- 1	MILLING EXIST ASPH PAVT (1" AVG DEPTH)	SY	0.000	8434.000	8434.000
	0337- 7- 7	ASPH CONC FRICTION COURSE(INC BIT / RUBBER) (FC-9	TN	0.000	464.000	464.000
	0660- 2-102	LOOP ASSEMBLY (F&I) (TYPE B)	AS	0.000	3.000	3.000
	0660- 2-106	LOOP ASSEMBLY (F&I) (TYPE F)	AS	0.000	1.000	1.000

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PPROJQTY 02/28/06

PROPOSAL: E5J15
FINPROJ : 41994137201 COUNTY/SECTION: COUNTY: BREVARD MANDIST: 05

0532 SUMMARY OF Pavement Striping (Large Machine) PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41994137201 Non-Participating	41994137201 Participating	QUANTITY TOTAL
		0711- 33-	TRAFFIC STRIPE SKIP (THERMOPLASTIC) (WHITE)	LF	0.000	1070.000	1070.000
		0711- 34-	TRAFFIC STRIPE SKIP (THERMOPLASTIC) (YELLOW)	LF	0.000	270.000	270.000
		0711- 35- 61	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (6")	LF	0.000	3179.000	3179.000
		0711- 36- 61	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(6")	LF	0.000	1902.000	1902.000

PPROJQTY 02/28/06

PROPOSAL: E5J15
FINPROJ : 41994137201 COUNTY/SECTION: COUNTY: BREVARD MANDIST: 05

0534 SUMMARY OF Pavement Symbols PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41994137201 Non-Participating	41994137201 Participating	QUANTITY TOTAL
		0711- 4-	DIRECTIONAL ARROWS THERMOPLASTIC	EA	0.000	6.000	6.000
		0711- 35-121	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (12")	LF	0.000	235.000	235.000
		0711- 35-241	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (24")	LF	0.000	36.000	36.000

PPROJQTY 02/28/06

PROPOSAL: E5J15
FINPROJ : 41994137201 COUNTY/SECTION: COUNTY: BREVARD MANDIST: 05

0537 SUMMARY OF RAISED PAVEMENT MARKER PLACEMENT PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41994137201 Non-Participating	41994137201 Participating	QUANTITY TOTAL
		0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	0.000	115.000	115.000

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PPROJQTY 03/02/06

PROPOSAL: E5H69
FINPROJ : 41578417201 COUNTY/SECTION: COUNTY: LAKE MANDIST: 05

0412 SUMMARY OF Asphalt Repair (Mechanical) PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41578417201 Non-Participating	41578417201 Participating	QUANTITY TOTAL
		0102- 1-	MAINTENANCE OF TRAFFIC	LS	0.000	1.000	1.000
		0327- 70- 6	MILLING EXIST ASPH PAVT (1 1/2" AVG DEPTH)	SY	0.000	3813.330	3813.330
		0337- 7- 6	ASPH CONC FRICTION COURSE(INC BIT/RUBBER)FC 12.5(	TN	0.000	305.070	305.070

PPROJQTY 03/02/06

PROPOSAL: E5H69
FINPROJ : 41578417201 COUNTY/SECTION: COUNTY: LAKE MANDIST: 05

0532 SUMMARY OF Pavement Striping (Large Machine) PAY ITEMS

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41578417201 Non-Participating	41578417201 Participating	QUANTITY TOTAL
	0710- 25- 61	TRAFFIC STRIPE SOLID (WHITE/BLACK) (6")	LF	0.000	2693.000	2693.000
	0710- 26- 61	TRAFFIC STRIPE SOLID (YELLOW) (6")	LF	0.000	4467.000	4467.000
	0710- 27-	TRAFFIC STRIPE SKIP (WHITE/BLACK)	LF	0.000	40.000	40.000
	0710- 28-	TRAFFIC STRIPE SKIP (YELLOW)	LF	0.000	50.000	50.000

PPROJQTY 03/02/06

PROPOSAL: E5H69
FINPROJ : 41578417201 COUNTY/SECTION: COUNTY: LAKE MANDIST: 05

0537 SUMMARY OF RAISED PAVEMENT MARKER PLACEMENT PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41578417201 Non-Participating	41578417201 Participating	QUANTITY TOTAL
		0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	0.000	129.000	129.000

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PPROJQTY 03/23/06

PROPOSAL: E5J19
FINPROJ : 41380915202 COUNTY/SECTION: COUNTY: LAKE MANDIST: 05
SUMTER
STATEWIDE

0200 SUMMARY OF Pavement Striping PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41380915202 Non-Participating	41380915202 Participating	QUANTITY TOTAL
		0711- 3-	PAVT MESSAGES THERMOPLASTIC	EA	0.000	62.000	62.000
		0711- 4-	DIRECTIONAL ARROWS THERMOPLASTIC	EA	0.000	583.000	583.000
		0711- 5- 1	GUIDE LINES (THERMOPLASTIC) (WHITE)	LF	0.000	2579.000	2579.000
		0711- 5- 2	GUIDE LINES (THERMOPLASTIC) (YELLOW)	LF	0.000	100.000	100.000
		0711- 31-	TRAFFIC STRIPE SKIP (THERMOPLASTIC)(WHITE)	GM	0.000	42.110	42.110
		0711- 32-	TRAFFIC STRIPE SKIP (THERMOPLASTIC)(YELLOW)	GM	0.000	2.783	2.783
		0711- 35-121	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (12")	LF	0.000	10796.000	10796.000
		0711- 35-181	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (18")	LF	0.000	2082.000	2082.000
		0711- 35-241	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (24")	LF	0.000	2611.000	2611.000
		0711- 36-181	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(18")	LF	0.000	894.000	894.000
		0711- 37- 61	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (6")	NM	0.000	37.209	37.209
		0711- 37- 81	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (8")	NM	0.000	1.270	1.270
		0711- 38- 61	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(6")	NM	0.000	27.076	27.076
		0711- 38- 81	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(8")	NM	0.000	0.237	0.237

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PPROJQTY 03/23/06

PROPOSAL: E5J19
FINPROJ : 41578317202 COUNTY/SECTION: COUNTY: LAKE MANDIST: 05

0532 SUMMARY OF Pavement Striping Large Machine PAY ITEMS

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41578317202 Non-Participating	41578317202 Participating	QUANTITY TOTAL
	0711- 37- 81	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (8")	NM	0.000	1.332	1.332
	0711- 38- 81	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(8")	NM	0.000	0.132	0.132
	E711- 31- 1	HOT SPRAY BINDER, SKIP STRIPE (WHITE)	GM	0.000	0.500	0.500
	E711- 32- 1	HOT SPRAY BINDER, SKIP STRIPE (YELLOW)	GM	0.000	2.486	2.486
	E711- 37- 6	HOT SPRAY BINDER, SOLID, 6" STRIPE (WHITE)	NM	0.000	14.060	14.060
	E711- 38- 6	HOT SPRAY BINDER, SOLID, 6" STRIPE (YELLOW)	NM	0.000	11.780	11.780

PROPOSAL: E5J19
FINPROJ : 41578317202 COUNTY/SECTION: COUNTY: LAKE MANDIST: 05

0534 SUMMARY OF Pavement Symbols

S P C ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	PAY ITEMS 41578317202 Non-Participating	41578317202 Participating	QUANTITY TOTAL
	0710- 11-	MARKINGS (PAINT) REMOVAL	SF	0.000	100.000	100.000
	0711- 3-	PAVT MESSAGES THERMOPLASTIC	EA	0.000	41.000	41.000
	0711- 4-	DIRECTIONAL ARROWS THERMOPLASTIC	EA	0.000	775.000	775.000
	0711- 5- 1	GUIDE LINES (THERMOPLASTIC) (WHITE)	LF	0.000	34.000	34.000
	0711- 5- 2	GUIDE LINES (THERMOPLASTIC) (YELLOW)	LF	0.000	10.000	10.000
	0711- 7-	PAVT MARKING REMOVE THERMOPLASTIC	SF	0.000	1710.000	1710.000
	0711- 35-121	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (12")	LF	0.000	6657.000	6657.000
	0711- 35-181	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (18")	LF	0.000	3031.000	3031.000
	0711- 35-241	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (24")	LF	0.000	2313.000	2313.000
	0711- 36-181	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(18")	LF	0.000	6018.000	6018.000

PPROJQTY 03/23/06

PROPOSAL: E5J19
FINPROJ : 41578317202 COUNTY/SECTION: COUNTY: LAKE MANDIST: 05

0537 SUMMARY OF RPM's

PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41578317202 Non-Participating	41578317202 Participating	QUANTITY TOTAL
		E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REM AND REPL)(CLASS B)	EA	0.000	23376.000	23376.000

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PPROJQTY 02/28/06

PROPOSAL: E5J23
FINPROJ : 42010927201 COUNTY/SECTION: COUNTY: ORANGE MANDIST: 05

0425 SUMMARY OF CONCRETE SLAB REPLACEMENT PAY ITEMS

S P C ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	42010927201 Non-Participating	42010927201 Participating	QUANTITY TOTAL
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	0.000	1.000	1.000
	0353- 70-	CONC PAVT SLAB REPLACEMENT	CY	0.000	607.430	607.430
	0425- 5-	MANHOLE (ADJUST)	EA	0.000	3.000	3.000
	0660- 2-102	LOOP ASSEMBLY (F&I) (TYPE B)	AS	0.000	3.000	3.000
	0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	0.000	39.000	39.000
	0710- 25- 61	TRAFFIC STRIPE SOLID (WHITE/BLACK) (6")	LF	0.000	138.000	138.000
	0710- 26- 61	TRAFFIC STRIPE SOLID (YELLOW) (6")	LF	0.000	1320.000	1320.000
	0710- 27-	TRAFFIC STRIPE SKIP (WHITE/BLACK)	LF	0.000	1290.000	1290.000
	E425- 73- 7	MANHOLE FRAME & COVER	EA	0.000	3.000	3.000

1

PPROJQTY 03/14/06

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PROPOSAL: E5J30
FINPROJ : 42030627201 COUNTY/SECTION: COUNTY: OSCEOLA MANDIST: 05

0433 SUMMARY OF Sodding

PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	42030627201 Non-Participating	42030627201 Participating	QUANTITY TOTAL
		0570- 5-	FERTILIZER	TN	0.000	1.260	1.260
		0570- 9-	WATER FOR GRASS	MG	0.000	1158.300	1158.300

PROPOSAL: E5J30
FINPROJ : 42030627201 COUNTY/SECTION: COUNTY: OSCEOLA MANDIST: 05

0436 SUMMARY OF Rework Non Paved Shoulders PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	42030627201 Non-Participating	42030627201 Participating	QUANTITY TOTAL
		0575- 1- 1	SODDING (BAHIA)	SY	0.000	45873.450	45873.450
		0577- 70-	SHOULDER REWORK	SY	0.000	21825.670	21825.670

PROPOSAL: E5J30
FINPROJ : 42030627201 COUNTY/SECTION: COUNTY: OSCEOLA MANDIST: 05

0451 SUMMARY OF Pipe Desilting PAY ITEMS

S
P
C

ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	42030627201 Non-Participating	42030627201 Participating	QUANTITY TOTAL
	0430-944- 23	PIPE DESILTING (15" SD)	LF	0.000	140.000	140.000
	0430-944- 25	PIPE DESILTING (18" SD)	LF	0.000	4587.000	4587.000
	0430-944- 29	PIPE DESILTING (24" SD)	LF	0.000	3452.000	3452.000
	0430-944- 33	PIPE DESILTING (30" SD)	LF	0.000	1907.000	1907.000
	0430-944- 38	PIPE DESILTING (36" SD)	LF	0.000	610.000	610.000
	0430-944- 40	PIPE DESILTING (42" SD)	LF	0.000	138.000	138.000

PPROJQTY 03/14/06

PROPOSAL: E5J30
FINPROJ : 42030627201 COUNTY/SECTION: COUNTY: OSCEOLA MANDIST: 05

0461 SUMMARY OF Clean and Reshape Ditches PAY ITEMS

S
P
C

ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	42030627201 Non-Participating	42030627201 Participating	QUANTITY TOTAL
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	0.000	1.000	1.000
	0104- 10- 1	HAY OR STRAW BALE (18" X 18" X 36")	EA	0.000	297.000	297.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	0.000	43286.000	43286.000

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PPROJQTY 02/28/06

PROPOSAL: E5J40
FINPROJ : 42010987201 COUNTY/SECTION: COUNTY: ORANGE SEMINOLE MANDIST: 05

0532 SUMMARY OF Pavement Striping - Large Machine PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	42010987201 Non-Participating	42010987201 Participating	QUANTITY TOTAL
		0711- 37- 61	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (6")	NM	0.000	10.518	10.518
		0711- 38- 61	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(6")	NM	0.000	3.090	3.090
		E711- 31- 1	HOT SPRAY BINDER, SKIP STRIPE (WHITE)	GM	0.000	38.199	38.199
		E711- 32- 1	HOT SPRAY BINDER, SKIP STRIPE (YELLOW)	GM	0.000	7.350	7.350
		E711- 37- 6	HOT SPRAY BINDER, SOLID, 6" STRIPE (WHITE)	NM	0.000	42.910	42.910
		E711- 38- 6	HOT SPRAY BINDER, SOLID, 6" STRIPE (YELLOW)	NM	0.000	33.182	33.182

PPROJQTY 02/28/06

PROPOSAL: E5J40
FINPROJ : 42010987201 COUNTY/SECTION: COUNTY: ORANGE SEMINOLE MANDIST: 05

0534 SUMMARY OF Pavement Symbols

S P C

ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	PAY ITEMS 42010987201 Non-Participating	42010987201 Participating	QUANTITY TOTAL
	0711- 3-	PAVT MESSAGES THERMOPLASTIC	EA	0.000	63.000	63.000
	0711- 4-	DIRECTIONAL ARROWS THERMOPLASTIC	EA	0.000	883.000	883.000
	0711- 5- 1	GUIDE LINES (THERMOPLASTIC) (WHITE)	LF	0.000	3100.000	3100.000
	0711- 7-	PAVT MARKING REMOVE THERMOPLASTIC	SF	0.000	53486.000	53486.000
	0711- 33-	TRAFFIC STRIPE SKIP (THERMOPLASTIC) (WHITE)	LF	0.000	601.000	601.000
	0711- 35- 61	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (6")	LF	0.000	11687.000	11687.000
	0711- 35- 81	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (8")	LF	0.000	5316.500	5316.500
	0711- 35-121	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (12")	LF	0.000	20359.000	20359.000
	0711- 35-181	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (18")	LF	0.000	2865.000	2865.000
	0711- 35-241	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (24")	LF	0.000	5354.000	5354.000
	0711- 36- 61	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(6")	LF	0.000	11311.000	11311.000
	0711- 36- 81	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(8")	LF	0.000	241.000	241.000
	0711- 36-181	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(18")	LF	0.000	1709.000	1709.000

PPROJQTY 02/28/06

PROPOSAL: E5J40
FINPROJ : 42010987201 COUNTY/SECTION: COUNTY: ORANGE SEMINOLE MANDIST: 05

0537 SUMMARY OF Raised Pavement Marker Replacement ; RPM's PAY ITEMS

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	42010987201 Non-Participating	42010987201 Participating	QUANTITY TOTAL
	0704- 1- 13	MARKER PAVEMENT CERAMIC (F&I) (CLASS C)	EA	0.000	1654.000	1654.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REM AND REPL) (CLASS B)	EA	0.000	43462.000	43462.000

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PPROJQTY 03/02/06

PROPOSAL: E5J43
FINPROJ : 24384457201 COUNTY/SECTION: COUNTY: VOLUSIA MANDIST: 05
STATEWIDE

0498 SUMMARY OF Storm Water Management PAY ITEMS

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	24384457201 Non-Participating	24384457201 Participating	QUANTITY TOTAL
		0101- 1-	MOBILIZATION	LS	0.000	1.000	1.000
		0102- 1-	MAINTENANCE OF TRAFFIC	LS	0.000	1.000	1.000
		0104- 10- 1	HAY OR STRAW BALE (18" X 18" X 36")	EA	0.000	60.000	60.000
		0104- 13- 1	SILT FENCE STAKED (TYPE III)	LF	0.000	2000.000	2000.000
		0110- 1- 1	CLEARING & GRUBBING	LS	0.000	1.000	1.000
		0430-171-125	PIPE CULV(OPT MATL)(ROUND)(18"SS)	LF	0.000	24.000	24.000
		0430-982-125	MITERED END SECTION (OPTIONAL ROUND) (18" CD)	EA	0.000	2.000	2.000
		0448- 73-	PUMPING STATION	LS	0.000	1.000	1.000
		0555- 1- 2	DIRECTIONAL BORE (6" TO < 12")	LF	0.000	8027.000	8027.000
T		0750- 71-	ELECTRICAL WORK	LS	0.000	1.000	1.000
		0999- 25-	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	LS	0.000	1.000	1.000

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PPROJQTY 03/09/06

PROPOSAL: E5J44
FINPROJ : 41743717201 COUNTY/SECTION: COUNTY: MARION MANDIST: 05

0412 SUMMARY OF Asphalt Repair (Mechanical) PAY ITEMS

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41743717201 Non-Participating	41743717201 Participating	QUANTITY TOTAL
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	0.000	1.000	1.000
	0327- 70- 6	MILLING EXIST ASPH PAVT (1 1/2" AVG DEPTH)	SY	0.000	8396.220	8396.220
	0327- 70- 19	MILLING EXIST ASPH PAVT (3/4" AVG DEPTH)	SY	0.000	3526.670	3526.670
	0337- 7- 5	ASPH CONC FRICTION COURSE(INC BIT/RUBBER) (FC-5)	TN	0.000	141.070	141.070
	0337- 7- 6	ASPH CONC FRICTION COURSE(INC BIT/RUBBER)FC 12.5(	TN	0.000	671.700	671.700
	0660- 2-102	LOOP ASSEMBLY (F&I) (TYPE B)	AS	0.000	2.000	2.000
	0660- 2-106	LOOP ASSEMBLY (F&I) (TYPE F)	AS	0.000	1.000	1.000

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PROPOSAL: E5J44
FINPROJ : 41743717201 COUNTY/SECTION: COUNTY: MARION MANDIST: 05

0532 SUMMARY OF Pavement Striping (Large Machine) PAY ITEMS

S P C ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41743717201 Non-Participating	41743717201 Participating	QUANTITY TOTAL
	0710- 21-	TRAFFIC STRIPE SKIP (WHITE/BLACK)	GM	0.000	0.430	0.430
	0710- 22-	TRAFFIC STRIPE SKIP (YELLOW)	GM	0.000	0.490	0.490
	0710- 23- 61	TRAFFIC STRIPE SOLID (WHITE/BLACK/BLUE) (6")	NM	0.000	1.370	1.370
	0710- 24- 61	TRAFFIC STRIPE SOLID (YELLOW) (6")	NM	0.000	1.810	1.810

PPROJQTY 03/09/06

PROPOSAL: E5J44
FINPROJ : 41743717201 COUNTY/SECTION: COUNTY: MARION MANDIST: 05

0534 SUMMARY OF Pavement Symbols

PAY ITEMS

S P C ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41743717201 Non-Participating	41743717201 Participating	QUANTITY TOTAL
	0710- 25- 81	TRAFFIC STRIPE SOLID (WHITE/BLACK) (8")	LF	0.000	17.000	17.000
	0710- 25-241	TRAFFIC STRIPE SOLID (WHITE/BLACK) (24")	LF	0.000	14.000	14.000

PPROJQTY 03/09/06

PROPOSAL: E5J44
FINPROJ : 41743717201 COUNTY/SECTION: COUNTY: MARION MANDIST: 05

0537 SUMMARY OF RAISED PAVEMENT MARKER PLACEMENT PAY ITEMS

S P C

ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41743717201 Non-Participating	41743717201 Participating	QUANTITY TOTAL
	0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	0.000	397.000	397.000

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PPROJQTY 03/13/06

PROPOSAL: E5K67
FINPROJ : 24102015201 COUNTY/SECTION: 79040000 COUNTY: VOLUSIA MANDIST: 05

0200 SUMMARY OF ROADWAY PAY ITEMS

S P C ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	24102015201 Non-Participating	24102015201 Participating	QUANTITY TOTAL
	0101- 1-	MOBILIZATION	LS	0.000	1.000	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	0.000	1.000	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	MH	0.000	16.000	16.000
	0102- 60-	WORK ZONE SIGNS	ED	0.000	5046.000	5046.000
	0102- 74- 1	BARRICADE (TEMPORARY)(TYPES I,II,DI,VP & DRUM)	ED	0.000	8910.000	8910.000
	0102- 74- 2	BARRICADE (TEMPORARY)(TYPE III) (6')	ED	0.000	658.000	658.000
	0102- 76-	PANELS ARROW ADVANCE WARNING	ED	0.000	174.000	174.000
	0102- 77-	HIGH INTENSITY FLASHING LIGHTS (TEMP - TYPE B)	ED	0.000	1740.000	1740.000
	0102- 78-	MARKER PAVT REFLECTIVE (TEMPORARY)	EA	0.000	24.000	24.000
	0102- 99-	CHANGEABLE-VARIABLE MESSAGE SIGN (TEMPORARY)	ED	0.000	604.000	604.000
	0102-107-	TEMPORARY TRAF DETECTION(INTERSECT)	DA	0.000	73.000	73.000
	0104- 4-	MOWING	AC	0.000	1.000	1.000
	0104- 10- 1	HAY OR STRAW BALE (18" X 18" X 36")	EA	0.000	20.000	20.000
	0104- 13- 1	SILT FENCE STAKED (TYPE III)	LF	0.000	407.000	407.000
	0104- 16-	ROCK BAGS	EA	0.000	140.000	140.000
	0110- 1- 1	CLEARING & GRUBBING	LS	0.000	1.000	1.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY)	LS	0.000	1.000	1.000
	0285-711-	BASE OPTIONAL (BASE GROUP 11)	SY	0.000	365.000	365.000
	0327- 70- 4	MILLING EXIST ASPH PAVT (3" AVG DEPTH)	SY	0.000	199.000	199.000
	0327- 70- 6	MILLING EXIST ASPH PAVT (1 1/2" AVG DEPTH)	SY	0.000	7865.000	7865.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC (TRAFFIC C)	TN	0.000	75.900	75.900
	0337- 7- 6	ASPH CONC FRICTION COURSE(INC BIT/RUBBER)FC 12.5(	TN	0.000	674.400	674.400
	0400- 1- 15	CONC CLASS I(MISCELLANEOUS)	CY	0.000	6.000	6.000
	0425- 1-315	INLETS (CURB) (TYPE P-1) (PARTIAL)	EA	0.000	1.000	1.000
	0425- 5-	MANHOLE (ADJUST)	EA	0.000	1.000	1.000
	0520- 1- 7	CURB & GUTTER CONC (TYPE E)	LF	0.000	363.000	363.000
	0520- 1- 10	CURB & GUTTER CONC (TYPE F)	LF	0.000	284.000	284.000
	0520- 5- 11	TRAF SEP CONC (TYPE I) (4' WIDE)	LF	0.000	334.000	334.000
	0522- 1-	SIDEWALK CONC (4" THICK)	SY	0.000	369.000	369.000
	0575- 1-	SODDING	SY	0.000	266.000	266.000
	0710- 6-	DIRECTIONAL ARROWS, PAINTED	EA	0.000	20.000	20.000
	0710- 23- 61	TRAFFIC STRIPE SOLID (WHITE/BLACK/BLUE)(6")	NM	0.000	1.272	1.272
	0710- 25- 81	TRAFFIC STRIPE SOLID (WHITE/BLACK) (8")	LF	0.000	706.000	706.000
	0710- 25-121	TRAFFIC STRIPE SOLID (WHITE/BLACK) (12")	LF	0.000	1230.000	1230.000
	0710- 25-181	TRAFFIC STRIPE SOLID (WHITE/BLACK) (18")	LF	0.000	228.000	228.000
	0710- 25-241	TRAFFIC STRIPE SOLID (WHITE/BLACK) (24")	LF	0.000	184.000	184.000
	0710- 26- 61	TRAFFIC STRIPE SOLID (YELLOW) (6")	LF	0.000	2828.000	2828.000
	0710- 26- 81	TRAFFIC STRIPE SOLID (YELLOW) (8")	LF	0.000	273.000	273.000
	0710- 26-181	TRAFFIC STRIPE SOLID (YELLOW) (18")	LF	0.000	212.000	212.000
	0710- 27-	TRAFFIC STRIPE SKIP (WHITE/BLACK)	LF	0.000	952.000	952.000
	0711- 7-	PAVT MARKING REMOVE THERMOPLASTIC	SF	0.000	329.000	329.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	LS	0.000	1.000	1.000

PROPOSAL: E5K67
FINPROJ : 24102015201 COUNTY/SECTION: 79040000 COUNTY: VOLUSIA MANDIST: 05

0300 SUMMARY OF SIGNING

PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	24102015201 Non-Participating	24102015201 Participating	QUANTITY TOTAL
		0700- 40- 1	SIGN SINGLE POST (LESS THAN 12)	AS	0.000	6.000	6.000
		0700- 46- 11	SIGN EXISTING (REMOVAL) (SINGLE POST)	AS	0.000	2.000	2.000
		0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	0.000	289.000	289.000
		0710- 29-	REFLECTIVE PAINT (ISLAND NOSE) (WHITE)	SY	0.000	6.000	6.000
		0710- 30-	REFLECTIVE PAINT (ISLAND NOSE) (YELLOW)	SY	0.000	5.000	5.000
		0711- 4-	DIRECTIONAL ARROWS THERMOPLASTIC	EA	0.000	20.000	20.000
		0711- 5- 1	GUIDE LINES (THERMOPLASTIC) (WHITE)	LF	0.000	94.000	94.000
		0711- 33-	TRAFFIC STRIPE SKIP (THERMOPLASTIC) (WHITE)	LF	0.000	558.000	558.000
		0711- 35- 61	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (6")	LF	0.000	3359.000	3359.000
		0711- 35- 81	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (8")	LF	0.000	706.000	706.000
		0711- 35-121	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (12")	LF	0.000	1230.000	1230.000
		0711- 35-181	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (18")	LF	0.000	228.000	228.000
		0711- 35-241	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (24")	LF	0.000	184.000	184.000
		0711- 36- 61	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(6")	LF	0.000	1414.000	1414.000
		0711- 36- 81	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(8")	LF	0.000	273.000	273.000
		0711- 36-181	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(18")	LF	0.000	212.000	212.000

PROPOSAL: E5K67
FINPROJ : 24102015201 COUNTY/SECTION: 79040000 COUNTY: VOLUSIA MANDIST: 05

0500 SUMMARY OF SIGNALIZATION PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	24102015201 Non-Participating	24102015201 Participating	QUANTITY TOTAL
		0630- 1- 12	CONDUIT (FURNISH & INSTALL)(UNDERGROUND)	LF	0.000	1488.000	1488.000
		0630- 1- 14	CONDUIT (FURNISH & INSTALL)(UNDERGROUND - JACKED)	LF	0.000	486.000	486.000
		0632- 7- 1	CABLE (SIGNAL) (FURNISH & INSTALL)	PI	0.000	1.000	1.000
		0635- 1- 11	PULL & JUNCTION BOXES (F&I) (PULL BOX)	EA	0.000	23.000	23.000
		0639- 1- 22	ELECTRICAL POWER SERVICE (UNDERGROUND)	AS	0.000	1.000	1.000
		0639- 2- 1	ELECTRICAL SERVICE WIRE	LF	0.000	171.000	171.000
		0649-415-003	M/ARM (F&I/HL)(SGL ARM W/O LUM)1ST ARM(B5)	EA	0.000	2.000	2.000
		0649-416-004	M/ARM (F&I/HL)(SGL ARM W/O LUM)(1ST ARM(B6)2ND(0)	EA	0.000	1.000	1.000
		0649-417-006	M/ARM (F&I/HL)(SGL ARM W/O LUM)1ST ARM(B7)	EA	0.000	1.000	1.000
		0650- 51-311	SIGNAL TRAFFIC(F&I)(3 SECT 1 WAY)(STD)	AS	0.000	14.000	14.000
		0653-181-	SIGNAL PEDESTRIAN (F&I) (LED) (1 DIRECTION)	AS	0.000	4.000	4.000
		0653-182-	SIGNAL PEDESTRIAN (F&I) (LED) (2 DIRECTIONS)	AS	0.000	2.000	2.000
		0659-107-	SIGNAL HEAD AUXILIARIES (ALUMINUM PEDESTAL)	EA	0.000	6.000	6.000
		0659-109-	SIGNAL HEAD AUXILIARIES (CONC PEDESTAL TYPE II)	EA	0.000	1.000	1.000
		0660- 1-105	LOOP DETECTOR INDUCTIVE (F&I) (TYPE 5)	EA	0.000	10.000	10.000
		0660- 1-108	LOOP DETECTOR INDUCTIVE (F&I) (TYPE 8)	EA	0.000	8.000	8.000
		0660- 2-102	LOOP ASSEMBLY (F&I) (TYPE B)	AS	0.000	10.000	10.000
		0660- 2-106	LOOP ASSEMBLY (F&I) (TYPE F)	AS	0.000	10.000	10.000
		0665- 11-	DETECTOR PEDEST(F&I)(DET STA POLE OR CABINET MTD)	EA	0.000	8.000	8.000
		0670- 5-112	CNTL ASSEM ACT SS F&I NEMA PRE(TWO)	AS	0.000	1.000	1.000
		0690- 10-	SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	EA	0.000	8.000	8.000
		0690- 20-	SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	EA	0.000	8.000	8.000
		0690- 31-	SIGNAL PEDESTAL REMOVAL	EA	0.000	2.000	2.000
		0690- 32- 1	POLE REMOVAL(SHALLOW/DIRECT BURIAL)	EA	0.000	2.000	2.000
		0690- 50- 1	CNTRL ASSEM REMOVE (CAB ASSM LESS FOUNDATION)	EA	0.000	1.000	1.000
		0690- 80-	SPAN WIRE ASSEMBLY REMOVE	EA	0.000	1.000	1.000
		0690- 90-	CONDUIT & CABLING REMOVE	PI	0.000	1.000	1.000
		0690-100-	SIGNAL EQUIPMENT MISCELLANOUS REMOVE	PI	0.000	1.000	1.000
		0699- 1- 1	SIGN, INTERNAL ILLUM(ST NAME)	EA	0.000	4.000	4.000
		0700- 46- 15	SIGN EXISTING (REMOVAL) (SPAN WIRE)	AS	0.000	2.000	2.000

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PPROJQTY 03/14/06

PROPOSAL: E5K68
FINPROJ : 41357615201 COUNTY/SECTION: COUNTY: BREVARD MANDIST: 05

0200 SUMMARY OF ROADWAY PAY ITEMS

S P C ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41357615201 Non-Participating	41357615201 Participating	QUANTITY TOTAL
	0999- 2-	LUMP SUM CONTRACT, ALTERNATIVE BIDDING	LS	0.000	1.000	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT (DO NOT BID)	LS	0.000	1.000	1.000

FLORIDA DEPARTMENT OF TRANSPORTATION
FINANCIAL PROJECT SUMMARY OF PAY ITEMS

PPROJQTY 03/20/06

PROPOSAL: E5K69
FINPROJ : 23800225234 COUNTY/SECTION: COUNTY: STATEWIDE MANDIST: 05

0500 SUMMARY OF SIGNALIZATION — PAY ITEMS

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	23800225234 Non-Participating	23800225234 Participating	QUANTITY TOTAL
		0102- 14-	TRAFFIC CONTROL OFFICER	MH	0.000	48.000	48.000
		0102- 60-	WORK ZONE SIGNS	ED	0.000	2421.000	2421.000
		0102- 71- 11	BARRIER WALL (TEMPORARY) (F&I)(CONCRETE)	LF	0.000	300.000	300.000
		0102- 74- 1	BARRICADE (TEMPORARY)(TYPES I,II,DI,VP & DRUM)	ED	0.000	2412.000	2412.000
		0102- 76-	PANELS ARROW ADVANCE WARNING	ED	0.000	37.000	37.000
		0102- 77-	HIGH INTENSITY FLASHING LIGHTS (TEMP - TYPE B)	ED	0.000	1447.000	1447.000
		0102- 79-	LIGHTS(TEMP-BARR. WALL MOUNT)(TYPE C STEADY BURN)	ED	0.000	6.000	6.000
		0102- 99-	CHANGEABLE-VARIABLE MESSAGE SIGN (TEMPORARY)	ED	0.000	81.000	81.000
		0110- 4-	PAVEMENT REMOVAL OF EXISTING CONCRETE	SY	0.000	385.000	385.000
		0120- 1-	EXCAVATION REGULAR	CY	0.000	184.000	184.000
		0120- 2- 2	EXCAVATION BORROW (TRUCK MEASURE)	CY	0.000	158.000	158.000
		0285-709-	BASE OPTIONAL (BASE GROUP 09)	SY	0.000	700.000	700.000
		0327- 70- 1	MILLING EXIST ASPH PAVT (1" AVG DEPTH)	SY	0.000	900.000	900.000
		0327- 70- 4	MILLING EXIST ASPH PAVT (3" AVG DEPTH)	SY	0.000	900.000	900.000
		0334- 1- 13	SUPERPAVE ASPHALTIC CONC (TRAFFIC C)	TN	0.000	125.000	125.000
		0337- 7- 5	ASPH CONC FRICTION COURSE(INC BIT/RUBBER) (FC-5)	TN	0.000	10.000	10.000
		0337- 7- 7	ASPH CONC FRICTION COURSE(INC BIT / RUBBER) (FC-9	TN	0.000	20.000	20.000
		0430-174-125	PIPE CULV(OPT MATL)(ROUND)(18"SD)	LF	0.000	24.000	24.000
		0430-174-129	PIPE CULV(OPT MATL)(ROUND)(24"SD)	LF	0.000	24.000	24.000
		0430-174-133	PIPE CULV(OPT MATL)(ROUND)(30"SD)	LF	0.000	16.000	16.000
		0430-984-125	MITERED END SECTION (OPTIONAL ROUND) (18" SD)	EA	0.000	2.000	2.000
		0430-984-129	MITERED END SECTION (OPTIONAL ROUND) (24" SD)	EA	0.000	2.000	2.000
		0430-984-133	MITERED END SECTION (OPTIONAL ROUND) (30" SD)	EA	0.000	1.000	1.000
		0515- 1- 2	PIPE HANDRAIL (ALUMINUM)	LF	0.000	100.000	100.000
		0520- 1- 10	CURB & GUTTER CONC (TYPE F)	LF	0.000	800.000	800.000
		0520- 2- 1	CURB CONC (TYPE A)	LF	0.000	300.000	300.000
		0522- 1-	SIDEWALK CONC (4" THICK)	SY	0.000	100.000	100.000
		0522- 2-	SIDEWALK CONC (6" THICK)	SY	0.000	400.000	400.000
		0575- 1-	SODDING	SY	0.000	800.000	800.000
		0630- 1- 11	CONDUIT (FURNISH & INSTALL)(ABOVEGROUND)	LF	0.000	140.000	140.000
		0630- 1- 12	CONDUIT (FURNISH & INSTALL)(UNDERGROUND)	LF	0.000	4000.000	4000.000
		0630- 1- 13	CONDUIT (FURNISH & INSTALL)(UNDER PAVEMENT)	LF	0.000	116.000	116.000
		0630- 1- 14	CONDUIT (FURNISH & INSTALL)(UNDERGROUND - JACKED)	LF	0.000	1000.000	1000.000
		0632- 6- 1	CABLE (SIGNAL) (FURNISH & INSTALL)	LF	0.000	3790.000	3790.000
		0632- 8-111	CABLE (INTERCONNECT)(F&I) (AERIAL)	LF	0.000	1000.000	1000.000
		0632- 8-112	CABLE (INTERCONNECT)(F&I) (UNDER-GRND)	LF	0.000	1000.000	1000.000
		0634- 5- 1	FIBERGLASS INSULATOR (FURNISH & INSTALL)	LF	0.000	50.000	50.000
T		0634- 6- 1	MESSENGER WIRE (FURNISH & INSTALL)	LF	0.000	2000.000	2000.000
		0635- 1- 11	PULL & JUNCTION BOXES (F&I) (PULL BOX)	EA	0.000	60.000	60.000
		0635- 1- 12	PULL & JUNCTION BOXES (F&I) (AERIAL JUNCT BOX)	EA	0.000	1.000	1.000
T		0635- 1- 15	PULL & JUNCTION BOXES (F&I) (FIBER OPTICS)	EA	0.000	4.000	4.000
T		0635- 1- 16	PULL & JUNCTION BOXES(F&I)(SPECIAL)	EA	0.000	2.000	2.000
		0639- 1- 12	ELECTRICAL POWER SERVICE (OVERHEAD)	AS	0.000	4.000	4.000
		0639- 1- 22	ELECTRICAL POWER SERVICE (UNDERGROUND)	AS	0.000	1.000	1.000
		0639- 1- 23	ELECTRICAL POWER SERVICE (UNDERGROUND)	AS	0.000	1.000	1.000
		0639- 2- 1	ELECTRICAL SERVICE WIRE	LF	0.000	200.000	200.000

PROPOSAL: E5K69
FINPROJ : 23800225234 COUNTY/SECTION: COUNTY: STATEWIDE MANDIST: 05

0500 SUMMARY OF SIGNALIZATION — PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	23800225234 Non-Participating	23800225234 Participating	QUANTITY TOTAL
		0641- 1-	STRAIN POLES GUYING(CONCRETE)	EA	0.000	1.000	1.000
		0641- 11-130	PREST CONC POLE (F&I)(30' TYPE N-II)(SVC POLE)	EA	0.000	1.000	1.000
		0641- 13-134	PREST CONC POLE (F&I)(34' TYPE N-IV)	EA	0.000	1.000	1.000
		0641- 14-142	PREST CONC POLE (F&I)(42' TYPE N-V)	EA	0.000	1.000	1.000
		0641- 14-146	PREST CONC POLE (F&I)(46' TYPE N-V)	EA	0.000	1.000	1.000
		0641- 14-148	PREST CONC POLE (F&I)(48' TYPE N-V)	EA	0.000	1.000	1.000
		0641- 14-150	PREST CONC POLE (F&I)(50' TYPE N-V)	EA	0.000	1.000	1.000
		0641- 15-142	PREST CONC POLE (F&I)(42' TYPE N-VI)	EA	0.000	1.000	1.000
		0641- 15-144	PREST CONC POLE (F&I)(44' TYPE N-VI)	EA	0.000	1.000	1.000
		0641- 15-146	PREST CONC POLE (F&I)(46' TYPE N-VI)	EA	0.000	1.000	1.000
		0641- 15-150	PREST CONC POLE (F&I)(50' TYPE N-VI)	EA	0.000	1.000	1.000
		0641- 15-152	PREST CONC POLE (F&I)(52' TYPE N-VI)	EA	0.000	1.000	1.000
		0641- 15-154	PREST CONC POLE (F&I)(54' TYPE N-VI)	EA	0.000	1.000	1.000
		0641- 16-146	PREST CONC POLE (F&I)(46' TYPE N-VII)	EA	0.000	2.000	2.000
		0641- 16-148	PREST CONC POLE (F&I)(48' TYPE N-VII)	EA	0.000	1.000	1.000
		0641- 16-150	PREST CONC POLE (F&I)(50' TYPE N-VII)	EA	0.000	1.000	1.000
		0641- 16-152	PREST CONC POLE (F&I)(52' TYPE N-VII)	EA	0.000	1.000	1.000
		0641- 16-154	PREST CONC POLE (F&I)(54' TYPE N-VII)	EA	0.000	1.000	1.000
		0641- 16-156	PREST CONC POLE (F&I)(56' TYPE N-VII)	EA	0.000	1.000	1.000
		0641- 16-158	PREST CONC POLE (F&I)(58' TYPE N-VII)	EA	0.000	1.000	1.000
		0641- 30-	PREST CONC POLE (INSTALL)	EA	0.000	1.000	1.000
		0650- 51-111	SIGNAL TRAFFIC(F&I)(1 SECT 1 WAY)(STD)	AS	0.000	5.000	5.000
		0650- 51-121	SIGNAL TRAFFIC(F&I)(1 SECT 2 WAY)(STD)	AS	0.000	2.000	2.000
		0650- 51-311	SIGNAL TRAFFIC(F&I)(3 SECT 1 WAY)(STD)	AS	0.000	20.000	20.000
		0650- 51-312	SIGNAL TRAFFIC(F&I)(3 SECT 1 WAY)(LW)	AS	0.000	3.000	3.000
		0650- 51-321	SIGNAL TRAFFIC(F&I)(3 SECT 2 WAY)(STD)	AS	0.000	5.000	5.000
		0650- 51-322	SIGNAL TRAFFIC(F&I)(3 SECT 2 WAY)(LW)	AS	0.000	2.000	2.000
		0650- 51-511	SIGNAL TRAFFIC(F&I)(5 SECT 1 WAY)(STD)	AS	0.000	7.000	7.000
		0650- 51-512	SIGNAL TRAFFIC(F&I)(5 SECT 1 WAY)(LW)	AS	0.000	2.000	2.000
		0650- 53-111	SIGNAL TRAFFIC(INS)(1SECT1WAY(STD)	AS	0.000	4.000	4.000
		0650- 53-311	SIGNAL TRAFFIC(INS)(3SECT1WAY(STD)	AS	0.000	3.000	3.000
		0650- 53-321	SIGNAL TRAFFIC(INS)(3SECT2WAY(STD)	AS	0.000	2.000	2.000
		0650- 53-511	SIGNAL TRAFFIC(INS)(5SECT1WAY(STD)	AS	0.000	2.000	2.000
		0653-111-	SIGNAL PEDESTRIAN (12" INCANDESCENT)	AS	0.000	4.000	4.000
		0653-112-	SIGNAL PEDESTRIAN (12" INCANDESCENT)	AS	0.000	2.000	2.000
		0653-181-	SIGNAL PEDESTRIAN (F&I) (LED) (1 DIRECTION)	AS	0.000	10.000	10.000
		0653-182-	SIGNAL PEDESTRIAN (F&I) (LED) (2 DIRECTIONS)	AS	0.000	5.000	5.000
		0653-311-	SIGNAL PEDESTRIAN (12" INCANDESCENT)	AS	0.000	2.000	2.000
		0653-312-	SIGNAL PEDESTRIAN (12" INCANDESCENT)	AS	0.000	2.000	2.000
		0659-107-	SIGNAL HEAD AUXILIARIES (ALUMINUM PEDESTAL)	EA	0.000	8.000	8.000
		0659-109-	SIGNAL HEAD AUXILIARIES (CONC PEDESTAL TYPE II)	EA	0.000	4.000	4.000
		0660- 1-101	LOOP DETECTOR INDUCTIVE (F&I) (TYPE 1)	EA	0.000	10.000	10.000
		0660- 1-102	LOOP DETECTOR INDUCTIVE, F&I, TYPE 2	EA	0.000	10.000	10.000
		0660- 1-109	LOOP DETECTOR INDUCTIVE (F&I) (TYPE 9)	EA	0.000	10.000	10.000
		0660- 1-110	LOOP DETECTOR INDUCTIVE (F&I) (TYPE 10)	EA	0.000	10.000	10.000
		0660- 2-101	LOOP ASSEMBLY (F&I) (TYPE A)	AS	0.000	8.000	8.000

PROPOSAL: E5K69
FINPROJ : 23800225234 COUNTY/SECTION: COUNTY: STATEWIDE MANDIST: 05

0500 SUMMARY OF SIGNALIZATION PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	23800225234 Non-Participating	23800225234 Participating	QUANTITY TOTAL
		0660- 2-102	LOOP ASSEMBLY (F&I) (TYPE B)	AS	0.000	30.000	30.000
		0660- 2-106	LOOP ASSEMBLY (F&I) (TYPE F)	AS	0.000	26.000	26.000
		0663- 74- 11	VEHICLE DETECTOR ASSEM (F&I)(OPTICAL TYPE)	EA	0.000	2.000	2.000
		0665- 11-	DETECTOR PEDEST(F&I)(DET STA POLE OR CABINET MTD)	EA	0.000	22.000	22.000
		0668- 13-	DETECTOR CABINET (F&I)(TYPE III) (32"X20"X14")	EA	0.000	2.000	2.000
		0670- 4- 1	CNTRL ASSEM FLASHING BEACON (FURNISH & INSTAL)	AS	0.000	2.000	2.000
		0670- 5-110	CNTL ASSEM ACT SS F&I NEMA PRE(NONE)	AS	0.000	1.000	1.000
		0670- 5-111	CNTL ASSEM ACT SS F&I NEMA PRE(ONE)	AS	0.000	1.000	1.000
		0670- 5-112	CNTL ASSEM ACT SS F&I NEMA PRE(TWO)	AS	0.000	1.000	1.000
		0670- 5-131	CNTL ASSEM ACT SS F&I SPEC PRE(ONE)	AS	0.000	1.000	1.000
		0670- 5-132	CNTL ASSEM ACT SS(F&I) (SPECIAL) PRE(TWO)	AS	0.000	1.000	1.000
		0670- 5-311	CNTL ASSEM ACT SS INS NEMA PRE(ONE)	AS	0.000	1.000	1.000
		0670- 5-410	CNTL ASSEM ACT SS MOD NEMA PRE(NONE)	AS	0.000	1.000	1.000
		0670- 5-411	CNTL ASSEM ACT SS MOD NEMA PRE(ONE)	AS	0.000	1.000	1.000
		0670- 5-412	CNTL ASSEM ACT SS MOD NEMA PRE(TWO)	AS	0.000	1.000	1.000
		0678- 1-107	CONTROLLER ACCESSORIES(F&I)(TYPE 1 TIME SWITCH)	EA	0.000	1.000	1.000
		0690- 10-	SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	EA	0.000	50.000	50.000
		0690- 20-	SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	EA	0.000	4.000	4.000
		0690- 31-	SIGNAL PEDESTAL REMOVAL	EA	0.000	2.000	2.000
		0690- 32- 1	POLE REMOVAL(SHALLOW/DIRECT BURIAL)	EA	0.000	2.000	2.000
		0690- 32- 2	POLE REMOVAL(SHALLOW/BOLT ON ATTACH)	EA	0.000	1.000	1.000
		0690- 33- 1	POLE REMOVAL (DEEP DIRECT BURIAL)	LF	0.000	20.000	20.000
		0690- 33- 2	POLE REMOVAL (DEEP BOLT ON ATTACH)	LF	0.000	20.000	20.000
		0690- 50-	CNTRL ASSEM REMOVE	EA	0.000	3.000	3.000
		0690- 70-	DETECTOR PEDESTRIAN ASSEMBLY REMOVE	EA	0.000	8.000	8.000
		0690- 80-	SPAN WIRE ASSEMBLY REMOVE	EA	0.000	9.000	9.000
		0690- 90-	CONDUIT & CABLING REMOVE	PI	0.000	8.000	8.000
		0690-100-	SIGNAL EQUIPMENT MISCELLANOUS REMOVE	PI	0.000	5.000	5.000
		0699- 1- 1	SIGN, INTERNAL ILLUM(ST NAME)	EA	0.000	8.000	8.000
		0700- 40- 1	SIGN SINGLE POST (LESS THAN 12)	AS	0.000	16.000	16.000
		0700- 40- 2	SIGN SINGLE POST (12 - 25)	AS	0.000	2.000	2.000
		0700- 41- 10	SIGN MULTI POST (50 OR LESS)	AS	0.000	2.000	2.000
		0700- 43- 11	SIGN OVHD CTLVR (C 20 OR <,S/ 50 OR <)	AS	0.000	6.000	6.000
		0700- 46- 11	SIGN EXISTING (REMOVAL) (SINGLE POST)	AS	0.000	15.000	15.000
		0700- 46- 21	SIGN EXISTING (RELOCATE) (SINGLE POST)	AS	0.000	2.000	2.000
		0700- 47- 1	SIGN INSTL EXISTING BREAKWAY SUPPORT SINGLE POST	AS	0.000	2.000	2.000
		0700- 48- 18	SIGN PANELS (F & I) (15 OR <)	EA	0.000	10.000	10.000
		0700- 48- 48	SIGN PANELS (RELOCATE) (15 OR <)	EA	0.000	4.000	4.000
		0700- 89- 3	SIGN ELEC POWERED(CHGABLE MESSAGE-FIBER OPTICS)	EA	0.000	2.000	2.000
		0700- 90- 14	SIGN FLASHING BEACON (F&I) (SPAN WIRE)	AS	0.000	1.000	1.000
		0705- 71-	DELINEATOR TUBULAR (FLEXIBLE)	EA	0.000	5.000	5.000
		0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	0.000	144.000	144.000
		0710- 25- 61	TRAFFIC STRIPE SOLID (WHITE/BLACK) (6")	LF	0.000	200.000	200.000
		0710- 26- 61	TRAFFIC STRIPE SOLID (YELLOW) (6")	LF	0.000	200.000	200.000
		0710- 29-	REFLECTIVE PAINT (ISLAND NOSE) (WHITE)	SY	0.000	12.000	12.000
		0710- 30-	REFLECTIVE PAINT (ISLAND NOSE) (YELLOW)	SY	0.000	20.000	20.000

PROPOSAL: E5K69
FINPROJ : 23800225234 COUNTY/SECTION: COUNTY: STATEWIDE MANDIST: 05

0500 SUMMARY OF SIGNALIZATION PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	23800225234 Non-Participating	23800225234 Participating	QUANTITY TOTAL
		0711- 3-	PAVT MESSAGES THERMOPLASTIC	EA	0.000	5.000	5.000
		0711- 4-	DIRECTIONAL ARROWS THERMOPLASTIC	EA	0.000	45.000	45.000
		0711- 5- 1	GUIDE LINES (THERMOPLASTIC) (WHITE)	LF	0.000	100.000	100.000
		0711- 7-	PAVT MARKING REMOVE THERMOPLASTIC	SF	0.000	2000.000	2000.000
		0711- 33-	TRAFFIC STRIPE SKIP (THERMOPLASTIC) (WHITE)	LF	0.000	224.000	224.000
		0711- 34-	TRAFFIC STRIPE SKIP (THERMOPLASTIC) (YELLOW)	LF	0.000	83.000	83.000
		0711- 35- 61	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (6")	LF	0.000	1809.000	1809.000
		0711- 35- 81	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (8")	LF	0.000	140.000	140.000
		0711- 35-121	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (12")	LF	0.000	2000.000	2000.000
		0711- 35-181	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (18")	LF	0.000	50.000	50.000
		0711- 35-241	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(WHITE) (24")	LF	0.000	925.000	925.000
		0711- 36- 61	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(6")	LF	0.000	2065.000	2065.000
		0711- 36- 81	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(8")	LF	0.000	422.000	422.000
		0711- 36-181	TRAFFIC STRIPE SOLID (THERMOPLASTIC)(YELLOW)(18")	LF	0.000	113.000	113.000
		E102- 1- 3	MAINTENANCE OF TRAFFIC	LO	0.000	10.000	10.000
		E102- 1- 4	MAINTENANCE OF TRAFFIC (NIGHT WORK)	LO	0.000	3.000	3.000
		E110- 70-	REMOVAL OF FLEXIBLE PAVEMENT	SY	0.000	713.000	713.000
		E632- 8-141	CABLE (INTERCONNECT)(REMOVE) (AERIAL)	LF	0.000	1500.000	1500.000
		E634- 8-112	SPAN WIRE ASSEMBLY (2 WIRE DIAGONAL)	LF	0.000	1114.000	1114.000
		E634- 8-113	SPAN WIRE ASSEMBLY (2 WIRE BOX)	LF	0.000	433.000	433.000
		E660- 4- 4	LOOP MATERIAL (F&I) (AWG #14 LEAD-IN CABLE)	LF	0.000	6068.000	6068.000