BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 06100325 CALL ORDER: 011 PROPOSAL ID: E6G23 DISTRICT: 06
COUNTIES : MIAMI-DADE, , ,

ROAD NAME : GUARDRAIL INSTALLATION
LIMITS : MIAMI-DADE COUNTY

FINPROJ NO(S): 41278147201 (*) FEDERAL AID NO: N/A WORK MIX: ROUTINE MAINTENANCE

TOTAL ROADWAY LENGTH: 0.000 MILES CONTRACT DAYS: 365
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 03/25/10
TOTAL PROPOSAL LENGTH: 0.000 MILES CONTRACT EXECUTION DAYS: 10
SPECIAL START DATE: N/A

PROPOSAL BUDGET ESTIMATE: $ 120,000.00

PROPOSAL PACKAGE FEE(PLANS + PROPOSAL): $0.00 PLANS ONLY FEE: $0.00 SPECS ONLY FEE: $0.00

DESCRIPTION:
SEALED BIDS ARE REQUESTED FOR A PUSH-BUTTON CONTRACT FOR PROVIDING LABOR, EQUIPMENT AND MATERIALS TO CONSTRUCT NEW GUARDRAIL, REMOVE AND REPAIR OR REPLACE DAMAGED OR DESTROYED SECTIONS OF GUARDRAIL, CONSTRUCT NEW BULLET RAILING (ALUMINUM), PIPE HANDRAIL (STEEL, ALUMINUM AND PVC) AND PEDESTRIAN/BICYCLE RAILING (PICKET RAIL ALUMINUM AND STEEL) IN ACCORDANCE WITH THE DEPARTMENT DESIGN STANDARDS, AND REVISIONS THERETO CURRENT AT THE TIME CONTRACT LETTING. THE WORK MAY BE INCLUDE REALIGMENT OF PANELS, POSTS, BLOCKS AND ANCHORAGES, AND MISCELLANEOUS HARDWARE. THE VARIOUS ITEMS SHALL BE PERFORMED IN ACCORDANCE WITH THESE SPECIFICATIONS AND IN CONFORMITY WITH THE EXISTING LINES, GRADES AND DIMENSIONS. THIS IS A WORK ORDER DRIVEN CONTRACT, THERE ARE NO SPECIFIC LOCATIONS. THE WORK WILL BE ASSIGNED WITHIN THE LIMITS OF MIAMI-DADE COUNTY BY THE DISTRICT MAINTENANCE ENGINEER OR IS REPRESENTATIVE. THIS CONTRACT IS FOR A TERM OF 365 DAYS; BUDGETARY CEILING: $120,000.00; DBE AVAILABILITY: N/A; INTERNET BIDDING IS AVAILABLE FOR THIS PROPOSAL.

ALT	ITEM NO.	D E S C R I P T I O N	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<<		SECTION 0001 GUARDRAIL REPAIR		>>>>>>>>>>>>
	0460 70 1	ALUMINUM BULLET RAILINGS, SINGLE RAIL	LF	75.000
	0460 70 2	ALUMINUM BULLET RAILINGS, DOUBLE RAIL	LF	75.000
	0460 70 3	ALUMINUM BULLET RAILINGS, TRIPLE RAIL	LF	75.000
	0515 1 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	75.000
	0515 1 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	75.000
	0515 1 5	PIPE HANDRAIL- GUIDERAIL, PVC	LF	75.000
	0515 2201	PEDESTRIAN, BICYCLE RAILING, STEEL ONLY,42" PICKET RAIL	LF	75.000
	0515 2202	PEDESTRIAN / BICYCLE RAILING, STEEL ONLY, 54" PICKET RAIL	LF	75.000
	0515 2301	PEDESTRIAN, BICYCLE RAILING, ALUMINUM ONLY,42" PICKET RAIL	LF	75.000
	0515 2302	PEDESTRIAN, BICYCLE RAILING, ALUMINUM ONLY,54" PICKET RAIL	LF	60.000
	0536 2	GUARDRAIL- SHOP-BENT PANELS	LF	500.000
	0536 7	SPECIAL GUARDRAIL POST	EA	10.000
	0536 85 22	GUARDRAIL END ANCHORAGE ASSEMBLY- FLARED	EA	10.000
	0536 85 24	GUARDRAIL END ANCHORAGE ASSEMBLY- PARALLEL	EA	7.000
	0538 1	GUARDRAIL RESET	LF	100.000
	E536 3122	GUARDRAIL PANELS (INSTALL) (0' - 50')	LF	500.000
	E536 3240	GUARDRAIL THRIE BEAM (REPLACE)	LF	20.000
	E536 5 1	THRIE BEAM (TERMINAL CONNECTOR)	EA	7.000
	E536 5 2	THRIE BEAM (RAIL SPLICE)	EA	7.000
	E536 5 3	THRIE BEAM (TRANSITION SECTION)	EA	20.000
	E536 5 4	THRIE BEAM (MODIFIED OFFSET BLOCK)	EA	7.000
	E536 6 61	END ANCHORAGE ASSEM (F&I) (TYPE II)	EA	7.000
	E536 12602	GUARDRAIL REPAIRS (REPLACE) (WOOD BLOCK)	EA	50.000
	E536 12603	GUARDRAIL REPAIRS (REPL) (PLASTIC BLOCK)	EA	65.000
	E536 12604	GUARDRAIL REPAIRS (REPLACE) (STEEL POST IN CONC.)	EA	12.000
	E536 12605	GUARDRAIL REPAIRS (REPLACE) (STEEL POST IN ASPH.)	EA	25.000
	E536 12606	GUARDRAIL REPAIRS (REPLACE) (STEEL POST IN SOIL)	EA	25.000
	E536 12608	GUARDRAIL REPAIRS (REPLACE) (WOOD POST IN ASPH.)	EA	25.000
	E536 12609	GUARDRAIL REPAIRS (REPLACE) (WOOD POST IN SOIL)	EA	15.000
	E536 12611	GUARDRAIL REPAIRS (REPLACE) (REFLECTORS)	EA	40.000
	E536 14 2	GUARDRAIL ALIGNMENT (SINGLE FACE)	LF	200.000
	E536301501	END ANCHOR ASSEM TYPE II (REPL FLARED END SECT)	EA	5.000
	E536301503	END ANCHOR ASSEM TYPE II (REPL BUFFER END SECT)	EA	5.000

ALT	ITEM NO.	D E S C R I P T I O N	UNITS	FA/NFA QUANTITY
	E536301506	END ANCHOR ASSEM TYPE II (REPL GUARDRAIL BEAM)	EA	7.000
	E536305501	END ANCHOR ASSEM ET-2000 (REPL TIMBER BRK POST)	EA	7.000
	E536305507	END ANCHOR ASSEM ET-2000 (REPL STEEL TUBE/POST)	EA	7.000
	E536305508	END ANCHOR ASSEM ET-2000 (REPL GUARDRAIL BEAM)	EA	7.000
	E536308213	END ANCHOR ASSEM SRT-350 (INSTALL END SHOE)	EA	10.000
	E536308505	END ANCHOR ASSEM SRT-350 (REPL TIMBER BREAK POST)	EA	10.000
	E536308507	END ANCHOR ASSEM SRT-350 (REPL BUFFER END SECT)	EA	7.000
	E536308511	END ANCHOR ASSEM SRT-350 (REPL GUARDRAIL BEAM)	EA	7.000
	E536313508	END ANCHOR ASSEMBLY SKT-350 (REPL GUARDRAIL BEAM)	EA	5.000
	E536317511	END ANCHORAGE ASSEMBLY (REGENT C) GUARDRAIL BEAM	EA	5.000