BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 06120126 CALL ORDER: 005 PROPOSAL ID: E6H26-R0 DISTRICT: 06
COUNTIES : MIAMI-DADE, , ,

ROAD NAME : THERMOPLASTIC STRIPING MIAMI-DADE COUNTYWIDE
LIMITS : VARIOUS ROADS IN MIAMI-DADE COUNTY

FINPROJ NO(S):	FEDERAL AID NO(S):	MAJOR WORK TYPE:
42828527201 (*)	N/A	ROUTINE MAINTENANCE

TOTAL ROADWAY LENGTH: 0.000 MILES
TOTAL BRIDGE LENGTH: 0.000 MILES
TOTAL PROPOSAL LENGTH: 0.000 MILES

CONTRACT DAYS: 365
LETTING DATE : 01/26/12
CONTRACT EXECUTION DAYS: 10
SPECIAL START DATE: N/A

PROPOSAL BUDGET ESTIMATE: $ 375,000.00

PROPOSAL PACKAGE FEE(PLANS + PROPOSAL): $0.00 PLANS ONLY FEE: $0.00 SPECS ONLY FEE: $0.00

DESCRIPTION:
Electronic/Sealed Bids are requested for a contract providing labor, equipment and materials to apply or refurbish new and exisiting Thermoplastic Traffic Stripes and Markings, in accordance with Section 711 of the 2010 Edition of the Florida Department of Transportation Standard Specifications and all revisions thereafter. This is a work order driven contract, there are no specific locations. No quantities are guaranteed and there will be no unit cost adjustment for quantities required over or under the estimated quantities. The quantities to be paid for will be the area of existing painted traffic stripes and/or markings removed and accepted in square feet. Quantities of 500 ft or less will be paid under pay items with units of LF. Quantities of more than 500 ft will be paid under pay items with units of GM or NM. The actual quantities may be adjusted depending on the work assigned. Actual reimbursement to the contractor will be based on the unit price bid regardless of the actual quantity of work authorized for completion and approved by the Department. The work will be assigned within the limits of Miami-Dade County by the District Maintenance Engineer or his representative. This contract is for a term of 365 calendar days. In lieu of a pre-qualification in Pavement Markings, an Experience and Expertise form must be completed and submitted with the bid to be deemed responsive. Budget Amount:$375,000.00; DBE Availability is 12%.

Special Note: District Six is no longer accepting handwritten bids.

ALT	ITEM NO.	D E S C R I P T I O N	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<<		SECTION 0001 PAVEMENT STRIPING		>>>>>>>>>>>>
	0711 11111	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	NM	9.000
	0711 11122	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8"	LF	2,000.000
	0711 11123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	LF	3,000.000
	0711 11124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18"	LF	1,000.000
	0711 11125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	LF	2,000.000
	0711 11131	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	9.000
	0711 11151	THERMOPLASTIC, STANDARD, WHITE, DOTTED/GUIDELINE/ 6-10 GAP EXTENSION, 6"	LF	1,000.000
	0711 11211	THERMOPLASTIC, STANDARD,YELLOW, SOLID, 6"	NM	9.000
	0711 11222	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 8"	LF	1,000.000
	0711 11224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18"	LF	1,000.000
	0711 11231	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	GM	1.000
	0711 11251	THERMOPLASTIC, STANDARD, YELLOW, DOTTED / GUIDELINE /6-10 GAP EXTENSION, 6"	LF	500.000
	0711 12111	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6"	NM	35.000
	0711 12121	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6"	LF	6,000.000
	0711 12122	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 8"	LF	5,500.000
	0711 12123	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 12"	LF	8,000.000
	0711 12124	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 18"	LF	4,500.000
	0711 12125	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 24"	LF	4,500.000

ALT	ITEM NO.	D E S C R I P T I O N	UNITS	FA/NFA QUANTITY
	0711 12131	THERMOPLASTIC, REFURBISHMENT, WHITE, SKIP, 6"	GM	39.000
	0711 12151	THERMOPLASTIC, REFURBISHMENT, WHITE, DOTTED/ GUIDELINE /6-10 GAP EXTENSION, 6"	LF	2,000.000
	0711 12211	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	NM	20.000
	0711 12221	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	LF	5,000.000
	0711 12222	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 8"	LF	6,000.000
	0711 12223	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 12"	LF	3,000.000
	0711 12224	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 18"	LF	4,500.000
	0711 12231	THERMOPLASTIC, REFURBISHMENT, YELLOW, SKIP, 6"	GM	2.000
	0711 12241	THERMOPLASTIC, REFURBISHMENT, YELLOW, SKIP, 6"	LF	2,000.000
	0711 12251	THERMOPLASTIC, REFURBISHMENT, YELLOW DOTTED / GUIDELINE/ 6-10 GAP EXTENSION, 6"	LF	500.000
	0711 14123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12"	LF	600.000
	0711 14125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24"	LF	600.000
	0711 17	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS	SF	20,500.000
	0713102533	PREFORMED TAPE, HIGH PERFORMANCE, WHITE/BLACK CONTRAST, SKIP, 9"	GM	12.000
	0713102547	PREFORMED TAPE, HIGH PERFORMANCE, WHITE/BLACK CONTRAST, SKIP, 11"	LF	1,000.000
	E706 1 42	REFLECTIVE PAVEMENT MARKER(REM AND REPL)(CLASS B)	EA	500.000
	E711 11121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	500.000
	E711 11221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	400.000
<<<<<<<<<<<<		SECTION 0002 PAVEMENT SYMBOLS (SF)		>>>>>>>>>>>>
	0711 11160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE	EA	125.000
	0711 11170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	150.000
	0711 12160	THERMOPLASTIC, REFURBISH, WHITE, MESSAGE	EA	150.000
	0711 12170	THERMOPLASTIC, REFURBISH, WHITE, ARROWS	EA	300.000
	0711 14160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	15.000
	0711 14170	THERMOPLASTIC, PREFORMED, WHITE, ARROWS	EA	18.000