FLORIDA DEPARTMENT OF TRANSPORTATION
BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 06140424 CALL ORDER: 006 PROPOSAL ID: E6J13-R0 DISTRICT: 06
COUNTIES : MIAMI-DADE, , ,

ROAD NAME : ASPHALT REPAIR
LIMITS : VARIOUS ROADS IN MIAMI-DADE COUNTY

FINPROJ NO(S): FEDERAL AID NO(S):
43027917202 (*) N/A

TOTAL ROADWAY LENGTH: 0.000 MILES CONTRACT DAYS: 365
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 04/24/14
TOTAL PROPOSAL LENGTH: 0.000 MILES CONTRACT EXECUTION DAYS: 10
SPECIAL START DATE: N/A

PROPOSAL PACKAGE FEE(PLANS + PROPOSAL): $0.00 PLANS ONLY FEE: $0.00 SPECS ONLY FEE: $0.00

DESCRIPTION:
Electronic/sealed bids are requested for a contract that consists of repairing existing asphalt pavement. This is a work order driven contract and there are no specific locations. No quantities are guaranteed and there will be no pay item unit cost adjustments for quantities required over or under the estimated quantities. The various items shall be constructed in accordance with these specifications and in conformity with the existing lines, grades and dimensions. The work is to be performed as directed by the Maintenance Engineer or his representative.

Bidders must complete the Experience in Asphalt Repair (Form No. 850-070-01) and submit it with the bid or the bid will be deemed non-responsive. Budgetary Ceiling: $100,000.00.

* Special Note: This bid must be submitted using Expedite Bid or through Bid Express and all attachments must be in a zip format.

ALT	ITEM NO.	D E S C R I P T I O N	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<<		SECTION 0001 ASPHALT REPAIR MACHANICAL		>>>>>>>>>>>>
	0327 70 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	195.000
	0327 70 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	800.000
	0327 70 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	400.000
	0327 70 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	195.000
	0334 1 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	66.000
	0334 1 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	22.000
	0337 7 24	ASPHALT CONCRETE FRICTION COURSE, FC-5, PG 76-22, ARB	TN	10.000
	0337 7 42	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22, PMA	TN	33.000
	0337 7 45	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC D, FC-12.5, PG 76-22, PMA	TN	11.000
	0337 7 74	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22, ARB	TN	56.000
	0660 2101	LOOP ASSEMBLY- F&I, TYPE A	AS	2.000
<<<<<<<<<<<<		SECTION 0002 TRAFFIC CONTROL DEVICES CONTROL (MH)		>>>>>>>>>>>>
	0285709	OPTIONAL BASE, BASE GROUP 09	SY	120.000
	0425 5	MANHOLE, ADJUST	EA	35.000
	0706 3	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	100.000
	0711 11123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	LF	72.000
	0711 11124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18"	LF	100.000
	0711 11125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	LF	72.000
	0711 11160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE	EA	7.000
	0711 11170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	7.000
	E101 1 1	MOBILIZATION	LO	8.000
	E102 1 3	MAINTENANCE OF TRAFFIC	LO	2.000
	E102 1 4	MAINTENANCE OF TRAFFIC (NIGHT WORK)	LO	6.000
	E102 10	OFF-DUTY LAW ENFORCEMENT OFFICER	MH	24.000
	E711 11121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	750.000
	E711 11141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	250.000
	E711 11221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	250.000