FLORIDA DEPARTMENT OF TRANSPORTATION
BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 06150730 CALL ORDER: 001 PROPOSAL ID: E6J85-R0 (Maintenance)
DISTRICT : 06 COUNTIES : MIAMI-DADE, , ,

ROAD NAME : DELINEATOR REPAIR
LIMITS : VARIOUS ROADS IN MIAMI-DADE COUNTY

FINPROJ NO(S): FEDERAL AID NO(S):
43715717201 (*) N/A

TOTAL ROADWAY LENGTH: 0.000 MILES CONTRACT DAYS: 365
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 07/30/15
TOTAL PROPOSAL LENGTH: 0.000 MILES CONTRACT EXECUTION DAYS: 10
BUDGET AMOUNT: $ 270,000.00 SPECIAL START DATE: N/A

Please read the full advertisement

DESCRIPTION:
Electronic/sealed bids are requested for a contract that consists of replacing damaged or missing delineators on the State Road 977/Southwest 177 Avenue/Krome Avenue, from State Road-5/US 1 to North Okeechobee Road. Replacement of damaged delineators will be any of the following: A) furnish and install complete delineator assemblies, B) furnish and install delineator posts on existing bases, including all hardware, and C) install complete delineator assemblies. This project will replace several types of existing delineators. Existing delineator bases may either be epoxied or bolted to the pavement. Replacement of existing posts shall be in kind and compatible with the existing bases, per each of the manufacturer's recommendations. In some cases, the Department may provide Contractor any type of delineator for installation only, either epoxied or bolted to the pavement. This is a Work Order driven contract. No quantities are guarenteed and there will be no pay item unit cost adjustments for quantities required over or under the estimated quantities. Contractors shall submit a Maintenance of Traffic Plan for approval by the Project Manager before any work is performed. The summary of pay items for this project is listed in the bid price proposal.

*** SPECIAL NOTE: This bid must be submitted using Expedite Bid or through Bid Express and all attachments must be in a zip format. Handwritten bids will not be considered.

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<		SECTION 0001 DELINEATORS (UN)		>>>>>>>>>>>
	0705 11 5	DELINEATOR, FLEXIBLE HIGH PERFORMANCE 36" MANAGED LANES	EA	644.000
	0705 11 10	DELINEATOR, INSTALL ONLY- ITEM FURNISHED BY FDOT	EA	215.000
	0705 11 11	DELINEATOR POST, FURNISH & INSTALL ON EXISTING BASE	EA	3,435.000