PROPOSAL : E7I15 LEAD PROJECT : 42907425201 COUNTY : HILLSBOROUG , MANDIST: 07
PROJECT(S): 42907425201 COUNTY/SECTION: 10060000 ,

0001 SUMMARY OF ROADWAY PAY ITEMS

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	42907425201		QUANTITY TOTAL
	0101- 1-	MOBILIZATION (42907425201)	LS	1.000		1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42907425201)	LS	1.000		1.000
	0102- 3-	COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	CY	106.000		106.000
	0102- 60-	WORK ZONE SIGN	ED	4099.000		4099.000
	0102- 74- 1	TEMPORARY BARRICADE- TYPES I, II, DI, VP, DRUM, ORLCD	ED	8454.000		8454.000
	0102- 74- 2	BARRICADE, TEMPORARY, TYPE III, 6'	ED	455.000		455.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	125.000		125.000
	0102- 77-	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	528.000		528.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	766.000		766.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	217.000		217.000
	0102-911- 1	PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, SKIP	LF	84.000		84.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, SOLID	LF	5775.000		5775.000
	0102-911- 3	PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, OTHER	SF	234.000		234.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	1301.000		1301.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	32.000		32.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1077.000		1077.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	33.000		33.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	11.000		11.000
	0104- 19-	CHEMICAL TREATMENT- POWDERED, FOR EROSION CONTROL	SY	32.000		32.000
	0107- 1-	LITTER REMOVAL	AC	4.500 N		4.500
	0107- 2-	MOWING	AC	4.500 N		4.500
	0110- 1- 1	CLEARING & GRUBBING (42907425201)	LS	1.000		1.000
	0110- 4-	REMOVAL OF EXISTING CONCRETE PAVEMENT	SY	394.000		394.000
	0120- 1-	REGULAR EXCAVATION	CY	269.000		269.000
	0120- 6-	EMBANKMENT	CY	288.000		288.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	531.000		531.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	320.000		320.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	150.000		150.000
	0327- 70- 3	MILLING EXIST ASPH PAVT, 4 1/2" AVG DEPTH	SY	385.000		385.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	3168.000		3168.000
	0327- 70- 7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	SY	11038.000		11038.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	508.000		508.000
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	2748.000		2748.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	501.100		501.100
	0334- 1- 24	SUPERPAVE ASPH CONC, TRAF D, PG76-22	TN	1478.300		1478.300
	0337- 7- 5	ASPHALT CONCRETE FRICTION COURSE- INC BIT/RUBBER, FC-5	TN	133.600		133.600
	0337- 7- 45	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC D, FC-12 5,PG 76-22	TN	1232.700		1232.700

PROPOSAL : E7I15 LEAD PROJECT : 42907425201 COUNTY : HILLSBOROUG , MANDIST: 07
PROJECT(S): 42907425201 COUNTY/SECTION: 10060000 ,

0001 SUMMARY OF ROADWAY PAY ITEMS CONTINUED

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	42907425201		QUANTITY TOTAL
	0341- 70-	ASPHALT RUBBER MEMBRANE INTERLAYER	SY	11038.000		11038.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	108.000		108.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	20324.000		20324.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000		1.000
	0425- 7-	MANHOLE COVER- REPLACE	EA	3.000		3.000
	0430-950-	DESILTING CONCRETE BOX CULVERT,	CY	236.000 N		236.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1236.000		1236.000
	0522- 1-	SIDEWALK CONCRETE, 4" THICK	SY	1379.000		1379.000
	0522- 2-	SIDEWALK CONCRETE, 6" THICK	SY	384.000		384.000
	0570- 1- 1	PERFORMANCE TURF	SY	1591.000		1591.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2376.000		2376.000
	0710- 11-111	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	NM	1.738		1.738
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 12"	LF	118.000		118.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	LF	887.000		887.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP 6",10-30 OR 3-9 SKIP	GM	2.914		2.914
	0710- 11-151	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED /GUIDELINE/ 6-10 GAP EXTENSION, 6"	LF	456.000		456.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	EA	16.000		16.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	12.000		12.000
	0710- 11-211	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	NM	1.402		1.402
	0710- 11-251	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, DOTTED/GUIDELINE/6-10 GAP EXTENSION, 6"	LF	504.000		504.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42907425201)	LS	1.000 N		1.000

PROPOSAL : E7I15 LEAD PROJECT : 42907425201 COUNTY : HILLSBOROUG , MANDIST: 07
PROJECT(S): 42907425201 COUNTY/SECTION: 10060000 ,

0002 SUMMARY OF SIGNING

PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	42907425201		QUANTITY TOTAL
		0700- 20- 11	SINGLE POST SIGN, F&I, LESS THAN 12 SF	AS	8.000		8.000
		0700- 20- 40	SINGLE POST SIGN, RELOCATE	AS	1.000		1.000
		0700- 20- 60	SINGLE POST SIGN, REMOVE	AS	8.000		8.000
		0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	2.000		2.000
		0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	EA	5.000		5.000
		0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	215.000		215.000
		0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLANDNOSE	SF	64.000		64.000
		0711- 11-111	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	NM	0.869		0.869
		0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	LF	118.000		118.000
		0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	LF	484.000		484.000
		0711- 11-131	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.457		1.457
		0711- 11-151	THERMOPLASTIC, STANDARD, WHITE, DOTTED/GUIDELINE/6-10 GAP EXTENSION, 6"	LF	228.000		228.000
		0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE	EA	8.000		8.000
		0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	6.000		6.000
		0711- 11-211	THERMOPLASTIC, STANDARD,YELLOW, SOLID, 6"	NM	0.701		0.701
		0711- 11-251	THERMOPLASTIC, STANDARD, YELLOW, DOTTED / GUIDELINE/6-10 GAP EXTENSION, 6"	LF	252.000		252.000
		0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENTMARKINGS	SF	274.000		274.000