PROPOSAL : E7I94 LEAD PROJECT : 40574415211 COUNTY : DIST/ST-WID , MANDIST: 07
PROJECT(S): 40574415211 COUNTY/SECTION: 15190000

0001 SUMMARY OF STRUCTURES — PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	40574415211 BR # Varies		QUANTITY TOTAL
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (40574415211)	LS	1.000		1.000
T		0110- 71- 1	BRIDGE FENDER SYSTEM, REMOVAL & DISPOSAL	LF	50.000		50.000
		0120- 5-	CHANNEL EXCAVATION	CY	100.000		100.000
		0125- 1-	EXCAVATION FOR STRUCTURES	CY	160.000		160.000
D		0142- 70-	FILL SAND	CY	17.000		17.000
		0400- 2- 4	CONC CLASS II, SUPERSTRUCTURE	CY	100.000		100.000
		0400- 3- 8	CONCRETE CLASS III, BULKHEAD	CY	50.000		50.000
		0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	100.000		100.000
		0400- 4- 5	CONCRETE CLASS IV, SUBSTRUCTURE	CY	50.000		50.000
T		0400- 32-	CONCRETE FOR JOINT REPAIR	CY	3.000		3.000
T		0400- 91-	DEWATERING FOR SPREAD FOOTINGS	EA	1.000		1.000
T		0400-128-	GROUTING PRECAST DECK PANELS, NON-SHRINK GROUT	LF	100.000		100.000
T		0400-142- 3	CATHODIC PROTECTION SYSTEM, ZINC ALUMINUM SPRAY	SF	200.000		200.000
T		0401- 70-	RESTORE SPALLED AREAS, GUNITE	CF	50.000		50.000
T		0401- 70- 1	RESTORE SPALLED AREAS, EPOXY	CF	20.000		20.000
T		0401- 70- 2	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR-STYRENEBUTADIENE	CF	20.000		20.000
T		0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR-ACRYLIC	CF	100.000		100.000
T		0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	50.000		50.000
T		0401- 70- 5	RESTORE SPALLED AREAS, CONTRACTORS OPTION	CF	25.000		25.000
T		0401- 70- 6	SPALLED AREAS RESTORE, THERMOSETTING POLYMER CONC	CF	50.000		50.000
		0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	20.000		20.000
		0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	50.000		50.000
		0415- 1- 4	REINFORCING STEEL - SUPERSTRUCTURE	LB	25.000		25.000
		0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	15.000		15.000
		0430-950-	DESILTING CONCRETE BOX CULVERT,	CY	25.000		25.000
		0440- 1- 10	UNDERDRAIN, TYPE I	LF	160.000		160.000
		0440- 73- 1	UNDERDRAIN OUTLET PIPE, 4"	LF	40.000		40.000
T		0450- 83- 1	BEAM REPAIR, STRAND SPLICES	EA	4.000		4.000
		0455- 34- 2	PRESTRESSED CONCRETE PILING, 14" SQ.	LF	80.000		80.000
		0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	45.000		45.000
		0455- 76-	WRAP PILE CLUSTERS	EA	10.000		10.000
T		0455- 81-101	CATHODIC PROTECTION, F&I, PILE, ZINC ANODE ASSEMBLY	EA	4.000		4.000
T		0455- 81-102	CATHODIC PROTECTION, F&I, PIER, ZINC ANODE ASSEMBLY	EA	2.000		2.000
		0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	100.000		100.000
T		0457- 2-111	CATHODIC PROTECTION INTEGRAL PILE JACKET, NON-STRUCTURAL, UP TO 16", GALVANIC SYSTEM	LF	30.000		30.000
T		0457- 2-121	CATHODIC PROTECTION INTEGRAL PILE JACKET, NON-STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	30.000		30.000
T		0457- 2-211	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, UP TO 16", GALVANIC SYSTEM	LF	30.000		30.000

PROPOSAL : E7I94 LEAD PROJECT : 40574415211 COUNTY : DIST/ST-WID , MANDIST: 07
PROJECT(S): 40574415211 COUNTY/SECTION: 15190000 ,

0001 SUMMARY OF STRUCTURES PAY ITEMS CONTINUED

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	40574415211 BR # Varies		QUANTITY TOTAL
T		0457- 2-221	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	30.000		30.000
T		0458- 1- 26	BRIDGE DECK EXPANSION JOINT, REHABILITATION, OTHER	LF	150.000		150.000
		0460- 1- 2	STRUCT STEEL, REHAB, LOW ALLOY	LB	25.000		25.000
		0460- 1- 13	STRUCTURAL STEEL REHAB- BOLTS, NUTS, WASHERS& PLATES	LB	30.000		30.000
		0460- 1- 15	STRUCTURAL STEEL - REHABILITATION, MISCELLANEOUS	LB	40.000		40.000
		0460- 6- 2	LADDERS & PLATFORMS, REHAB	LB	15.000		15.000
T		0460- 95-	STRUCTURAL STEEL REPAIR	LB	30.000		30.000
T		0460-112-	ANCHOR BOLT REPLACEMENT	EA	20.000		20.000
		0462- 2- 11	POST TENSIONING TENDONS, SUPERSTRUCTURE STRAND	LB	15.000		15.000
		0470- 1-	TREATED TIMBER, STRUCTURAL	MB	2.000		2.000
		0471- 1- 2	FENDER SYSTEM,PLASTIC MARINE LUMBER, NON-REINFORCED	MB	2.000		2.000
		0514- 71- 2	PLASTIC FILTER FABRIC, STABILIZATION	SY	112.000		112.000
		0530- 1-	RIPRAP, SAND-CEMENT	CY	75.000		75.000
		0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	165.000		165.000
		0530- 74-	BEDDING STONE	TN	25.000		25.000
T		0530- 78-	RIPRAP - ARTICULATING BLOCK	SY	75.000		75.000
		0561- 1-	COATING EXISTING STRUCTURAL STEEL (40574415211)	LS	1.000		1.000

PROPOSAL : E7I94 LEAD PROJECT : 40574415211 COUNTY : DIST/ST-WID , MANDIST: 07
PROJECT(S): 40574415211 COUNTY/SECTION: 15190000 ,

0002 SUMMARY OF ROADWAY PAY ITEMS

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	40574415211		QUANTITY TOTAL
		0101- 1-	MOBILIZATION (40574415211)	LS	1.000		1.000
		0102- 1-	MAINTENANCE OF TRAFFIC (40574415211)	LS	1.000		1.000
		0102- 60-	WORK ZONE SIGN	ED	50.000		50.000
		0102- 71- 11	BARRIER WALL, TEMPORARY, F&I, CONCRETE	LF	25.000		25.000
		0102- 71- 21	BARRIER WALL, TEMPORARY, RELOCATE, CONCRETE	LF	25.000		25.000
		0102- 71- 24	BARRIER WALL, TEMPORARY, RELOCATE, TYPE K	LF	25.000		25.000
		0102- 73-	TEMPORARY GUARDRAIL	LF	25.000		25.000
		0102- 74- 1	TEMPORARY BARRICADE- TYPES I, II, DI, VP, DRUM, ORLCD	ED	50.000		50.000
		0102- 74- 2	BARRICADE, TEMPORARY, TYPE III, 6'	ED	50.000		50.000
		0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	50.000		50.000
		0102- 77-	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	50.000		50.000
		0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	10.000		10.000
		0102- 79-	LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C,STEADY BURN	ED	50.000		50.000
		0102- 89- 7	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION, NON-CAPACITY PROJECTS OR >50	LO	1.000		1.000
		** Item 0102- 89- 7 is obsolete as of 12/31/2013 for lead project scheduled letting date 07/01/2014					
		0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	50.000		50.000
		0102-911- 1	PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, SKIP	LF	25.000		25.000
		0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, SOLID	LF	25.000		25.000
		0104- 10- 3	SEDIMENT BARRIER	LF	30.000		30.000
		0104- 11-	FLOATING TURBIDITY BARRIER	LF	100.000		100.000
		0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	30.000		30.000
		0110- 2- 1	CLEARING & GRUBBING (PUSH BUTTON CONTRACT)	AC	1.000		1.000
		0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	5.000		5.000
		0350- 78-	CLEANING & SEALING RANDOM CRACKS IN EXISTING CONCRETEPAVEMENT- REHAB	LF	25.000		25.000
T		0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (40574415211)	LS	1.000		1.000
T		0510- 1- 4	NAVIGATION LIGHTS- FIXED BRIDGE, REPAIR/REHAB	EA	1.000		1.000
		0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	30.000		30.000
		0522- 2-	CONC SIDEWALK AND DRIVEWAYS, 6" THICK	SY	30.000		30.000
		0525- 1-	CURB ASPHALTIC CONC	LF	30.000		30.000
		0536- 1- 2	GUARDRAIL- BRIDGE	LF	30.000		30.000
		0536- 7-	SPECIAL GUARDRAIL POST	EA	1.000		1.000
		0536- 8-	GUARDRAIL- BRIDGE ANCHORAGE ASSEMBLY,FURNISH & INSTALL	EA	1.000		1.000
		0536- 8- 6	GUARDRAIL, BRIDGE ANCHORAGE ASSEMBLY, REMOVE	EA	1.000		1.000
		0536- 73-	GUARDRAIL REMOVAL	LF	30.000		30.000
		0536- 83- 1	GUARDRAIL POST REPLACEMENT, REGULAR	EA	4.000		4.000
		0538- 1-	GUARDRAIL RESET	LF	20.000		20.000
		0690- 90-	CONDUIT & CABLING- WITHIN INTERSECTION, REMOVE	PI	3.000		3.000

PROPOSAL : E7I94 LEAD PROJECT : 40574415211 COUNTY : DIST/ST-WID , MANDIST: 07
PROJECT(S): 40574415211 COUNTY/SECTION: 15190000 ,

0002 SUMMARY OF ROADWAY PAY ITEMS CONTINUED

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	40574415211		QUANTITY TOTAL
		0700- 20- 12	SINGLE POST SIGN, F&I, 12-20 SF	AS	1.000		1.000
		** Item 0700- 20- 12 is obsolete as of 12/31/2013 for lead project scheduled letting date 07/01/2014					
		0700- 20- 40	SINGLE POST SIGN, RELOCATE	AS	1.000		1.000
		** Item 0700- 20- 40 is obsolete as of 12/31/2013 for lead project scheduled letting date 07/01/2014					
		0700- 20- 60	SINGLE POST SIGN, REMOVE	AS	1.000		1.000
		** Item 0700- 20- 60 is obsolete as of 12/31/2013 for lead project scheduled letting date 07/01/2014					
D		0700- 22-500	OVERHEAD TRUSS SPAN SIGN, REPAIR	AS	1.000		1.000
		** Item 0700- 22-500 is obsolete as of 12/31/2013 for lead project scheduled letting date 07/01/2014					
		0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	1.000		1.000
		0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	1.000		1.000