FLORIDA DEPARTMENT OF TRANSPORTATION
PROPOSAL SUMMARY OF PAY ITEMS

PROPOSAL : E7I92 LEAD PROJECT : 41602617237 COUNTY : HILLSBOROUG , MANDIST: 07
PROJECT(S): 41602617237 COUNTY/SECTION: ,

0001 SUMMARY OF SODDING (SY) PAY ITEMS

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41602617237		QUANTITY TOTAL
	0101- 1-	MOBILIZATION	LS	1.000		1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000		1.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	180.000		180.000
	0104- 10- 3	SEDIMENT BARRIER	LF	12000.000		12000.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	200.000		200.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000		2.000
	0120- 6-	EMBANKMENT	CY	200.000		200.000
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	5.060		5.060
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	3566.000		3566.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	1046.000		1046.000
	0430- 94- 3	DESILTING PIPE, 37 - 48"	LF	180.000		180.000
	0430-174-236	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH,36"SD	LF	40.000		40.000
	0430-950-	DESILTING CONCRETE BOX CULVERT,	CY	115.000		115.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	544.000		544.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	11125.000		11125.000
	E120- 10- 5	CLEAN AND RESHAPE CANAL (> 7.0' DEPTH)	LF	110.000		110.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	5.000		5.000
	E570- 5-	FERTILIZER	TN	2.000		2.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	5.000		5.000
	E575- 1-	SODDING	SY	25000.000		25000.000

PROPOSAL : E7I97 LEAD PROJECT : 41912715205 COUNTY : DIST/ST-WID , MANDIST: 07
PROJECT(S): 41912715205 COUNTY/SECTION: ,

0001 SUMMARY OF ROADWAY PAY ITEMS

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41912715205		QUANTITY TOTAL
		0110- 4-	REMOVAL OF EXISTING CONCRETE PAVEMENT	SY	50.000		50.000
		0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	40.000		40.000
		0121- 70-	FLOWABLE FILL	CY	180.000		180.000
T		0145- 71-	REINFORCEMENT GRID FOR SOIL STABILIZATION	SY	150.000		150.000
		0160- 4-	TYPE B STABILIZATION	SY	120.000		120.000
T		0173- 71-	DRILLING HOLES FOR PRESSURE GROUTING	EA	30.000		30.000
T		0173- 76-	GROUT PIPE INSTALLATION	LF	250.000		250.000
T		0173- 77- 3	SUBSURFACE PRESSURE GROUTING, CEMENT SLURRY	CY	225.000		225.000
		0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	80.000		80.000
		0287- 1-	ASPHALT TREATED PERMEABLE BASE	CY	80.000		80.000
		0327- 70- 7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	SY	225.000		225.000
		0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	110.000		110.000
		0337- 7- 22	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22, PMA	TN	25.000		25.000
		0350- 72-	CLEANING & RESEALING JOINTS- EXISTING CONCRETE PAVEMENT:REHAB	LF	25.000		25.000
		0350- 78-	CLEANING & SEALING RANDOM CRACKS IN EXISTING CONCRETEPAVEMENT- REHAB	LF	25.000		25.000
		0353- 70-	CONCRETE PAVEMENT SLAB REPLACEMENT	CY	15.000		15.000
		0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	125.000		125.000
		0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	125.000		125.000
T		0431- 1- 1	PIPE LINER, OPTIONAL MATERIAL, 0-24"	LF	35.000		35.000
T		0431- 1- 2	PIPE LINER, OPTIONAL MATERIAL, 25-36"	LF	20.000		20.000
		0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	30.000		30.000
		0522- 2-	SIDEWALK CONCRETE, 6" THICK	SY	30.000		30.000
		0711- 11-111	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	NM	0.100		0.100
		0711- 11-131	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.100		0.100
		0711- 11-211	THERMOPLASTIC, STANDARD,YELLOW, SOLID, 6"	NM	0.100		0.100
		0711- 11-231	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	GM	0.100		0.100