



# FLORIDA DEPARTMENT OF TRANSPORTATION

## ADDENDUM NO. 2

For

### FDOT DISTRICT SEVEN ADMINISTRATION BUILDING ROOF REPLACEMENT Project Number 43378215201 and 43378215202 Contract # E7J09

FDOT "FCO" Program

DATED: NOVEMBER 8, 2013

#### GENERAL

**A Revised Bid Blank form has been provided with this addendum. The following language has been added to the Bid Blank form:** An allowance of 500 sheets (based on 4' x 8' sheets per Specification Section 07 21 13 – COMPOSITE BOARD INSULATION ) for removal and replacement of existing damaged composite board underlayment shall be included in the Lump Sum Bid Amount. In addition, Bidders shall include a line item indicating the "per sheet" cost (materials and labor) of replacement board for the Department's use for any additions or deducts which may be required.

#### DRAWING SHEETS

##### DRAWING SHEET AA-103

Under LEGEND; **ADD** the following to Asphalt Shingle Roofing description:

"Clarify: 2 x 4 wood sleepers shall be installed vertically (perpendicular to gutter) at 24" on center over the entire asphalt shingle roof area with 7/16" OSB to allow space for venting of asphalt roofing shingle system substrate. 3-inch slots shall be provided in the OSB board between the wood sleepers at the roof edge as shown on Detail A1 of Drawing Sheet AA-401 for the purpose of conveying the venting through the edge of the roof. The sleepers shall terminate at the hip to permit venting through the ridge vent as shown on Detail C1 on Drawing Sheet AA-400."

**DRAWING SHEET AA-401**

At Details A1 and C1; **REVISE** thickness of gutters from 16 gauge to **22 gauge**.

**TECHNICAL SPECIFICATIONS**

**SECTION 01 11 00 –SUMMARY OF WORK**

**ADD** the following Paragraphs “D.” and “E.” to Item 1.01 – PROJECT DESCRIPTION:

- “D. For informational purposes, the thickness of the existing composite insulation board is 3-inches. The board is composed of 1/2-inch OSB and 2-1/2 inches of polyisocyanurate insulation.”
- “E. Provide Contractor’s Warranty for a period of two (2) years from date of Final Acceptance inclusive of all roofing work.”

**SECTION 01 12 16 – PHASING, SEQUENCING, AND WORK RESTRICTIONS**

Under Item 1.05 WORK PHASING, Paragraphs “B.” and “C.”; **REVISE** the number of Calendar Days for completion from 90 Calendar Days to **130 Calendar Days**. Note that this revision supersedes all references to project completion time specified elsewhere in the Contract Documents.

**SECTION 07 31 13 – ASPHALT SHINGLES**


Under Item 2.01 GLASS-FIBER-REINFORCED ASPHALT SHINGLES, Paragraph “A.”; **DELETE** the “Cool Roof” requirement.

Under Item 2.06 ASPHALT SHINGLE INSTALLATION, Paragraph “F.”; **DELETE** Subparagraphs “1.” And “2.” Installation shall be in accordance with manufacturer’s written instructions and in compliance with code requirements as stated.

**SECTION 07 54 19 – POLYVINYL-CHLORIDE (PVC) MEMBRANE ROOFING**

Under Item 2.01 POLYVINYL-CHLORIDE (PVC) ROOFING MEMBRANE, Paragraph “A.”, Subparagraph “3.”; **ADD** the exposed face color to be “**Tan.**”

Approved by

  
\_\_\_\_\_  
John D. Ellis  
District Contracts Administrator

## BID PROPOSAL

Bidder's Firm Name: \_\_\_\_\_

Address: \_\_\_\_\_

Vendor Number (FEID #) \_\_\_\_\_ Contact Person \_\_\_\_\_

E-mail Address \_\_\_\_\_ Telephone #: ( ) \_\_\_\_\_

FOR CONSTRUCTION OR RENOVATION OF THE FOLLOWING BUILDING PROJECT:

Financial Project Number: 433782-1-52-01 Contract Number E7J09

Project Name: District Seven Headquarters, Administration Building, Roof Replacement and Parking Lot Drainage Improvements

Project Location: 11201 N. McKinley Drive, Tampa, FL 33612

County: Hillsborough Date Submitted: \_\_\_\_\_

**TO THE STATE OF FLORIDA, DEPARTMENT OF TRANSPORTATION:**

The Bidder hereby declares that no person or persons, firm, or corporation, other than the Bidder, is interested in this proposal, as principals, and that this Proposal is made without collusion with any person, firm, or corporation, and have carefully and to our full satisfaction examined the drawings, specifications (Technical and Non-Technical), and all other related contract documents, made a full examination of the location of the proposed work and the sources of supply of materials, agree to furnish all necessary labor, equipment, and materials, fully understanding that the quantities shown herewith are approximate only, and that we will fully complete all necessary work in accordance with Plans and Specifications, and all requirements of the Owner, within the time limit specified in contract documents.

I (We) hereby acknowledge receipt of the following Addenda issued during the bidding period.					
Addendum No.	Dated	Initial	Addendum No.	Dated	Initial
1	10/30/2013				
2	11/08/2013				

Base Bid for Roof \_\_\_\_\_ (Dollars), \$ \_\_\_\_\_

With foregoing as a Base Bid, the following costs of alternate proposals, if any, are submitted in accordance with the drawings and specifications.

Alternate #	Description of Alternate	Unit Price per 4'x8' Composition Board
1	<u>Replacement of OSB/Insulation Composition Boards</u> Base Bid includes An allowance of 500 sheets (based on 4' x 8' sheets per Specification Section 07 21 13 – COMPOSITE BOARD INSULATION ) for removal and replacement of existing damaged composite board underlayment shall be included in the Lump Sum Bid Amount. In addition, Bidders shall include a line item indicating the "per sheet" cost (materials and labor) of replacement board for the Department's use for any additions or deducts which may be required.	

Bid for Drainage Project \_\_\_\_\_ (Dollars), \$ \_\_\_\_\_

**\*Project Total \_\_\_\_\_ (Dollars), \$ \_\_\_\_\_**

\*The Project Total is equal to the Base Bid for Roof and Bid for Drainage Project  
 Selection will be based on the lowest bid for "Project Total." The Department reserves the right to remove the "Drainage Project" Work.