FLORIDA'S TURNPIKE ENTERPRISE

Operates the statewide Turnpike System as part of the Florida Department of Transportation

CHARLIE CRIST
Governor

STEPHANIE C. KOPELOUSOS
Secretary of Transportation

JAMES L. ELY
Executive Director

Turnpike Headquarters:
Milepost 263, Bldg. 5315
Turkey Lake Service Plaza
Ocoee, FL 34761

Mailing Address:
P.O. Box 613069
Ocoee, FL 34761

Tel: 407.532.3999

www.floridasturnpike.com

ADDENDUM NO. 2

DATE: June 4, 2010

TO: PROSPECTIVE BIDDERS

FROM: Richard M. Nethercote, Jr.,
District Contracts Administrator
Florida's Turnpike Enterprise

SUBJECT:

CONTRACT NO.:	**E8K52**
FINANCIAL PROJECT NOS.:	**190736-1-93-06**
COUNTIES:	**Miami-Dade, Palm Beach, St. Lucie, Broward**
PROJECT NAME:	**HVAC Replacement**

BIDS TO BE RECEIVED: June 15, 2010 at 2:30 P.M. Local Time.

Proposers and other interested parties are informed that the above referenced documents are hereby revised, changed and supplemented as set forth below:

APPENDIX "A" - SCOPE OF SERVICES

Appendix "A" is modified as follows:

- 3.0, K; Delete the term "stainless steel" and replace with "galvanized".
- 3.0, P is deleted and the following substituted:

  The Contractor shall provide a one (1) year labor, material and equipment warranty for each HVAC system furnished and installed, which shall begin on the start-up date of each individual unit. The Contractor shall provide a five (5) year compressor part warranty which shall begin on the start-up date of each individual unit.

APPENDIX "B" – HVAC EQUIPMENT TO BE REPLACED

Appendix "B" is modified as follows:

- Item No.19A is hereby added to indicate that there are two (2) 15 ton condenser units and one (1) 30 ton air handler unit at the Snapper Creek service Plaza FHP Admin Building. See revised Appendix B, attached herewith.

NEW EXPEDITE FILE

If you are a **PROPOSAL** HOLDER, a new Expedite File (.EBS file) will be sent via email to use when preparing your bid for this project, for those who intend to bid electronically. Please discard the previously issued Expedite File for this project.

If you are a PROPOSAL HOLDER, who intends to submit a hardcopy bid, please acknowledge receipt of this Addendum on Page 1 of the Form 375-020-08 of your Proposal, and return with your bid.

If you have any questions regarding this information, please do not hesitate to contact Rich Nethercote at the same number as shown above, ext. 3885.

Attachment

Appendix "B" - HVAC Equipment to be Replaced

No.	M.P.	Location	Bldg. No.	Quantity	Manufacturer Condenser/Air Handler	Unit	Model# Condenser	Serial # Condenser	Unit	Model# Air Handler	Serial # Air Handler	Ton	BTU	PH	Volts
Furnish and Install															
Turnpike Mainline (SR 91)															
1	152	FORT PIERCE COMM TOWER BUILDING	4201	1	CARRIER/RUUD	CU1	38CKBO30300	1296214794	AH1	UEPB1410BFS	TM23813118	2.5	18,000	1	208
2	109	PALM BEACH GARDENS TOLL PLAZA	4502	1	CARRIER/RUUD	CU1	24ABR360A350	2607000	AH1	UBEA24J11SFEA1	M089931425	3	19,000	1	208
3	93	LAKE WORTH TOLL PLAZA - RECORDER ROOM	4500	1	CARRIER	CU2	38CKCO24330	2998E12454	AH2	FA4ANC024	0599A15748	2	18,000	1	208
4	93	LAKE WORTH TOLL PLAZA - BOOTH 2	4500	1	CARRIER	PU	50SS018301					2	18,000	1	208
5	93	LAKE WORTH TOLL PLAZA - BOOTH 3	4500	1	CARRIER	PU	50SS018301					2	18,000	1	208
6	93	LAKE WORTH TOLL PLAZA - BOOTH 4	4500	1	CARRIER	PU	50SS018301					2	18,000	1	208
7	88	LANTANA TOLL PLAZA - BOOTH 1	4468	1	CARRIER	PU	50SS018301					2	18,000	1	208
8	88	LANTANA TOLL PLAZA - BOOTH 14	4468	1	CARRIER	PU	50SS018301					2	18,000	1	208
9	88	LANTANA TOLL PLAZA - BOOTH 15	4468	1	CARRIER	PU	50SS018301					2	18,000	1	208
10	88	LANTANA TOLL PLAZA - BOOTH 16	4468	1	CARRIER	PU	50SS018301					2	18,000	1	208
11	81	DELRAY BEACH EAST TOLL PLAZA RECORDER ROOM	4170	1	CARRIER	PU2	50SS0118301	4601G20711				1.5	18,000	1	208
12	81	DELRAY BEACH COMM TOWER BULDING	4171	1	RUUD/RUDD	CU1	UALB030JAZ	5761M339811822	AH1	UEPB1410BFS	TM39823294	2.5	18,00	1	208
13	67	POMPANO BEACH COMM TOWER BUILDING	4167	1	RUDD/RUDD	CU1	UALB024JAZ	2349MO9942239	AH1	RCGA24A1GG14	M31943161	2	24,000	1	208
14	58	SUNRISE FHP POST 3 ADMIN BUILDING	4158	1	CARRIER	PU1	50TFF006V511	4603G10366				5	60,000	1	208
15	58	SUNRISE FHP POST 3 ADMIN BUILDING	4158	1	CARRIER	PU1	50TFF006V511	4603G10366				5	60,000	1	208
16	58	SUNRISE COMM TOWER BUILDING	4156	1	CARRIER/INTER-CITY	CU1	38CK6036351	3103E13712	AH1	H2B536A35	L931045005	3	36,000	1	208
Homestead Extension (SR821)															
17	23	BIRD RD WEST TOLL PLAZA	6028	1	CARRIER	PU2	50TJQ12V501	1199G30477				10	120,000	3	208
18	19	SNAPPER CREEK SERVICE PLAZA - MATERIALS LABORATORY	7121	1	CARRIER	PU3	50TFF008V511	14036130517				7.5	90,000	1	208
19	19	SNAPPER CREEK SERVICE PLAZA - FHP ADMIN BUILDING	6103	1*	CARRIER/CARRIER	CU1	38AH5016-410	1998F41860	AH1	39TFFVAB-V-BAL-AB	3198F60459	30	360,000	3	208
19A	19	SNAPPER CREEK SERVICE PLAZA - FHP ADMIN BUILDING	6103	1*	CARRIER/CARRIER	CU2	38AH5016-410	1998F41860							
Furnish, Deliver and Unload Only (Packaged Units for Stock)															
Turnpike Mainline (SR 91)															
20	99	WEST PALM MAINTENANCE YARD	4180	15	BRYANT	PU	704DNX024					2	18,000	1	208

CU=Conderser Unit AH=Air Handler PU=Package Unit

***Rev1 = FHP Admnin Bldg at Snapper Creek Serv Plaza = There are two condenser units (15 ton each) and one air handler (30 tons).**