

RICK SCOTT GOVERNOR

Florida's Turnpike Enterprise P.O. Box 613069, Ocoee, FL 34761 407-532-3999

JIM BOXOLD SECRETARY

#### ADDENDUM No. 2

DATE:

August 12, 2016

TO:

**PROPOSERS** 

FROM:

Richard M. Nethercote, Jr.

District Contracts Administrator Florida's Turnpike Enterprise

SUBJECT:

Contract No.: E8Q11

Financial Project No: 437156-2-52-01

Counties: Orange

Project Name: Orlando south Interchange Improvements between SR 528, US

441 and SR 91

# BIDS TO BE RECEIVED: August 16, 2016 at 2:30 P.M Local Time

Proposers and other interested parties are informed that the above referenced documents are hereby revised, changed and supplemented as set forth below:

#### PLANS AND PAY ITEM REVISIONS

Plan sheets, Specifications and Pay Items for the above-mentioned project have been revised. Please go to the Online Ordering Web Site at

https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/ to download the Plans Revision from your Order History. See the attached Revision Memo for a complete listing of Plans, Specification, and Pay Item Revisions. Please substitute these sheets for the likenumbered sheets you now have.

### **AMENDMENT NOTIFICATION**

If you are a **BID DOCUMENT HOLDER** for the subject project, please go to the Online Ordering Web Site at <a href="https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/">https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/</a> to download E8Q11Amendment002.zip for this Bid Document from your Order History.

If you are a **BID DOCUMENT HOLDER**, in Expedite Bid open the Acceptance of Bidding Acknowledgements folder to confirm your acknowledgement of Amendment and Addenda Files. Failure to load all amendment files will cause the bid to be rejected.

If you have any questions regarding this information, please do not hesitate to contact Rich Nethercote at 407-264-3885.



RICK SCOTT GOVERNOR

Tallahassee, FL 32399-0450

JIM BOXOLD SECRETARY

# TRANSMITTAL OF CONTRACT ADDENDUM

Contract No.	E8Q11					
Letting	August 2016					
FPID(s)						
Description						
	Orange					
Contract Adden	ndum No. 2 includes:					
✓ Digitall	y signed + sealed Co	ntract Plan Revision 1 (PD	F file)			
		CADD-Rev1.zip file)				
<b>5</b>	(	eribb Revi.zip ine)				
Contract	t time revised No	0 <u>X</u> Yes If	yes,total calendar days			
✓ Addendu construct	m package is complete ability and biddability	e, has no known errors or omis and is ready for distribution t	sions, has been reviewed for contract bidders.			
	Patrick M	Digitally signed by Patrick M Muench DN: c=US, c=IdenTrust ACES Business Representative, ou=FDOT - TURNPIKE, cn=Patrick M				
CONCURRENC	E: Muench	Muench, 0.9.2342.19200300.100.1.1=A01097C0000014504D A5168000038CB Date: 2016.08.12 15:01:22 -04'00'	DATE: Accept 40, 0040			
	Turppile	Design Engineer	August 12, 2016			

Turnpike Design Engineer

# CONTRACT ADDENDUM INCLUDES:

SHEET	DESCRIPTION OF MODIFICATION		
1	Edit Revision 1 sheet index.		
2A	Add signature sheet for Revision 1 Digital Delivery.		
3A thru 3D	Revise Summary of pay items per SQ sheet changes.		
SQ-2	Add Design Note that Rev 1 added Temp Pavement along Ramp X-2 to Special Detour 1 Pay Item.		
SQ-3	Add 600 LF Pay Item 102-71-13 to Phase I-D (TBW, F & I, Low Profile Barrier) Add 320 LF Pay Item 102-71-23 to Phase II (TBW, Relocate, Low Profile Barrier)		
SQ-5	Add Design Note that Rev 1 added Temp Pavement along Ramp X-2 to Special Detour 1 Pay Item.  Revise total from 1435 to 2035 LF Pay Item 102-71-13 (TBW, F & I, Low Profile Barrier).  Revise total from 330 to 650 LF Pay Item 102-71-23 (TBW, Relocate, Low Profile Barrier).		
113	Phase I-B - Show construction of 6 foot wide Temp Pavement from Ramp X-2 BL Station 306+00 to 309+00, to be paid as Special Detour. Extend from outside edge of proposed Ramp 2 Shoulder Pavement. Also shift position of Low Profile Barrier to edge of work zone.		
116	Phase I-C - Show Temporary pavement from 306+00 to 309+00 constructed in Phase I-B.		
118	Phase I-D – Extend work area to 223+80, and add Low Profile Barrier on both sides of work area (Left side Ramp X-2 and Right side Ramp X) from about 221+20 to 223+80. Show Ramp X-2 Partially on new shoulder and new Temp Pavement.		
122	Phase II – Add Low Profile barrier on left side of Ramp X to protect area of reconstruction up to 223+80.		

PAY ITEMS + QUANTITIES (AASHTOWare PrP) - FPID 437156-2 -52-01						
PAY ITEMS	SHEET	ADD / MOD / DEL	OLD QUANTITY	NEW QUANTITY		
102-2-1	SQ-2,5	Modify Special Detour to Add Temp Pavt (200SY)	1	1		
102-71-13	SQ-3,5	Add 600 LF	1435	2035		
102-71-23	SQ-3,5	Add 320 LF	330	650		