



Florida Department of Transportation

RICK SCOTT
GOVERNOR

Florida's Turnpike Enterprise
P.O. Box 613069, Ocoee, FL 34761
407-532-3999

JIM BOXOLD
SECRETARY

ADDENDUM No. 2

DATE: October 18, 2016

TO: PROPOSERS

FROM:  Richard M. Nethercote, Jr.
District Contracts Administrator
Florida's Turnpike Enterprise

SUBJECT: Contract No.: E8Q12
Financial Project Nos.: 411406-1-52-01; 411406-4-52-01; 411406-1-56-01
Counties: Orange and Osceola
Project Name: Turnpike Widening – South of Osceola Parkway to Beachline Exp.

BIDS TO BE RECEIVED: November 15, 2016 at 2:30 P.M Local Time

Proposers and other interested parties are informed that the above referenced documents are hereby revised, changed and supplemented as set forth below:

PLANS AND PAY ITEMS REVISIONS

Plan sheets, Specifications and Pay Items for the above-mentioned project have been revised. Please go to the Online Ordering Web Site at <https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/> to download the Plans Revision from your Order History. See the attached Revision Memo for a complete listing of Plans and Pay Items Revisions. Please substitute these sheets for the like-numbered sheets you now have.

RE-ISSUED SPECIFICATIONS PACKAGE

Please go to the Online Ordering Web Site at <https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/> to download the .PDF file of the re-issued Specification Package, E8Q12Specs_Re-issued, for the above-mentioned Project. This Specification Package replaces the original package provided.

AMENDMENT NOTIFICATION

If you are a **BID DOCUMENT HOLDER** for the subject project, please go to the Online Ordering Web Site at <https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/> to download E8Q12Amendment002.zip for this Bid Document from your Order History.

If you are a **BID DOCUMENT HOLDER**, in Expedite Bid open the Acceptance of Bidding Acknowledgements folder to confirm your acknowledgement of Amendment and Addenda Files. Failure to load all amendment files will cause the bid to be rejected.

If you have any questions regarding this information, please do not hesitate to contact Rich Nethercote at 407-264-3885.



Florida Department of Transportation

RICK SCOTT
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

JIM BOXOLD
SECRETARY

TRANSMITTAL OF CONTRACT ADDENDUM

Contract No. **E8Q12**
 Letting November 2016
 FPID(s) 411406-1-52-01, 411406-1-56-01 + 411406-4-52-01
 Description Turnpike Widening from South of Osceola Parkway to Beachline Expressway
 County Orange + Osceola

Contract Addendum No. 2 includes:

- ✓ Digitally signed + sealed Contract Plans Revision 1 (PDF file) *See Page 2 for details*
- ✓ Digitally signed + sealed Reissued Specifications Package (PDF file)
- ✓ Digitally signed + sealed Geotechnical Engineering for Bridges + Associated MSE Walls – Addendum Report (PDF file)
- ✓ Design + engineering data (CADD .zip file)

Contract Addendum Narrative:

Plan Revision 1 consists of eliminating the 100% dynamic testing and EDC from the bridge piles and the addition of one static load test. The change in testing requirements resulted in modifications to the corresponding phi factor and test pile lengths for all bridges. The pay item numbers and lengths for the piling were also updated in the BQ sheets accordingly.

Contract time revised No X Yes _____ If yes, _____ total calendar days

- ✓ Addendum package is complete, has no known errors or omissions, has been reviewed for constructability and biddability, and is ready for distribution to contract bidders.

CONCURRENCE: **Patrick M Muench**
Digitally signed by Patrick M Muench
 DN: cn=US, o=IdenTrust, ACES Business Representative, ou=FDOT-TURNPIKE, cn=Patrick M Muench,
 0.9.2342.19200300.100.1.1=A01097C0000014504D
 A316800038C8
 Date: 2016.10.18 15:29:51 -0400
 Turnpike Design Engineer

DATE: October 18, 2016

CONTRACT ADDENDUM INCLUDES:

PLAN REVISIONS	
SHEET	DESCRIPTION OF MODIFICATION
1	Added Sheet Number 3A.
3A	Added Sheet.
4	Removed pay items 455-34-105 and 455-143-105, added pay items 455-34-5 and 455-143-5, modified pay item 455-199-103.
5	Removed pay items 455-34-105 and 455-143-105, added pay items 455-34-5 and 455-143-5.
6	Removed pay items 455-34-105 and 455-143-105, added pay items 455-34-5 and 455-143-5, modified pay item 455-199-103.
B-1	Show revised sheets.
B-7A	Added Sheet.
B-8	Changes to phi factor due to removal of 100% dynamic load testing of production piles.
B-9	Changes to phi factor due to removal of 100% dynamic load testing of production piles.
B-10	Changes to phi factor due to removal of 100% dynamic load testing of production piles.
B-11	Changes to phi factor due to removal of 100% dynamic load testing of production piles.
BQ1-1	Removed pay items 455-34-105 and 455-143-105, added pay items 455-34-5 and 455-143-5
BQ2-1	Removed pay items 455-34-105 and 455-143-105, added pay items 455-34-5 and 455-143-5
BQ2-2	Removed pay items 455-34-105 and 455-143-105, added pay items 455-34-5 and 455-143-5
BQ3-1	Removed pay items 455-34-105 and 455-143-105, added pay items 455-34-5 and 455-143-5
BQ4-1	Removed pay items 455-34-105 and 455-143-105, added pay items 455-34-5 and 455-143-5
BQ6-1	Removed pay items 455-34-105 and 455-143-105, added pay items 455-34-5 and 455-143-5
BQ7-1	Removed pay items 455-34-105 and 455-143-105, added pay items 455-34-5 and 455-143-5
BQ7-2	Removed pay items 455-34-105 and 455-143-105, added pay items 455-34-5 and 455-143-5
BQ8-1	Removed pay items 455-34-105 and 455-143-105, added pay items 455-34-5, 455-143-5 and 455-119-103.
B-17	Revised pay item footnote for static load test pile
B1-15	Changes to phi factor due to removal of 100% dynamic load testing of production piles.
B2-10	Changes to phi factor due to removal of 100% dynamic load testing of production piles. Changes to static load test pile load value.
B2-11	Changes to phi factor due to removal of 100% dynamic load testing of production piles.
B3-20	Changes to phi factor due to removal of 100% dynamic load testing of production piles.
B4-18	Changes to phi factor due to removal of 100% dynamic load testing of production piles.
B6-13	Changed test pile location at End Bent 2
B6-14	Changes to phi factor due to removal of 100% dynamic load testing of production piles.
B7-9	Changes to phi factor due to removal of 100% dynamic load testing of production piles. Changes to static load test pile load value.
B8-01	Clarification of boring locations
B8-09	Changes to phi factor due to removal of 100% dynamic load testing of production piles. Added static load test.

PAY ITEMS + QUANTITIES (AASHTOWare PrP) – FPID 411406-1-52-01

PAY ITEMS	SHEET	ADD / MOD / DEL	BR#	OLD QUANTITY	NEW QUANTITY
455-119-103	4	MOD	750641	0	1
455-34-105	4	DEL	750611	12984	-
455-34-105	4	DEL	750641	3832	-
455-34-105	4	DEL	750642	2760	-
455-34-105	4	DEL	750643	3840	-
455-143-105	4	DEL	750611	918	-
455-143-105	4	DEL	750641	379	-
455-143-105	4	DEL	750642	214	-
455-143-105	4	DEL	750643	363	-
455-34-5	4	ADD	750611	-	14000
455-34-5	4	ADD	750641	-	4135
455-34-5	4	ADD	750642	-	2940
455-34-5	4	ADD	750643	-	4100
455-143-5	4	ADD	750611	-	974
455-143-5	4	ADD	750641	-	505
455-143-5	4	ADD	750642	-	226
455-143-5	4	ADD	750643	-	247
455-34-105	5	DEL	750644	11433	-
455-34-105	5	DEL	754169	2848	-
455-34-105	5	DEL	754170	2664	-
455-34-105	5	DEL	754171	3544	-
455-34-105	5	DEL	754172	3544	-
455-143-105	5	DEL	750644	910	-
455-143-105	5	DEL	754169	134	-
455-143-105	5	DEL	754170	430	-
455-143-105	5	DEL	754171	503	-
455-143-105	5	DEL	754172	397	-
455-34-5	5	ADD	750644	-	12420
455-34-5	5	ADD	754169	-	3060
455-34-5	5	ADD	754170	-	2865
455-34-5	5	ADD	754171	-	3766
455-34-5	5	ADD	754172	-	3766
455-143-5	5	ADD	750644	-	966
455-143-5	5	ADD	754169	-	143
455-143-5	5	ADD	754170	-	454
455-143-5	5	ADD	754171	-	520
455-143-5	5	ADD	754172	-	414
455-34-105	6	DEL	-	47449	-
455-143-105	6	DEL	-	4248	-
455-34-5	6	ADD	-	-	51052
455-119-103	6	MOD	-	3	4
455-143-5	6	ADD	-	-	4449