FLORIDA DEPARTMENT OF TRANSPORTATION
PROPOSAL SUMMARY OF PAY ITEMS

PROPOSAL : E8J28 LEAD PROJECT : 41957815201 COUNTY : MIAMI-DADE , MANDIST: 08
PROJECT(S): 41957815201 COUNTY/SECTION: 87471000 ,
41957835201 87471000

0001 SUMMARY OF ROADWAY PAY ITEMS

S P C T

ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41957815201	41957835201	QUANTITY TOTAL
	0101- 1-	MOBILIZATION	LS	1.000	0.000	1.000
	0101- 1-	MOBILIZATION	LS	0.000	1.000	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000	0.000	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	0.000	1.000	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	MH	1520.000	592.000	2112.000
	0102- 60-	WORK ZONE SIGN	ED	3845.000	4560.000	8405.000
	0102- 71- 14	BARRIER WALL, TEMPORARY, F&I, TYPE K	LF	0.000	125.000	125.000
	0102- 71- 24	BARRIER WALL, TEMPORARY, RELOCATE, TYPE K	LF	0.000	4500.000	4500.000
	0102- 74- 1	BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	ED	16320.000	19335.000	35655.000
	0102- 74- 2	BARRICADE, TEMPORARY, TYPE III, 6'	ED	230.000	148.000	378.000
	0102- 76-	ADVANCE WARNING ARROW PANEL	ED	115.000	74.000	189.000
	0102- 77-	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	2040.000	2101.000	4141.000
	0102- 78-	REFLECTIVE PAVEMENT MARKER,TEMPORARY	EA	5265.000	0.000	5265.000
	0102- 79-	LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C,STEADY BURN	ED	0.000	925.000	925.000
	0102- 89- 7	CRASH CUSHION/IMPACT ATTENUATOR, TEMPORARY, REDIRECTIVE OPTION	LO	0.000	37.000	37.000
	0102- 99-	CHANGEABLE-VARIABLE MESSAGE SIGN, TEMPORARY	ED	261.000	262.000	523.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	230.000	74.000	304.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	230.000	74.000	304.000
	0104- 10- 2	SYNTHETIC BALES	LF	1296.000	50.000	1346.000
	0104- 13- 1	STAKED SILT FENCE, TYPE III	LF	0.000	19915.000	19915.000
	0104- 16-	ROCK BAG	EA	2060.000	0.000	2060.000
	0110- 1- 1	CLEARING & GRUBBING	LS	0.000	1.000	1.000
	0120- 1-	REGULAR EXCAVATION	CY	0.000	1277.000	1277.000
	0120- 6-	EMBANKMENT	CY	0.000	496.600	496.600
	0160- 4-	TYPE B STABILIZATION	SY	0.000	4727.000	4727.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	0.000	5676.000	5676.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	0.000	2809.000	2809.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	78145.000	0.000	78145.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	2332.000	0.000	2332.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	161052.000	0.000	161052.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	4619.000	0.000	4619.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	88314.000	0.000	88314.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	55913.000	0.000	55913.000
	0327- 70- 16	MILLING EXIST ASPH PAVT, 1/2" AVG DEPTH	SY	34773.000	0.000	34773.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	59781.000	0.000	59781.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	1119.800	243.300	1363.100
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	9768.600	0.000	9768.600
	0334- 1- 23	SUPERPAVE ASPH CONC, TRAF C, PG76-22	TN	3437.700	0.000	3437.700
	0334- 1- 24	SUPERPAVE ASPH CONC, TRAF D, PG76-22	TN	27505.900	0.000	27505.900
	0337- 7- 22	ASPH CONC FRICTION COURSE, INC BIT, FC-5, PG76-22	TN	13867.300	0.000	13867.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	822.500	86.100	908.600
	0400- 2- 15	CONCRETE CLASS II, MISCELLANEOUS	CY	0.000	45.500	45.500

PROPOSAL : E8J28 LEAD PROJECT : 41957815201 COUNTY : MIAMI-DADE , MANDIST: 08
PROJECT(S): 41957815201 COUNTY/SECTION: 87471000 ,
41957835201 87471000

0001 SUMMARY OF ROADWAY PAY ITEMS CONTINUED

S P C

ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41957815201	41957835201	QUANTITY TOTAL
	0430-175-101	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 0-24"S/CD	LF	0.000	78.000	78.000
	0430-602-125	U-ENDWALL, WITH GRATE,STD 260, 1:4 SLOPE, 18"	EA	0.000	16.000	16.000
	0430-602-129	U-ENDWALL, WITH GRATE,STD 260, 1:4 SLOPE, 24"	EA	0.000	4.000	4.000
	0536- 1- 1	GUARDRAIL -ROADWAY	LF	0.000	3075.000	3075.000
	0536- 8-	GUARDRAIL- BRIDGE ANCHORAGE ASSEMBLY (FURNISH & INSTALL)	EA	0.000	37.000	37.000
	0536- 73-	GUARDRAIL REMOVAL	LF	0.000	2200.000	2200.000
	0536- 85- 22	GUARDRAIL END ANCHORAGE ASSEMBLY- FLARED	EA	0.000	20.000	20.000
	0536- 85- 25	GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE II	EA	0.000	1.000	1.000
	0546- 72- 51	RUMBLE STRIPS, GROUND-IN, 16" MIN. WIDTH	PM	30.600	0.000	30.600
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	8802.000	5676.000	14478.000
	0710- 11-111	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	NM	50.442	0.000	50.442
	0710- 11-112	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	NM	8.192	0.000	8.192
	0710- 11-114	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 18"	NM	2.472	0.000	2.472
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 12"	LF	3392.000	0.000	3392.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	LF	336.000	0.000	336.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP 6"	GM	40.564	0.000	40.564
	0710- 11-133	PAINTED PVMT MARK, STANDARD, WHITE, SKIP, 12"	GM	0.160	0.000	0.160
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	EA	50.000	0.000	50.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	58.000	0.000	58.000
	0710- 11-211	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	NM	49.116	1.343	50.459
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 18"	LF	86.000	0.000	86.000
	0999- 16-	PARTNERING, DO NOT BID	LS	1.000	0.000	1.000
	0999- 20-	DISPUTES REVIEW BOARD, DO NOT BID	DA	10.000	0.000	10.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000	0.000	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	0.000	1.000	1.000

PROPOSAL : E8J28 LEAD PROJECT : 41957815201 COUNTY : MIAMI-DADE , MANDIST: 08
PROJECT(S): 41957815201 COUNTY/SECTION: 87471000 ,
41957835201 87471000

0002 SUMMARY OF SIGNING

S P C

PAY ITEMS

ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	41957815201	41957835201	QUANTITY TOTAL
	0555- 1- 1	DIRECTIONAL BORE, LESS THAN 6"	LF	60.000	0.000	60.000
	0630- 1- 12	CONDUIT - SIGNALS, FURNISH & INSTALL, UNDERGROUND	LF	125.000	0.000	125.000
	0635- 1- 11	PULL & JUNCTION BOXES, F&I, PULL BOX	EA	3.000	0.000	3.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	7.000	0.000	7.000
	0700- 20- 11	SINGLE POST SIGN, F&I, LESS THAN 12 SF	AS	0.000	3.000	3.000
	0700- 21- 13	MULTI- POST SIGN, F&I, 101 - 150 SF	AS	0.000	1.000	1.000
	0700- 21- 15	MULTI- POST SIGN, F&I, 201 - 250 SF	AS	0.000	1.000	1.000
	0700- 21- 60	MULTI- POST SIGN, REMOVE	AS	0.000	2.000	2.000
	0700- 48- 18	SIGN PANELS, F & I, 15 OR <	EA	0.000	7.000	7.000
	0700- 48- 58	SIGN PANELS, REPLACE, 15 OR LESS	EA	0.000	14.000	14.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	342.000	0.000	342.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	1.000	0.000	1.000
	0711- 17-	THERMOPLASTIC, REMOVE	SF	10935.000	0.000	10935.000
	0741- 70-111	TMS VEHICLE SENSOR, CLASS II, F&I, TYP 1, 1/2 LN	EA	4.000	0.000	4.000
	0745- 70- 12	TMS INDUCTIVE LOOP ASSEM, F&I, 2 LOOPS / LANE	AS	4.000	0.000	4.000