FLORIDA DEPARTMENT OF TRANSPORTATION
PROPOSAL SUMMARY OF PAY ITEMS

PROPOSAL : E8J56 LEAD PROJECT : 42320115201 COUNTY : BROWARD , MANDIST: 08
PROJECT(S): 42320115201 COUNTY/SECTION: 86470000 ,

0001 SUMMARY OF ROADWAY PAY ITEMS

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	42320115201		QUANTITY TOTAL
		0101- 1-	MOBILIZATION (42320115201)	LS	1.000		1.000
		0102- 1-	MAINTENANCE OF TRAFFIC (42320115201)	LS	1.000		1.000
T		0102- 14-	TRAFFIC CONTROL OFFICER	MH	420.000		420.000
		0102- 60-	WORK ZONE SIGN	ED	475.000		475.000
		0102- 74- 1	BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	ED	4520.000		4520.000
		0102- 76-	ADVANCE WARNING ARROW PANEL	ED	90.000		90.000
		0102- 77-	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	135.000		135.000
		0102- 78-	REFLECTIVE PAVEMENT MARKER,TEMPORARY	EA	1260.000		1260.000
		0102- 99-	CHANGEABLE-VARIABLE MESSAGE SIGN, TEMPORARY	ED	86.000		86.000
		0102-150- 1	PORTABLE REGULATORY, SIGN	ED	90.000		90.000
		0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	90.000		90.000
		0104- 16-	ROCK BAG	EA	140.000		140.000
		0210- 1- 9	REWORKING LIMEROCK BASE, 3"	SY	1488.000		1488.000
		0210- 2-	LIMEROCK-NEW MATERIAL FOR REWORKING BASE	CY	62.000		62.000
		0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	38952.000		38952.000
		0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	6578.000		6578.000
		0334- 1- 23	SUPERPAVE ASPH CONC, TRAF C, PG76-22	TN	2224.200		2224.200
		0337- 7- 22	ASPH CONC FRICTION COURSE, INC BIT, FC-5, PG76-22	TN	1902.900		1902.900
		0546- 72- 51	RUMBLE STRIPS, GROUND-IN, 16" MIN. WIDTH	PM	0.300		0.300
		0710- 11-111	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	NM	2.584		2.584
		0710- 11-122	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	LF	2543.000		2543.000
		0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 18"	LF	508.000		508.000
		0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP 6"	GM	6.215		6.215
		0710- 11-142	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP 8"	LF	2957.000		2957.000
		0710- 11-211	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	NM	2.635		2.635
		0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42320115201)	LS	1.000		1.000

PROPOSAL : E8J56 LEAD PROJECT : 42320115201 COUNTY : BROWARD , MANDIST: 08
PROJECT(S): 42320115201 COUNTY/SECTION: 86470000 ,

0002 SUMMARY OF SIGNING

PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	42320115201		QUANTITY TOTAL
		0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42320115201)	LS	1.000		1.000