PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0001 SUMMARY OF STRUCTURES PAY ITEMS

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201 BR # 100539	43127515201 BR # 100545	43127515201 BR # 100636
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	1.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	1.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	1.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0400- 2- 4	CONC CLASS II, SUPERSTRUCTURE	CY	142.400	285.900	288.700
		0400- 2- 5	CONCRETE CLASS II, SUBSTRUCTURE	CY	93.500	0.000	0.000
		0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	119.100	46.400	99.700
		0400- 4- 5	CONCRETE CLASS IV, SUBSTRUCTURE	CY	0.000	85.200	65.400
		0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	0.000	0.000	209.000
		0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	791.000	1153.000	0.000
		0400- 9-	BRIDGE DECK GROOVING & PLANING, DECK 8.5"&>	SY	0.000	0.000	1069.000
		0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	0.000	2801.000	0.000
		0400-147-	COMPOSITE NEOPRENE PADS	CF	1.500	8.500	14.300
		0415- 1- 4	REINFORCING STEEL - SUPERSTRUCTURE	LB	38710.000	58442.000	67549.000
		0415- 1- 5	REINFORCING STEEL- SUBSTRUCTURE	LB	15947.000	10070.000	62990.000
		0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	23971.000	7972.000	19309.000
		0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	0.000	1040.000	0.000
		0450- 2- 45	PREST BEAMS: FLORIDA-I BEAM 45"	LF	316.000	0.000	1173.000
		0450- 2- 54	PREST BEAMS: FLORIDA-I BEAM 54"	LF	115.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	1.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	1.000
		0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	420.000	676.000	0.000
		0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	0.000	0.000	2835.000
		0455- 35- 20	STEEL PILING, 18" DIA. PIPE	LF	0.000	1220.000	0.000
		0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	0.000	0.000	8391.000
		0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	155.000	210.000	0.000
		0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	0.000	0.000	445.000
		0455-144- 20	TEST PILES - STEEL, 18" DIA PIPE	LF	0.000	230.000	0.000
		0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&IPOURED JOINT WITH BACKER ROD	LF	0.000	0.000	82.000
		0458- 1- 12	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&ISTRIP SEAL	LF	145.000	52.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0001 SUMMARY OF STRUCTURES PAY ITEMS CONTINUED

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201 BR # 100539	43127515201 BR # 100545	43127515201 BR # 100636
	0458- 1- 22	BRIDGE DECK EXPANSION JOINT, REHABILITATION, STRIP SEAL	LF	147.000	0.000	0.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	69.000	0.000	181.000
	0460- 2- 2	STRUCT STEEL, LOW ALLOY (43127515201)	LS	0.000	0.000	0.000
	0506- 2-	BRIDGE DRAINAGE PIPE	LF	0.000	0.000	0.000
	0506- 3-	BRIDGE DRAINS	EA	0.000	0.000	0.000
	0521- 5- 1	CONCRETE TRAFFIC RAILING, BRIDGE 32" F - SHAPE	LF	320.000	393.000	595.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT,NON REINFORCED, 4"	SY	6.000	0.000	34.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	0.000	0.000	0.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43127515201)	LS	0.000	1.000	0.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43127515201)	LS	0.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0001 SUMMARY OF STRUCTURES PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UN IT	43127515201 BR # 100541	43127515201 BR # 100546	43127515201 BR # 100538
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	1.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	1.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	1.000	0.000
		0400- 2- 4	CONC CLASS II, SUPERSTRUCTURE	CY	345.600	130.500	148.900
		0400- 2- 5	CONCRETE CLASS II, SUBSTRUCTURE	CY	0.000	0.000	54.700
		0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	75.000	56.700	120.600
		0400- 4- 5	CONCRETE CLASS IV, SUBSTRUCTURE	CY	287.400	132.300	0.000
		0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	0.000	0.000	0.000
		0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	1398.000	690.000	808.000
		0400- 9-	BRIDGE DECK GROOVING & PLANING, DECK 8.5"&>	SY	0.000	0.000	0.000
		0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	11612.000	5943.000	0.000
		0400-147-	COMPOSITE NEOPRENE PADS	CF	22.800	7.500	1.500
		0415- 1- 4	REINFORCING STEEL - SUPERSTRUCTURE	LB	94122.000	35770.000	40889.000
		0415- 1- 5	REINFORCING STEEL- SUBSTRUCTURE	LB	58188.000	24916.000	9857.000
		0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	15138.000	10642.000	25309.000
		0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	710.000	547.000	0.000
		0450- 2- 45	PREST BEAMS: FLORIDA-I BEAM 45"	LF	0.000	0.000	104.000
		0450- 2- 54	PREST BEAMS: FLORIDA-I BEAM 54"	LF	442.000	0.000	306.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	1.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	1.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	1.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
		0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	2855.000	1735.000	309.000
		0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	0.000	0.000	0.000
		0455- 35- 20	STEEL PILING, 18" DIA. PIPE	LF	0.000	0.000	0.000
		0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	16115.000	3987.000	0.000
		0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	234.000	385.000	118.000
		0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	0.000	0.000	0.000
		0455-144- 20	TEST PILES - STEEL, 18" DIA PIPE	LF	0.000	0.000	0.000
		0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&IPOURED JOINT WITH BACKER ROD	LF	0.000	0.000	0.000
		0458- 1- 12	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&ISTRIP SEAL	LF	94.000	70.000	150.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0001 SUMMARY OF STRUCTURES PAY ITEMS CONTINUED

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201 BR # 100541	43127515201 BR # 100546	43127515201 BR # 100538
	0458- 1- 22	BRIDGE DECK EXPANSION JOINT, REHABILITATION, STRIP SEAL	LF	110.000	77.000	113.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	14.000	131.000	85.000
	0460- 2- 2	STRUCT STEEL, LOW ALLOY (43127515201)	LS	0.000	0.000	0.000
	0506- 2-	BRIDGE DRAINAGE PIPE	LF	0.000	0.000	0.000
	0506- 3-	BRIDGE DRAINS	EA	0.000	0.000	0.000
	0521- 5- 1	CONCRETE TRAFFIC RAILING, BRIDGE 32" F - SHAPE	LF	663.000	178.000	348.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT,NON REINFORCED, 4"	SY	916.000	268.000	3.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	0.000	0.000	0.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43127515201)	LS	0.000	0.000	0.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43127515201)	LS	0.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0001 SUMMARY OF STRUCTURES — PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UN IT	43127515201 BR # 100540	43127515201 BR # 100547	43127515201 BR # 100635
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	1.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	1.000	0.000	0.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000	0.000	0.000
		0400- 2- 4	CONC CLASS II, SUPERSTRUCTURE	CY	345.600	111.700	188.100
		0400- 2- 5	CONCRETE CLASS II, SUBSTRUCTURE	CY	0.000	0.000	61.800
		0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	79.700	46.300	86.200
		0400- 4- 5	CONCRETE CLASS IV, SUBSTRUCTURE	CY	198.400	119.300	0.000
		0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	0.000	0.000	0.000
		0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	1437.000	582.000	0.000
		0400- 9-	BRIDGE DECK GROOVING & PLANING, DECK 8.5"&>	SY	0.000	0.000	802.000
		0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	9718.000	9205.000	0.000
		0400-147-	COMPOSITE NEOPRENE PADS	CF	22.800	5.700	5.700
		0415- 1- 4	REINFORCING STEEL - SUPERSTRUCTURE	LB	94957.000	30975.000	44448.000
		0415- 1- 5	REINFORCING STEEL- SUBSTRUCTURE	LB	38917.000	22715.000	13628.000
		0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	15619.000	9004.000	15454.000
		0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	705.000	410.000	0.000
		0450- 2- 45	PREST BEAMS: FLORIDA-I BEAM 45"	LF	0.000	0.000	0.000
		0450- 2- 54	PREST BEAMS: FLORIDA-I BEAM 54"	LF	442.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	1.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	1.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	1.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000	0.000	0.000
		0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	1837.000	1840.000	910.000
		0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	0.000	0.000	0.000
		0455- 35- 20	STEEL PILING, 18" DIA. PIPE	LF	0.000	0.000	0.000
		0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	10365.000	4659.000	0.000
		0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	157.000	115.000	212.000
		0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	0.000	0.000	0.000
		0455-144- 20	TEST PILES - STEEL, 18" DIA PIPE	LF	0.000	0.000	0.000
		0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&IPOURED JOINT WITH BACKER ROD	LF	0.000	0.000	64.000
		0458- 1- 12	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&ISTRIP SEAL	LF	95.000	59.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0001 SUMMARY OF STRUCTURES PAY ITEMS CONTINUED

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201 BR # 100540	43127515201 BR # 100547	43127515201 BR # 100635
	0458- 1- 22	BRIDGE DECK EXPANSION JOINT, REHABILITATION, STRIP SEAL	LF	90.000	77.000	0.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	87.000	0.000	195.000
	0460- 2- 2	STRUCT STEEL, LOW ALLOY (43127515201)	LS	0.000	0.000	1.000
	0506- 2-	BRIDGE DRAINAGE PIPE	LF	105.000	0.000	0.000
	0506- 3-	BRIDGE DRAINS	EA	1.000	0.000	0.000
	0521- 5- 1	CONCRETE TRAFFIC RAILING, BRIDGE 32" F - SHAPE	LF	685.000	178.000	535.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT,NON REINFORCED, 4"	SY	506.000	257.000	25.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	0.000	0.000	0.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43127515201)	LS	0.000	0.000	0.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43127515201)	LS	0.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0001 SUMMARY OF STRUCTURES PAY ITEMS

S P C	ALT	ITEM NUMBER	ITEM DESCRIPTION	UN IT	43127515201 BR # 100544		QUANTITY TOTAL
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000		1.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000		1.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	1.000		1.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000		1.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000		1.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000		1.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000		1.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000		1.000
		0110- 3-	REMOVAL OF EXISTING STRUCTURE (43127515201)	LS	0.000		1.000
		0400- 2- 4	CONC CLASS II, SUPERSTRUCTURE	CY	385.300		2372.700
		0400- 2- 5	CONCRETE CLASS II, SUBSTRUCTURE	CY	0.000		210.000
		0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	55.600		785.300
		0400- 4- 5	CONCRETE CLASS IV, SUBSTRUCTURE	CY	109.700		997.700
		0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	0.000		209.000
		0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	1584.000		8443.000
		0400- 9-	BRIDGE DECK GROOVING & PLANING, DECK 8.5"&>	SY	0.000		1871.000
		0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	2873.000		42152.000
		0400-147-	COMPOSITE NEOPRENE PADS	CF	11.300		101.600
		0415- 1- 4	REINFORCING STEEL - SUPERSTRUCTURE	LB	80079.000		585941.000
		0415- 1- 5	REINFORCING STEEL- SUBSTRUCTURE	LB	11737.000		268965.000
		0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	9030.000		151448.000
		0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	1442.000		4854.000
		0450- 2- 45	PREST BEAMS: FLORIDA-I BEAM 45"	LF	0.000		1593.000
		0450- 2- 54	PREST BEAMS: FLORIDA-I BEAM 54"	LF	0.000		1305.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000		1.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000		1.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000		1.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000		1.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000		1.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000		1.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000		1.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	0.000		1.000
		0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	1236.000		11818.000
		0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	0.000		2835.000
		0455- 35- 20	STEEL PILING, 18" DIA. PIPE	LF	1585.000		2805.000
		0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	0.000		43517.000
		0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	210.000		1796.000
		0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	0.000		445.000
		0455-144- 20	TEST PILES - STEEL, 18" DIA PIPE	LF	265.000		495.000
		0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&IPOURED JOINT WITH BACKER ROD	LF	0.000		146.000
		0458- 1- 12	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&ISTRIP SEAL	LF	71.000		736.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0001 SUMMARY OF STRUCTURES PAY ITEMS CONTINUED

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201 BR # 100544		QUANTITY TOTAL
	0458- 1- 22	BRIDGE DECK EXPANSION JOINT, REHABILITATION, STRIP SEAL	LF	0.000		614.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	51.000		813.000
	0460- 2- 2	STRUCT STEEL, LOW ALLOY (43127515201)	LS	0.000		1.000
	0506- 2-	BRIDGE DRAINAGE PIPE	LF	0.000		105.000
	0506- 3-	BRIDGE DRAINS	EA	0.000		1.000
	0521- 5- 1	CONCRETE TRAFFIC RAILING, BRIDGE 32" F - SHAPE	LF	408.000		4303.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT,NON REINFORCED, 4"	SY	0.000		2015.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	448.000		448.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43127515201)	LS	0.000		1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43127515201)	LS	1.000		1.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0002 SUMMARY OF ROADWAY PAY ITEMS

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201	43127515604	43127535201
	0101- 1-	MOBILIZATION (43127515201)	LS	1.000	0.000	0.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43127515201)	LS	1.000	0.000	0.000
	0102- 3-	COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	CY	250.000	0.000	0.000
	0102- 14-	TRAFFIC CONTROL OFFICER	MH	5416.000	0.000	0.000
	0102- 60-	WORK ZONE SIGN	ED	64096.000	0.000	0.000
	0102- 71- 14	BARRIER WALL, TEMPORARY, F&I, TYPE K	LF	45330.000	0.000	0.000
	0102- 71- 24	BARRIER WALL, TEMPORARY, RELOCATE, TYPE K	LF	540571.000	0.000	0.000
	0102- 74- 1	TEMPORARY BARRICADE- TYPES I, II, DI, VP, DRUM, ORLCD	ED	160282.000	0.000	0.000
	0102- 74- 2	BARRICADE, TEMPORARY, TYPE III, 6'	ED	3279.000	0.000	0.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1736.000	0.000	0.000
	0102- 77-	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	19580.000	0.000	0.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	8056.000	0.000	0.000
	0102- 79-	LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C,STEADY BURN	ED	507624.000	0.000	0.000
	0102- 89- 7	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	177.000	0.000	0.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2227.000	0.000	0.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	1252.000	0.000	0.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	1252.000	0.000	0.000
	0102-911- 1	PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, SKIP	LF	5646.000	0.000	0.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, SOLID	LF	8009.000	0.000	0.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	13385.000	0.000	0.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	16733.000	0.000	0.000
	0104- 10- 3	SEDIMENT BARRIER	LF	40676.000	0.000	0.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	2397.000	0.000	0.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	82.000	0.000	0.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	9.000	0.000	0.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	184.000	0.000	0.000
	0104- 19-	CHEMICAL TREATMENT- POWDERED, FOR EROSION CONTROL	SY	16733.000	0.000	0.000
	0107- 1-	LITTER REMOVAL	AC	1201.200	0.000	0.000
	0107- 2-	MOWING	AC	1201.200	0.000	0.000
	0110- 1- 1	CLEARING & GRUBBING (43127515201)	LS	1.000	0.000	0.000
	0120- 1-	REGULAR EXCAVATION	CY	124465.000	0.000	0.000
	0120- 4-	SUBSOIL EXCAVATION	CY	10592.000	0.000	0.000
	0120- 6-	EMBANKMENT	CY	210286.000	0.000	0.000
	0121- 70-	FLOWABLE FILL	CY	153.000	0.000	0.000
	0160- 4-	TYPE B STABILIZATION	SY	163675.000	0.000	0.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	54427.000	0.000	0.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	10670.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0002 SUMMARY OF ROADWAY PAY ITEMS CONTINUED

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201	43127515604	43127535201
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	5217.000	0.000	0.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	80470.000	0.000	0.000
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY	8438.000	0.000	0.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	1600.000	0.000	0.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	5741.000	0.000	0.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY	49580.000	0.000	0.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY	17651.000	0.000	0.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	4410.000	0.000	0.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	22950.800	0.000	0.000
	0334- 1- 23	SUPERPAVE ASPH CONC, TRAF C, PG76-22	TN	13271.300	0.000	0.000
	0337- 7- 22	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG76-22	TN	5250.500	0.000	0.000
	0337- 7- 43	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12 5,PG 76-22	TN	1136.500	0.000	0.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	655.800	0.000	0.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	294.500	0.000	0.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	17.900	0.000	0.000
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY	655.900	0.000	0.000
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY	5.400	0.000	0.000
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	391.000	0.000	0.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000	0.000	0.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	2.000	0.000	0.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	1.000	0.000	0.000
	0425- 1-501	INLETS, DT BOT, TYPE A, <10'	EA	1.000	0.000	0.000
	0425- 1-503	INLETS, DT BOT, TYPE A, J BOT, <10'	EA	2.000	0.000	0.000
	0425- 1-511	INLETS, DT BOT, TYPE B, <10'	EA	2.000	0.000	0.000
	0425- 1-513	INLETS, DT BOT, TYPE B, J BOT, <10'	EA	4.000	0.000	0.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	4.000	0.000	0.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	2.000	0.000	0.000
	0425- 1-581	INLETS, DT BOT, TYPE H, <10'	EA	5.000	0.000	0.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	39.000	0.000	0.000
	0425- 1-702	INLETS, GUTTER, TYPE S, >10'	EA	1.000	0.000	0.000
	0425- 1-703	INLETS, GUTTER, TYPE S, J BOTTOM <10'	EA	10.000	0.000	0.000
	0425- 1-841	INLETS, MEDIAN BARRIER, TYPE 3, <10'	EA	13.000	0.000	0.000
	0425- 1-843	INLETS, MEDIAN BARRIER, TYPE 3, J BOT, <10'	EA	1.000	0.000	0.000
	0425- 1-844	INLETS, MEDIAN BARRIER, TYPE 3, J BOT, >10'	EA	2.000	0.000	0.000
	0425- 1-863	INLETS, MB, TYPE 5, J BOT, <10'	EA	1.000	0.000	0.000
	0425- 1-891	INLETS, BARRIER WALL, <10'	EA	59.000	0.000	0.000
	0425- 1-892	INLETS, BARRIER WALL, >10'	EA	2.000	0.000	0.000
	0425- 1-893	INLETS, BARRIER WALL, J BOT, <10'	EA	20.000	0.000	0.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	10.000	0.000	0.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	2.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0002 SUMMARY OF ROADWAY PAY ITEMS CONTINUED

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201	43127515604	43127535201
		0425- 2- 91	MANHOLES, J-8, <10'	EA	3.000	0.000	0.000
		0425- 2- 92	MANHOLES, J-8, >10'	EA	2.000	0.000	0.000
T		0425- 11-	DRAINAGE STRUCTURE MODIFY	EA	10.000	0.000	0.000
T		0425- 78-	INLET CAP, PRECAST	EA	7.000	0.000	0.000
		0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	4060.000	0.000	0.000
		0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	1990.000	0.000	0.000
		0430- 94- 3	DESILTING PIPE, 37 - 48"	LF	239.000	0.000	0.000
		0430- 94- 4	DESILTING PIPE, 49 - 60"	LF	111.000	0.000	0.000
		0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	242.000	0.000	0.000
		0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	595.000	0.000	0.000
		0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	7873.000	0.000	0.000
		0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	2104.000	0.000	0.000
		0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	3602.000	0.000	0.000
		0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	307.000	0.000	0.000
		0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	27.000	0.000	0.000
		0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	43.000	0.000	0.000
		0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH,24"S/CD	LF	45.000	0.000	0.000
		0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH,30"S/CD	LF	252.000	0.000	0.000
		0430-611-125	U-ENDWALL WITH BAFFLES, STD 261, 1:4 SLOPE, 18"PIPE	EA	26.000	0.000	0.000
		0430-611-129	U-ENDWALL WITH BAFFLES, STD 261, 1:4 SLOPE, 24"PIPE	EA	5.000	0.000	0.000
		0430-950-	DESILTING CONCRETE BOX CULVERT,	CY	246.000	0.000	0.000
		0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000	0.000	0.000
		0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	7.000	0.000	0.000
		0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	1.000	0.000	0.000
		0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	1.000	0.000	0.000
		0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	4.000	0.000	0.000
		0430-982-629	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH 24" CD	EA	2.000	0.000	0.000
		0430-982-633	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH 30" CD	EA	1.000	0.000	0.000
		0451- 70-	PREST SOIL ANCHORS	EA	195.000	0.000	0.000
		0451- 70- 1	PRESTRESSED SOIL ANCHOR, PERFORMANCE TEST	EA	23.000	0.000	0.000
		0451- 70- 2	PRESTRESSED SOIL ANCHOR, CREEP TEST	EA	14.000	0.000	0.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS	1.000	0.000	0.000
		0455- 35- 7	STEEL PILING, HP 14 X 102	LF	90.000	0.000	0.000
		0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	245469.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0002 SUMMARY OF ROADWAY PAY ITEMS CONTINUED

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201	43127515604	43127535201
		0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	39169.000	0.000	0.000
		0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	598.000	0.000	0.000
		0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1294.000	0.000	0.000
		0520- 6-	SHOULDER GUTTER- CONCRETE	LF	8554.000	0.000	0.000
		0521- 1-	MEDIAN CONCRETE BARRIER WALL	LF	8149.000	0.000	0.000
		0521- 8- 1	CONCRETE TRAFFIC RAILING BARRIERWITH JUNCTION SLAB, 32" F SHAPE	LF	8787.000	0.000	0.000
		0521- 72- 3	SHOULDER CONCRETE BARRIER WALL, RIGID-SHOULDER	LF	5839.000	0.000	0.000
		0521- 72- 4	SHOULDER CONCRETE BARRIER WALL, RIGID RETAINING	LF	3212.000	0.000	0.000
		0521- 72- 10	SHOULDER CONCRETE BARRIER WALL, RIGID SHOULDER 42"	LF	798.000	0.000	0.000
		0522- 1-	SIDEWALK CONCRETE, 4" THICK	SY	675.000	0.000	0.000
		0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	2754.000	0.000	0.000
		0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	397.800	0.000	0.000
		0536- 1- 1	GUARDRAIL -ROADWAY	LF	11810.000	0.000	0.000
		0536- 2-	GUARDRAIL- SHOP-BENT PANELS	LF	63.000	0.000	0.000
		0536- 7-	SPECIAL GUARDRAIL POST	EA	71.000	0.000	0.000
		0536- 8- 1	GUARDRAIL, BRIDGE ANCHORAGE ASSEMBLY, INSTALL	EA	4.000	0.000	0.000
		0536- 8- 6	GUARDRAIL, BRIDGE ANCHORAGE ASSEMBLY, REMOVE	EA	28.000	0.000	0.000
		0536- 73-	GUARDRAIL REMOVAL	LF	28670.000	0.000	0.000
		0536- 82-	GUARDRAIL ANCHORAGE- CONCRETE BARRIER	EA	13.000	0.000	0.000
		0536- 85- 22	GUARDRAIL END ANCHORAGE ASSEMBLY- FLARED	EA	8.000	0.000	0.000
		0536- 85- 24	GUARDRAIL END ANCHORAGE ASSEMBLY- PARALLEL	EA	3.000	0.000	0.000
		0536- 85- 25	GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE II	EA	7.000	0.000	0.000
		0538- 1-	GUARDRAIL RESET	LF	800.000	0.000	0.000
T		0542- 70-	BUMPER GUARDS, CONCRETE	EA	4.000	0.000	0.000
		0544- 75-140	CRASH CUSHION - OPTIONAL, LESS THAN 50	EA	5.000	0.000	0.000
		0546- 72- 51	RUMBLE STRIPS, GROUND-IN, 16" MIN. WIDTH	PM	8.000	0.000	0.000
		0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	143569.000	0.000	0.000
		0548- 13-	RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	SF	3153.000	0.000	0.000
		0548- 14-	RETAINING WALL SYSTEM, PERMANENT-WIDENING, ATTACHEDTO EXISTING WALL	SF	21331.000	0.000	0.000
		0550- 10-230	FENCING, TYPE B, 6.1-7.0', STANDARD	LF	4576.000	0.000	0.000
		0556- 1- 5	JACK AND BORE, CASING DIAMETER 24"TO<36"	LF	406.000	0.000	0.000
		0556- 1- 6	JACK AND BORE, CASING DIAMETER, 36" TO <48"	LF	538.000	0.000	0.000
		0570- 1- 2	PERFORMANCE TURF, SOD	SY	152117.000	0.000	0.000
		0571- 1- 12	PLASTIC EROSION MAT, TRM, TYPE 2	SY	25638.000	0.000	0.000
		0710- 11-111	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	NM	21.000	0.000	0.000
		0710- 11-122	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	LF	9464.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0002 SUMMARY OF ROADWAY PAY ITEMS CONTINUED

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201	43127515604	43127535201
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 18"	LF	2553.000	0.000	0.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP 6",10-30 OR 3-9 SKIP	GM	11.000	0.000	0.000
	0710- 11-133	PAINTED PAVEME NT MARKING, STANDARD,WHITE, 12" WIDE, 3'-9' SKIP AND APPROACH TO TOLL PLAZA	GM	0.023	0.000	0.000
	0710- 11-151	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED /GUIDELINE/ 6-10 GAP EXTENSION, 6"	LF	2284.000	0.000	0.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	EA	12.000	0.000	0.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	15.000	0.000	0.000
	0710- 11-211	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	NM	17.000	0.000	0.000
	0999- 16-	PARTNERING, DO NOT BID (43127515201)	LS	1.000	0.000	0.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	30.000	0.000	0.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	5.000	0.000	0.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43127515201)	LS	1.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0002 SUMMARY OF ROADWAY PAY ITEMS

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT			QUANTITY TOTAL
	0101- 1-	MOBILIZATION (43127515201)	LS			1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43127515201)	LS			1.000
	0102- 3-	COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	CY			250.000
	0102- 14-	TRAFFIC CONTROL OFFICER	MH			5416.000
	0102- 60-	WORK ZONE SIGN	ED			64096.000
	0102- 71- 14	BARRIER WALL, TEMPORARY, F&I, TYPE K	LF			45330.000
	0102- 71- 24	BARRIER WALL, TEMPORARY, RELOCATE, TYPE K	LF			540571.000
	0102- 74- 1	TEMPORARY BARRICADE- TYPES I, II, DI, VP, DRUM, ORLCD	ED			160282.000
	0102- 74- 2	BARRICADE, TEMPORARY, TYPE III, 6'	ED			3279.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED			1736.000
	0102- 77-	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED			19580.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA			8056.000
	0102- 79-	LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C,STEADY BURN	ED			507624.000
	0102- 89- 7	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO			177.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED			2227.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED			1252.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED			1252.000
	0102-911- 1	PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, SKIP	LF			5646.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, SOLID	LF			8009.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF			13385.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY			16733.000
	0104- 10- 3	SEDIMENT BARRIER	LF			40676.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF			2397.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF			82.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA			9.000
	0104- 18-	INLET PROTECTION SYSTEM	EA			184.000
	0104- 19-	CHEMICAL TREATMENT- POWDERED, FOR EROSION CONTROL	SY			16733.000
	0107- 1-	LITTER REMOVAL	AC			1201.200
	0107- 2-	MOWING	AC			1201.200
	0110- 1- 1	CLEARING & GRUBBING (43127515201)	LS			1.000
	0120- 1-	REGULAR EXCAVATION	CY			124465.000
	0120- 4-	SUBSOIL EXCAVATION	CY			10592.000
	0120- 6-	EMBANKMENT	CY			210286.000
	0121- 70-	FLOWABLE FILL	CY			153.000
	0160- 4-	TYPE B STABILIZATION	SY			163675.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY			54427.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY			10670.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0002 SUMMARY OF ROADWAY PAY ITEMS CONTINUED

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT			QUANTITY TOTAL
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY			5217.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY			80470.000
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY			8438.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY			1600.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY			5741.000
	0327- 70- 11	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	SY			49580.000
	0327- 70- 13	MILLING EXIST ASPH PAVT, 1 3/4" AVG DEPTH	SY			17651.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY			4410.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN			22950.800
	0334- 1- 23	SUPERPAVE ASPH CONC, TRAF C, PG76-22	TN			13271.300
	0337- 7- 22	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG76-22	TN			5250.500
	0337- 7- 43	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12 5,PG 76-22	TN			1136.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN			655.800
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY			294.500
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY			17.900
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY			655.900
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY			5.400
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB			391.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA			1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA			2.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA			1.000
	0425- 1-501	INLETS, DT BOT, TYPE A, <10'	EA			1.000
	0425- 1-503	INLETS, DT BOT, TYPE A, J BOT, <10'	EA			2.000
	0425- 1-511	INLETS, DT BOT, TYPE B, <10'	EA			2.000
	0425- 1-513	INLETS, DT BOT, TYPE B, J BOT, <10'	EA			4.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA			4.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA			2.000
	0425- 1-581	INLETS, DT BOT, TYPE H, <10'	EA			5.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA			39.000
	0425- 1-702	INLETS, GUTTER, TYPE S, >10'	EA			1.000
	0425- 1-703	INLETS, GUTTER, TYPE S, J BOTTOM <10'	EA			10.000
	0425- 1-841	INLETS, MEDIAN BARRIER, TYPE 3, <10'	EA			13.000
	0425- 1-843	INLETS, MEDIAN BARRIER, TYPE 3, J BOT, <10'	EA			1.000
	0425- 1-844	INLETS, MEDIAN BARRIER, TYPE 3, J BOT, >10'	EA			2.000
	0425- 1-863	INLETS, MB, TYPE 5, J BOT, <10'	EA			1.000
	0425- 1-891	INLETS, BARRIER WALL, <10'	EA			59.000
	0425- 1-892	INLETS, BARRIER WALL, >10'	EA			2.000
	0425- 1-893	INLETS, BARRIER WALL, J BOT, <10'	EA			20.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA			10.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA			2.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0002 SUMMARY OF ROADWAY PAY ITEMS CONTINUED

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT			QUANTITY TOTAL
		0425- 2- 91	MANHOLES, J-8, <10'	EA			3.000
		0425- 2- 92	MANHOLES, J-8, >10'	EA			2.000
T		0425- 11-	DRAINAGE STRUCTURE MODIFY	EA			10.000
T		0425- 78-	INLET CAP, PRECAST	EA			7.000
		0430- 94- 1	DESILTING PIPE, 0 - 24"	LF			4060.000
		0430- 94- 2	DESILTING PIPE, 25 - 36"	LF			1990.000
		0430- 94- 3	DESILTING PIPE, 37 - 48"	LF			239.000
		0430- 94- 4	DESILTING PIPE, 49 - 60"	LF			111.000
		0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF			242.000
		0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF			595.000
		0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF			7873.000
		0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF			2104.000
		0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF			3602.000
		0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF			307.000
		0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF			27.000
		0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF			43.000
		0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH,24"S/CD	LF			45.000
		0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH,30"S/CD	LF			252.000
		0430-611-125	U-ENDWALL WITH BAFFLES, STD 261, 1:4 SLOPE, 18"PIPE	EA			26.000
		0430-611-129	U-ENDWALL WITH BAFFLES, STD 261, 1:4 SLOPE, 24"PIPE	EA			5.000
		0430-950-	DESILTING CONCRETE BOX CULVERT,	CY			246.000
		0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA			2.000
		0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA			7.000
		0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA			1.000
		0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA			1.000
		0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA			4.000
		0430-982-629	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH 24" CD	EA			2.000
		0430-982-633	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH 30" CD	EA			1.000
		0451- 70-	PREST SOIL ANCHORS	EA			195.000
		0451- 70- 1	PRESTRESSED SOIL ANCHOR, PERFORMANCE TEST	EA			23.000
		0451- 70- 2	PRESTRESSED SOIL ANCHOR, CREEP TEST	EA			14.000
T		0455- 18-	PROTECTION OF EXISTING STRUCTURES (43127515201)	LS			1.000
		0455- 35- 7	STEEL PILING, HP 14 X 102	LF			90.000
		0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF			245469.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0002 SUMMARY OF ROADWAY PAY ITEMS CONTINUED

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT			QUANTITY TOTAL
		0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF			39169.000
		0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF			598.000
		0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF			1294.000
		0520- 6-	SHOULDER GUTTER- CONCRETE	LF			8554.000
		0521- 1-	MEDIAN CONCRETE BARRIER WALL	LF			8149.000
		0521- 8- 1	CONCRETE TRAFFIC RAILING BARRIERWITH JUNCTION SLAB, 32" F SHAPE	LF			8787.000
		0521- 72- 3	SHOULDER CONCRETE BARRIER WALL, RIGID-SHOULDER	LF			5839.000
		0521- 72- 4	SHOULDER CONCRETE BARRIER WALL, RIGID RETAINING	LF			3212.000
		0521- 72- 10	SHOULDER CONCRETE BARRIER WALL, RIGID SHOULDER 42"	LF			798.000
		0522- 1-	SIDEWALK CONCRETE, 4" THICK	SY			675.000
		0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY			2754.000
		0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN			397.800
		0536- 1- 1	GUARDRAIL -ROADWAY	LF			11810.000
		0536- 2-	GUARDRAIL- SHOP-BENT PANELS	LF			63.000
		0536- 7-	SPECIAL GUARDRAIL POST	EA			71.000
		0536- 8- 1	GUARDRAIL, BRIDGE ANCHORAGE ASSEMBLY, INSTALL	EA			4.000
		0536- 8- 6	GUARDRAIL, BRIDGE ANCHORAGE ASSEMBLY, REMOVE	EA			28.000
		0536- 73-	GUARDRAIL REMOVAL	LF			28670.000
		0536- 82-	GUARDRAIL ANCHORAGE- CONCRETE BARRIER	EA			13.000
		0536- 85- 22	GUARDRAIL END ANCHORAGE ASSEMBLY- FLARED	EA			8.000
		0536- 85- 24	GUARDRAIL END ANCHORAGE ASSEMBLY- PARALLEL	EA			3.000
		0536- 85- 25	GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE II	EA			7.000
		0538- 1-	GUARDRAIL RESET	LF			800.000
T		0542- 70-	BUMPER GUARDS, CONCRETE	EA			4.000
		0544- 75-140	CRASH CUSHION - OPTIONAL, LESS THAN 50	EA			5.000
		0546- 72- 51	RUMBLE STRIPS, GROUND-IN, 16" MIN. WIDTH	PM			8.000
		0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF			143569.000
		0548- 13-	RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	SF			3153.000
		0548- 14-	RETAINING WALL SYSTEM, PERMANENT-WIDENING, ATTACHEDTO EXISTING WALL	SF			21331.000
		0550- 10-230	FENCING, TYPE B, 6.1-7.0', STANDARD	LF			4576.000
		0556- 1- 5	JACK AND BORE, CASING DIAMETER 24"TO<36"	LF			406.000
		0556- 1- 6	JACK AND BORE, CASING DIAMETER, 36" TO <48"	LF			538.000
		0570- 1- 2	PERFORMANCE TURF, SOD	SY			152117.000
		0571- 1- 12	PLASTIC EROSION MAT, TRM, TYPE 2	SY			25638.000
		0710- 11-111	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	NM			21.000
		0710- 11-122	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	LF			9464.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0002 SUMMARY OF ROADWAY PAY ITEMS CONTINUED

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT			QUANTITY TOTAL
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 18"	LF			2553.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP 6",10-30 OR 3-9 SKIP	GM			11.000
	0710- 11-133	PAINTED PAVEME NT MARKING, STANDARD,WHITE, 12" WIDE, 3'-9' SKIP AND APPROACH TO TOLL PLAZA	GM			0.023
	0710- 11-151	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED /GUIDELINE/ 6-10 GAP EXTENSION, 6"	LF			2284.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	EA			12.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA			15.000
	0710- 11-211	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	NM			17.000
	0999- 16-	PARTNERING, DO NOT BID (43127515201)	LS			1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA			30.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA			5.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43127515201)	LS			1.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0003 SUMMARY OF SIGNING

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	PAY ITEMS 43127515201	43127515604	43127535201
	0700- 20- 11	SINGLE POST SIGN, F&I, LESS THAN 12 SF	AS	14.000	0.000	0.000
	0700- 20- 12	SINGLE POST SIGN, F&I, 12-20 SF	AS	40.000	0.000	0.000
	0700- 20- 14	SINGLE POST SIGN, F&I, 21-30 SF	AS	22.000	0.000	0.000
	0700- 20- 15	SINGLE POST SIGN, F&I, 31+ SF	AS	1.000	0.000	0.000
	0700- 20- 21	SINGLE POST SIGN, F&I BARRIER MOUNTED, LESS THAN 12 SF	AS	3.000	0.000	0.000
	0700- 20- 22	SINGLE POST SIGN, F&I BARRIER MOUNTED, 12-20 SF	AS	4.000	0.000	0.000
	0700- 20- 60	SINGLE POST SIGN, REMOVE	AS	42.000	0.000	0.000
	0700- 21- 11	MULTI- POST SIGN, F&I, 50 SF OR LESS	AS	5.000	0.000	0.000
	0700- 21- 12	MULTI- POST SIGN, F&I, 51 - 100 SF	AS	3.000	0.000	0.000
	0700- 21- 13	MULTI- POST SIGN, F&I, 101 - 150 SF	AS	2.000	0.000	0.000
	0700- 21- 15	MULTI- POST SIGN, F&I, 201 - 250 SF	AS	3.000	0.000	0.000
	0700- 21- 60	MULTI- POST SIGN, REMOVE	AS	21.000	0.000	0.000
	0700- 22-121	OVERHEAD TRUSS SPAN SIGN, FURNISH & INSTALL,TRUSS LENGTH 51-100', SIGN AREA 300 OR LESS SF	AS	4.000	0.000	0.000
	0700- 22-132	OVERHEAD TRUSS SPAN SIGN, FURNISH & INSTALL,TRUSS LENGTH 101-150', SIGN AREA 301-500 SF	AS	1.000	0.000	0.000
	0700- 22-141	OVERHEAD TRUSS SPAN SIGN,FURNISH & INSTALL,TRUSS LENGTH 151-200', SIGN AREA 300 OR LESS SF	AS	1.000	0.000	0.000
	0700- 22-600	OVERHEAD TRUSS SPAN SIGN,REMOVE	AS	3.000	0.000	0.000
	0700- 23-112	OVERHEAD TRUSS CANTILEVER SIGN,F&I,T 30 OR <,S 101-200	AS	1.000	0.000	0.000
	0700- 23-113	OVERHEAD TRUSS CANTILEVER SIGN,F&I,T 30 OR <,S 201-300	AS	1.000	0.000	0.000
	0700- 23-123	OVERHEAD TRUSS CANTILEVER SIGN, FURNISH & INSTALL T 31-40, S 201-300	AS	1.000	0.000	0.000
	0700- 23-132	OVERHEAD TRUSS CANTILEVER SIGN,F&I, T 41-50, S 101-200	AS	1.000	0.000	0.000
	0700- 23-133	OVERHEAD TRUSS CANTILEVER SIGN,F&I, T 41-50, S 201-300	AS	1.000	0.000	0.000
	0700- 23-210	OVERHEAD TRUSS CANTILEVER SIGN,F&I TRUSS ONLY,T 30 OR <	AS	1.000	0.000	0.000
	0700- 23-220	OVERHEAD TRUSS CANTILEVER SIGN,F&I TRUSS ONLY,T 31-40	AS	2.000	0.000	0.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	233.000	0.000	0.000
	0705- 11- 4	DELINEATOR, FLEXIBLE HIGH PERFORMANCE	EA	9.000	0.000	0.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	20.500	0.000	0.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43127515201)	LS	1.000	0.000	0.000
	0711- 12-122	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 8"	LF	555.000	0.000	0.000
	0711- 12-124	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 18"	LF	572.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0003 SUMMARY OF SIGNING PAY ITEMS CONTINUED

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201	43127515604	43127535201
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENTMARKINGS	SF	4277.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0003 SUMMARY OF SIGNING PAY ITEMS

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT			QUANTITY TOTAL
	0700- 20- 11	SINGLE POST SIGN, F&I, LESS THAN 12 SF	AS			14.000
	0700- 20- 12	SINGLE POST SIGN, F&I, 12-20 SF	AS			40.000
	0700- 20- 14	SINGLE POST SIGN, F&I, 21-30 SF	AS			22.000
	0700- 20- 15	SINGLE POST SIGN, F&I, 31+ SF	AS			1.000
	0700- 20- 21	SINGLE POST SIGN, F&I BARRIER MOUNTED, LESS THAN 12 SF	AS			3.000
	0700- 20- 22	SINGLE POST SIGN, F&I BARRIER MOUNTED, 12-20 SF	AS			4.000
	0700- 20- 60	SINGLE POST SIGN, REMOVE	AS			42.000
	0700- 21- 11	MULTI- POST SIGN, F&I, 50 SF OR LESS	AS			5.000
	0700- 21- 12	MULTI- POST SIGN, F&I, 51 - 100 SF	AS			3.000
	0700- 21- 13	MULTI- POST SIGN, F&I, 101 - 150 SF	AS			2.000
	0700- 21- 15	MULTI- POST SIGN, F&I, 201 - 250 SF	AS			3.000
	0700- 21- 60	MULTI- POST SIGN, REMOVE	AS			21.000
	0700- 22-121	OVERHEAD TRUSS SPAN SIGN, FURNISH & INSTALL,TRUSS LENGTH 51-100', SIGN AREA 300 OR LESS SF	AS			4.000
	0700- 22-132	OVERHEAD TRUSS SPAN SIGN, FURNISH & INSTALL,TRUSS LENGTH 101-150', SIGN AREA 301-500 SF	AS			1.000
	0700- 22-141	OVERHEAD TRUSS SPAN SIGN,FURNISH & INSTALL,TRUSS LENGTH 151-200', SIGN AREA 300 OR LESS SF	AS			1.000
	0700- 22-600	OVERHEAD TRUSS SPAN SIGN,REMOVE	AS			3.000
	0700- 23-112	OVERHEAD TRUSS CANTILEVER SIGN,F&I,T 30 OR <,S 101-200	AS			1.000
	0700- 23-113	OVERHEAD TRUSS CANTILEVER SIGN,F&I,T 30 OR <,S 201-300	AS			1.000
	0700- 23-123	OVERHEAD TRUSS CANTILEVER SIGN, FURNISH & INSTALL T 31-40, S 201-300	AS			1.000
	0700- 23-132	OVERHEAD TRUSS CANTILEVER SIGN,F&I, T 41-50, S 101-200	AS			1.000
	0700- 23-133	OVERHEAD TRUSS CANTILEVER SIGN,F&I, T 41-50, S 201-300	AS			1.000
	0700- 23-210	OVERHEAD TRUSS CANTILEVER SIGN,F&I TRUSS ONLY,T 30 OR <	AS			1.000
	0700- 23-220	OVERHEAD TRUSS CANTILEVER SIGN,F&I TRUSS ONLY,T 31-40	AS			2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA			233.000
	0705- 11- 4	DELINEATOR, FLEXIBLE HIGH PERFORMANCE	EA			9.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF			20.500
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43127515201)	LS			1.000
	0711- 12-122	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 8"	LF			555.000
	0711- 12-124	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 18"	LF			572.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0003 SUMMARY OF SIGNING PAY ITEMS CONTINUED

SPC ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT			QUANTITY TOTAL
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENTMARKINGS	SF			4277.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0004 SUMMARY OF LIGHTING PAY ITEMS

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201	43127515604	43127535201
		0555- 1- 1	DIRECTIONAL BORE, LESS THAN 6"	LF	1386.000	0.000	0.000
		0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	74311.000	0.000	0.000
		0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	15599.000	0.000	0.000
		0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	22150.000	0.000	0.000
		0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	14061.000	0.000	0.000
		0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOROWNS	LF	30295.000	0.000	0.000
		0715- 2- 11	LIGHTING - CONDUIT, F&I, UNDERGROUND	LF	18827.000	0.000	0.000
		0715- 2- 12	LIGHTING - CONDUIT, F&I, UNDER EXISTING PAVEMENTSAWCUT	LF	2205.000	0.000	0.000
		0715- 2- 13	LIGHTING CONDUIT, F&I, SURFACE MOUNT	LF	212.000	0.000	0.000
		0715- 4-600	LIGHT POLE COMPLETE, REMOVE	EA	135.000	0.000	0.000
		0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000	0.000	0.000
		0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	1.000	0.000	0.000
		0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	2.000	0.000	0.000
		0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	8.000	0.000	0.000
		0715- 11-126	LUMINAIRE, F&I, UNDER DECK, PENDANT HUNG	EA	9.000	0.000	0.000
		0715- 11-500	LUMINAIRE, REMOVE	EA	9.000	0.000	0.000
		0715- 14- 11	LIGHTING - PULL BOX, F&I, ROADSIDE-MOULDED	EA	89.000	0.000	0.000
		0715- 14- 14	LIGHTING - PULL BOX, F&I, SURFACE MOUNT	EA	18.000	0.000	0.000
		0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	65.000	0.000	0.000
		0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	65.000	0.000	0.000
T		0715-511-135	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARMSHOULDER MOUNT, ALUMINUM, 35'	EA	65.000	0.000	0.000
T		0715-513-135	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I,SINGLE ARM WALL MOUNT, ALUMINUM, 35'	EA	6.000	0.000	0.000
T		0715-514-150	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I,DOUBLE ARM WALL MOUNT, ALUMINUM, 50'	EA	53.000	0.000	0.000
T		0715-515-135	LIGHT POLE COMPLETE- SEPCIAL DESIGN, F&I,SINGLE ARM BRIDGE MOUNT-ALUMINUM, 35'	EA	3.000	0.000	0.000
T		0715-517-150	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I,DOUBLE ARM BRIDGE MOUNT, ALUMINUM, 50'	EA	3.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0004 SUMMARY OF LIGHTING PAY ITEMS

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT			QUANTITY TOTAL
		0555- 1- 1	DIRECTIONAL BORE, LESS THAN 6"	LF			1386.000
		0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF			74311.000
		0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF			15599.000
		0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF			22150.000
		0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF			14061.000
		0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOROWNS	LF			30295.000
		0715- 2- 11	LIGHTING - CONDUIT, F&I, UNDERGROUND	LF			18827.000
		0715- 2- 12	LIGHTING - CONDUIT, F&I, UNDER EXISTING PAVEMENTSAWCUT	LF			2205.000
		0715- 2- 13	LIGHTING CONDUIT, F&I, SURFACE MOUNT	LF			212.000
		0715- 4-600	LIGHT POLE COMPLETE, REMOVE	EA			135.000
		0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA			2.000
		0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA			1.000
		0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA			2.000
		0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA			8.000
		0715- 11-126	LUMINAIRE, F&I, UNDER DECK, PENDANT HUNG	EA			9.000
		0715- 11-500	LUMINAIRE, REMOVE	EA			9.000
		0715- 14- 11	LIGHTING - PULL BOX, F&I, ROADSIDE-MOULDED	EA			89.000
		0715- 14- 14	LIGHTING - PULL BOX, F&I, SURFACE MOUNT	EA			18.000
		0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA			65.000
		0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA			65.000
T		0715-511-135	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARMSHOULDER MOUNT, ALUMINUM, 35'	EA			65.000
T		0715-513-135	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I,SINGLE ARM WALL MOUNT, ALUMINUM, 35'	EA			6.000
T		0715-514-150	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I,DOUBLE ARM WALL MOUNT, ALUMINUM, 50'	EA			53.000
T		0715-515-135	LIGHT POLE COMPLETE- SEPCIAL DESIGN, F&I,SINGLE ARM BRIDGE MOUNT-ALUMINUM, 35'	EA			3.000
T		0715-517-150	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I,DOUBLE ARM BRIDGE MOUNT, ALUMINUM, 50'	EA			3.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0005 SUMMARY OF LANDSCAPE / PERIPHERAL PAY ITEMS

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201	43127515604	43127535201
		0101- 1-	MOBILIZATION (43127535201)	LS	0.000	0.000	1.000
		0102- 1-	MAINTENANCE OF TRAFFIC (43127535201)	LS	0.000	0.000	1.000
		0160- 4-	TYPE B STABILIZATION	SY	0.000	62.000	0.000
		0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	0.000	62.000	0.000
		0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	0.000	14.000	0.000
		0337- 7- 22	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG76-22	TN	0.000	3.000	0.000
		0580- 1- 1	LANDSCAPE COMPLETE- SMALL PLANTS (43127535201)	LS	0.000	0.000	1.000
		0580- 1- 2	LANDSCAPE COMPLETE- LARGE PLANTS (43127535201)	LS	0.000	0.000	1.000
		0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43127535201)	LS	0.000	0.000	1.000
T		1050- 11-424	UTILITY PIPE, F&I, DI/CI, WATER / SEWER, 8 - 19.9"	LF	0.000	1750.000	0.000
T		1055- 11-414	UTILITY FITTINGS, F&I, DI/CI, ELBOW, 8 - 19.9"	EA	0.000	18.000	0.000
T		1055- 11-424	UTILITY FITTINGS, F&I, DI/CI, TEE, 8 - 19.9"	EA	0.000	1.000	0.000
T		1055- 11-434	UTILITY FITTINGS, F&I, DI/CI, REDUCER, 8 - 19.9"	EA	0.000	1.000	0.000
T		1080- 11-206	UTILITY FIXTURES, F&I, 2-4.9", VAC/AIR ASSEMBLY	EA	0.000	2.000	0.000
T		1080- 11-304	UTILITY FIXTURES, F&I, 5.0 - 7.9", VALVE ASSEMBLY	EA	0.000	1.000	0.000
T		1080- 11-404	UTILITY FIXTURES, F&I, 8.0-19.9", VALVE ASSEMBLY	EA	0.000	2.000	0.000
T		1080- 11-409	UTILITY FIXTURES, F&I, 8-19.9", MECHANICAL JOINT RESTRAINT	EA	0.000	86.000	0.000
T		1644-116- 08	FIRE HYDRANT, STANDARD, F&I, 3 WAY, 2 HOSE, 1 PUMPER, 6"	EA	0.000	1.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0005 SUMMARY OF LANDSCAPE / PERIPHERAL PAY ITEMS

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT			QUANTITY TOTAL
		0101- 1-	MOBILIZATION (43127535201)	LS			1.000
		0102- 1-	MAINTENANCE OF TRAFFIC (43127535201)	LS			1.000
		0160- 4-	TYPE B STABILIZATION	SY			62.000
		0285-709-	OPTIONAL BASE, BASE GROUP 09	SY			62.000
		0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN			14.000
		0337- 7- 22	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG76-22	TN			3.000
		0580- 1- 1	LANDSCAPE COMPLETE- SMALL PLANTS (43127535201)	LS			1.000
		0580- 1- 2	LANDSCAPE COMPLETE- LARGE PLANTS (43127535201)	LS			1.000
		0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43127535201)	LS			1.000
T		1050- 11-424	UTILITY PIPE, F&I, DI/CI, WATER / SEWER, 8 - 19.9"	LF			1750.000
T		1055- 11-414	UTILITY FITTINGS, F&I, DI/CI, ELBOW, 8 - 19.9"	EA			18.000
T		1055- 11-424	UTILITY FITTINGS, F&I, DI/CI, TEE, 8 - 19.9"	EA			1.000
T		1055- 11-434	UTILITY FITTINGS, F&I, DI/CI, REDUCER, 8 - 19.9"	EA			1.000
T		1080- 11-206	UTILITY FIXTURES, F&I, 2-4.9", VAC/AIR ASSEMBLY	EA			2.000
T		1080- 11-304	UTILITY FIXTURES, F&I, 5.0 - 7.9", VALVE ASSEMBLY	EA			1.000
T		1080- 11-404	UTILITY FIXTURES, F&I, 8.0-19.9", VALVE ASSEMBLY	EA			2.000
T		1080- 11-409	UTILITY FIXTURES, F&I, 8-19.9", MECHANICAL JOINT RESTRAINT	EA			86.000
T		1644-116- 08	FIRE HYDRANT, STANDARD, F&I, 3 WAY, 2 HOSE, 1 PUMPER, 6"	EA			1.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0006 SUMMARY OF ARCHITECTURAL PAY ITEMS

SPCTT	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201	43127515604	43127535201
		0735- 74- 1	TOLL PLAZA, LOCATION 1 (43127515201)	LS	1.000	0.000	0.000
		0735- 74- 2	TOLL PLAZA, LOCATION 2 (43127515201)	LS	1.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0006 SUMMARY OF ARCHITECTURAL PAY ITEMS

SPCT	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT			QUANTITY TOTAL
		0735- 74- 1	TOLL PLAZA, LOCATION 1 (43127515201)	LS			1.000
		0735- 74- 2	TOLL PLAZA, LOCATION 2 (43127515201)	LS			1.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0007 SUMMARY OF INTELLIGENT TRANSPORTATION SYSTEM PAY ITEMS

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201	43127515604	43127535201
		0555- 1- 1	DIRECTIONAL BORE, LESS THAN 6"	LF	1449.000	0.000	0.000
		0555- 1- 2	DIRECTIONAL BORE, 6" TO < 12"	LF	709.000	0.000	0.000
		0639- 1- 12	ELECTRICAL POWER SERVICE, OVERHEAD,METER FURNISHED BY CONTRACTOR	AS	3.000	0.000	0.000
		0639- 2- 1	ELECTRICAL SERVICE WIRE	LF	50650.000	0.000	0.000
		0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I,POLE MOUNT	EA	11.000	0.000	0.000
T		0639- 5- 1	EMERGENCY GENERATOR-PERMANENT, UP TO 25 KW	EA	3.000	0.000	0.000
		0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	6.000	0.000	0.000
		0649- 31-201	MAST ARM,F&I, WIND SPEED-130,SINGLE ARM,W/0 LUMINAIRE-36	EA	2.000	0.000	0.000
		0690- 34- 1	COMPLETE POLE REMOVAL- DEEP, DIRECT BURIAL	EA	3.000	0.000	0.000
		0781- 5-113	ITS DYNAMIC MESSAGE SIGN SUPPORT STRUCTURE, F&I, SPAN, 51-100'	EA	2.000	0.000	0.000
		0781- 5-122	ITS DYNAMIC MESSAGE SIGN SUPPORT STRUCTURE, F&I, CANTILEVER, 26-50'	EA	1.000	0.000	0.000
		0781- 41-215	ITS DYNAMIC MESSAGE SIGN, F&I WITH UPS, WALK-IN, MONOCHROME, 201-300 SF	EA	3.000	0.000	0.000
		0782- 1- 11	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - PRESSURIZED	EA	7.000	0.000	0.000
		0782- 1- 70	ITS CCTV CAMERA, REM0VE & STOCKPILE	EA	4.000	0.000	0.000
		0783- 1-121	ITS FIBER OPTIC CABLE, F& I, UNDERGROUND, 2 -12 FIBERS	LF	6948.000	0.000	0.000
		0783- 1-122	ITS FIBER OPTIC CABLE, F& I, UNDERGROUND, 13 -48 FIBERS	LF	2890.000	0.000	0.000
		0783- 1-123	ITS FIBER OPTIC CABLE, F& I, UNDERGROUND, 49 - 96 FIBERS	LF	23612.000	0.000	0.000
		0783- 1-600	ITS FIBER OPTIC CABLE, REMOVE	LF	20815.000	0.000	0.000
		0783- 2- 31	ITS FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	418.000	0.000	0.000
		0783- 3- 11	ITS FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICEENCLOSURE	EA	11.000	0.000	0.000
		0783- 3- 12	ITS FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE, TRAY	EA	36.000	0.000	0.000
		0783- 3- 13	ITS FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATEDCONNECTOR ASSEMBLY	EA	108.000	0.000	0.000
		0783- 3- 15	ITS FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL,PRETERMINATED	EA	14.000	0.000	0.000
		0783- 3- 16	ITS FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL.FIELD TERMINATED	EA	6.000	0.000	0.000
		0783- 3- 17	ITS FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTORPANEL	EA	9.000	0.000	0.000
		0783- 4-111	ITS CONDUIT, F& I, ABOVEGROUND	LF	771.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0007 SUMMARY OF INTELLIGENT TRANSPORTATION SYSTEM PAY ITEMS CONTINUED

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT	43127515201	43127515604	43127535201
		0783- 4-112	ITS CONDUIT, F& I, UNDERGROUND	LF	78460.000	0.000	0.000
		0783- 4-113	ITS CONDUIT, F& I, UNDER EXISTING PAVEMENTSAWCUT	LF	3825.000	0.000	0.000
		0783- 4-132	ITS CONDUIT, INSTALL, UNDERGROUND	LF	3035.000	0.000	0.000
		0783- 4-133	ITS CONDUIT, INSTALL, UNDER EXISTING PAVEMENTSAWCUT	LF	235.000	0.000	0.000
		0783- 4-160	ITS CONDUIT, REMOVE&DISPOSE	LF	58525.000	0.000	0.000
		0783- 5- 1	ITS PULL BOX FOR FIBER OPTIC CABLE, FURNISH AND INSTALL	EA	45.000	0.000	0.000
		0783- 6- 1	ITS SPLICE BOX FOR FIBER OPTIC CABLE, F & I	EA	19.000	0.000	0.000
		0783- 6- 6	ITS SPLICE BOX FOR FIBER OPTIC CABLE, REMOVEAND DISPOSE	EA	7.000	0.000	0.000
T		0783- 7- 1	ITS PULL & JUNCTION BOX, FURNISH AND INSTALL	EA	60.000	0.000	0.000
T		0783- 7- 3	ITS PULL & JUNCTION BOX, INSTALL	EA	4.000	0.000	0.000
T		0783- 7- 7	ITS PULL & JUNCTION BOX, REMOVE & STOCKPILE	EA	60.000	0.000	0.000
		0783- 9- 13	ITS LOCATE SYSTEM ELECTRONIC EQUIPMENT,BOX MARKER	EA	19.000	0.000	0.000
		0784- 1- 1	ITS MANAGED FIELD ETHERNET SWITCH, F&I	EA	11.000	0.000	0.000
		0784- 1- 7	ITS MANAGED FIELD ETHERNET SWITCH, REPLACE	EA	5.000	0.000	0.000
		0784- 2- 1	ITS DEVICE SERVER, F&I	EA	4.000	0.000	0.000
		0784- 3- 11	ITS DIGITAL VIDEO ENCODER WITH SOFTWARE DECODER, F&I,HARDENED ENCODER	EA	7.000	0.000	0.000
T		0784- 5- 12	ITS MANAGED ETHERNET HUB SWITCH,F&I, SHORT HAUL	EA	4.000	0.000	0.000
		0785- 1- 12	ITS POLE, F&I, STEEL WITH LOWERING DEVICE	EA	7.000	0.000	0.000
		0785- 1- 60	ITS POLE, REMOVE	EA	7.000	0.000	0.000
		0785- 2-121	ITS FIELD CABINET, F&I, TYPE 336 WITH SUNSHIELDS, POLEMOUNT	EA	3.000	0.000	0.000
		0785- 2-162	ITS FIELD CABINET, F&I, TYPE 332 W/SUNSHIELDS, GROUNDMOUNT	EA	5.000	0.000	0.000
T		0785- 2-192	ITS FIELD CABINET, F&I, SPECIAL, GROUND MOUNT	EA	5.000	0.000	0.000
		0785- 2-600	ITS CABINET, REMOVE & DISPOSE	EA	7.000	0.000	0.000
		0786- 1- 11	ITS VEHICLE DETECTION SYSTEM, F&I, MICROWAVE	EA	4.000	0.000	0.000
T		0786- 1- 19	ITS VEHICLE DETECTION SYSTEM, F&I, SPECIAL	EA	4.000	0.000	0.000
D		0786- 1- 50	ITS VEHICLE DETECTION SYSTEM, ADJUST & MODIFY	EA	13.000	0.000	0.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0007 SUMMARY OF INTELLIGENT TRANSPORTATION SYSTEM PAY ITEMS

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT			QUANTITY TOTAL
		0555- 1- 1	DIRECTIONAL BORE, LESS THAN 6"	LF			1449.000
		0555- 1- 2	DIRECTIONAL BORE, 6" TO < 12"	LF			709.000
		0639- 1- 12	ELECTRICAL POWER SERVICE, OVERHEAD,METER FURNISHED BY CONTRACTOR	AS			3.000
		0639- 2- 1	ELECTRICAL SERVICE WIRE	LF			50650.000
		0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I,POLE MOUNT	EA			11.000
T		0639- 5- 1	EMERGENCY GENERATOR-PERMANENT, UP TO 25 KW	EA			3.000
		0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA			6.000
		0649- 31-201	MAST ARM,F&I, WIND SPEED-130,SINGLE ARM,W/0 LUMINAIRE-36	EA			2.000
		0690- 34- 1	COMPLETE POLE REMOVAL- DEEP, DIRECT BURIAL	EA			3.000
		0781- 5-113	ITS DYNAMIC MESSAGE SIGN SUPPORT STRUCTURE, F&I, SPAN, 51-100'	EA			2.000
		0781- 5-122	ITS DYNAMIC MESSAGE SIGN SUPPORT STRUCTURE, F&I, CANTILEVER, 26-50'	EA			1.000
		0781- 41-215	ITS DYNAMIC MESSAGE SIGN, F&I WITH UPS, WALK-IN, MONOCHROME, 201-300 SF	EA			3.000
		0782- 1- 11	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - PRESSURIZED	EA			7.000
		0782- 1- 70	ITS CCTV CAMERA, REM0VE & STOCKPILE	EA			4.000
		0783- 1-121	ITS FIBER OPTIC CABLE, F& I, UNDERGROUND, 2 -12 FIBERS	LF			6948.000
		0783- 1-122	ITS FIBER OPTIC CABLE, F& I, UNDERGROUND, 13 -48 FIBERS	LF			2890.000
		0783- 1-123	ITS FIBER OPTIC CABLE, F& I, UNDERGROUND, 49 - 96 FIBERS	LF			23612.000
		0783- 1-600	ITS FIBER OPTIC CABLE, REMOVE	LF			20815.000
		0783- 2- 31	ITS FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA			418.000
		0783- 3- 11	ITS FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICEENCLOSURE	EA			11.000
		0783- 3- 12	ITS FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE, TRAY	EA			36.000
		0783- 3- 13	ITS FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATEDCONNECTOR ASSEMBLY	EA			108.000
		0783- 3- 15	ITS FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL,PRETERMINATED	EA			14.000
		0783- 3- 16	ITS FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL.FIELD TERMINATED	EA			6.000
		0783- 3- 17	ITS FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTORPANEL	EA			9.000
		0783- 4-111	ITS CONDUIT, F& I, ABOVEGROUND	LF			771.000

PROPOSAL : E8M60 LEAD PROJECT : 43127515201 COUNTY : HILLSBOROUG , MANDIST: 08
PROJECT(S): 43127515201 COUNTY/SECTION: 10470000 ,
43127515604 10470000
43127535201 10470000

0007 SUMMARY OF INTELLIGENT TRANSPORTATION SYSTEM PAY ITEMS CONTINUED

SPC	ALT	ITEM NUMBER	ITEM DESCRIPTION	UNIT			QUANTITY TOTAL
		0783- 4-112	ITS CONDUIT, F& I, UNDERGROUND	LF			78460.000
		0783- 4-113	ITS CONDUIT, F& I, UNDER EXISTING PAVEMENTSAWCUT	LF			3825.000
		0783- 4-132	ITS CONDUIT, INSTALL, UNDERGROUND	LF			3035.000
		0783- 4-133	ITS CONDUIT, INSTALL, UNDER EXISTING PAVEMENTSAWCUT	LF			235.000
		0783- 4-160	ITS CONDUIT, REMOVE&DISPOSE	LF			58525.000
		0783- 5- 1	ITS PULL BOX FOR FIBER OPTIC CABLE, FURNISH AND INSTALL	EA			45.000
		0783- 6- 1	ITS SPLICE BOX FOR FIBER OPTIC CABLE, F & I	EA			19.000
		0783- 6- 6	ITS SPLICE BOX FOR FIBER OPTIC CABLE, REMOVEAND DISPOSE	EA			7.000
T		0783- 7- 1	ITS PULL & JUNCTION BOX, FURNISH AND INSTALL	EA			60.000
T		0783- 7- 3	ITS PULL & JUNCTION BOX, INSTALL	EA			4.000
T		0783- 7- 7	ITS PULL & JUNCTION BOX, REMOVE & STOCKPILE	EA			60.000
		0783- 9- 13	ITS LOCATE SYSTEM ELECTRONIC EQUIPMENT,BOX MARKER	EA			19.000
		0784- 1- 1	ITS MANAGED FIELD ETHERNET SWITCH, F&I	EA			11.000
		0784- 1- 7	ITS MANAGED FIELD ETHERNET SWITCH, REPLACE	EA			5.000
		0784- 2- 1	ITS DEVICE SERVER, F&I	EA			4.000
		0784- 3- 11	ITS DIGITAL VIDEO ENCODER WITH SOFTWARE DECODER, F&I,HARDENED ENCODER	EA			7.000
T		0784- 5- 12	ITS MANAGED ETHERNET HUB SWITCH,F&I, SHORT HAUL	EA			4.000
		0785- 1- 12	ITS POLE, F&I, STEEL WITH LOWERING DEVICE	EA			7.000
		0785- 1- 60	ITS POLE, REMOVE	EA			7.000
		0785- 2-121	ITS FIELD CABINET, F&I, TYPE 336 WITH SUNSHIELDS, POLEMOUNT	EA			3.000
		0785- 2-162	ITS FIELD CABINET, F&I, TYPE 332 W/SUNSHIELDS, GROUNDMOUNT	EA			5.000
T		0785- 2-192	ITS FIELD CABINET, F&I, SPECIAL, GROUND MOUNT	EA			5.000
		0785- 2-600	ITS CABINET, REMOVE & DISPOSE	EA			7.000
		0786- 1- 11	ITS VEHICLE DETECTION SYSTEM, F&I, MICROWAVE	EA			4.000
T		0786- 1- 19	ITS VEHICLE DETECTION SYSTEM, F&I, SPECIAL	EA			4.000
D		0786- 1- 50	ITS VEHICLE DETECTION SYSTEM, ADJUST & MODIFY	EA			13.000