Florida Department of Transportation

RICK SCOTT
GOVERNOR

Florida's Turnpike Enterprise
P.O. Box 613069, Ocoee, FL 34761
407-532-3999

JIM BOXOLD
SECRETARY

ADDENDUM No. 1

DATE: Apr. 22, 2016

TO: PROPOSERS

FROM: Richard M. Nethercote, Jr.
District Contracts Administrator
Florida's Turnpike Enterprise

SUBJECT: Contract No.: E8P89
Financial Project Nos.: 435462-1-52-01
County: Miami-Dade County
Project Name: SR 821 (HEFT) Campbell Drive Interchange Improvements

---

Proposers and other interested parties are informed that the above referenced documents are hereby revised, changed and supplemented as set forth below:

REQUEST FOR PROPOSAL DOCUMENT

Attached is Addendum No. 1 to the Final RFP issued on March 7th, 2016. There were some minor changes made to the RFP Document. For your convenience, two versions are being provided: 1) A .PDF red-lined version showing what has changed since Final RFP was issued; and 2) A .PDF version with all changes already incorporated. The .PDF version herein is the official RFP for this contract. The version you were previously issued is hereby deleted.

1. Table of Contents – Reference Documents
   - Reference #5
     - Added "FPID 406119-2 SR 821 South Florida Part A ITS Improvements"

2. Section I – Introduction - Description of Work
   - No. 10
     - First sentence: Deleted "queue" and added "as depicted in the conceptual plans."
   - No. 10 a. i., and 10 a.ii.
     - Revised lengths to 100 feet.
   - No. 10 a. iii.
     - Replaced "allow for a future second right-only" with "design and construct the pavement required to accommodate a future second right-only turn lane,

transitioned from the beginning of the single right-only lane provide the ramp pavement required to accommodate"

- No. 11
  - Deleted "queue," and "storage", added "as depicted in the conceptual plans."
- No. 11.a.i.2.
  - Revised "380" to "350"
- No. 11.a.ii.
  - Revised to read: "Westbound two left-only (one existing: 245 feet, one proposed: 165 feet)"
- No. 11.b.i.
  - Revised to read: "Eastbound two left-only (one existing: 255 feet, one proposed: 310 feet)

3. Section V.N. – Meetings and Progress Reporting
   - Added paragraph: "The Design-Build Firm shall be responsible for preparing agendas and minutes for all design related meetings. The agenda will identify key issues, who will present the issue and time limitations for each topic. The agendas shall be sent to the Department's Design Project Manager not less than two (2) calendar days (excluding weekends and Department observed Holidays) prior to the meeting and all meeting minutes shall be prepared and sent to the Department's Design Project Manager within five (5) calendar days (excluding weekends and Department observed Holidays) after the meeting was conducted. Any comments from the Department shall be incorporated by the Design-Build Firm within two (2) calendar days (excluding weekends and Department observed Holidays) after receipt and distributed to all attendees for final distribution."

4. Section V.Q. – Engineers Field Office
   - Deleted text and added "N/A" to the section title.

5. Section VI.Q. – Lighting Plans
   - First Paragraph: Deleted "the Concept Plans included in the Request for Proposal (RFP)" from the first sentence.
   - First Paragraph: Added "The preliminary Concept Lighting Plans, provided as a Reference Document to the RFP, are for information only. If the cobra-head luminaire and photometric distribution indicated in the preliminary Concept Lighting Plans are not available, then the light pole spacing may need to be reduced depending upon the available luminaire and available photometric distribution as provided with the manufacturer's cobra-head luminaire and associated high pressure sodium lamps."
   - Fourth Paragraph: Deleted "electrical and lighting infrastructure shall be reused where indicated in the concept lighting plans, namely, the existing" from the first sentence.

REQUEST FOR PROPOSAL REFERENCE DOCUMENTS

Reference Documents to the original RFP Document that are not revised herein are still in effect for this contract.

1. Reference Document No. 01 – Conceptual Plans
   - Replace Lighting

2. Reference Document No. 05 – Existing Record Plans
    - Added FPID 406119-2 SR 821 South Florida Part A ITS Improvements

All other conditions of the subject contract remain unchanged.
If you are a **PROPOSAL HOLDER**, please acknowledge receipt of this Addendum on Page 1 of the Form 375-020-12 of your Proposal, and return with your bid.

If you have any questions regarding this information, please do not hesitate to contact Rich Nethercote at the same number as shown above, ext. 3885.

Attachments