BID SOLICITATIONENOTICENANDFAPPROXIMATETQUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 08090609 CALL ORDER: 002 PROPOSAL ID: E8J93 DISTRICT: 08
COUNTIES : MIAMI-DADE, , ,

ROAD NAME : NOISE WALL & BRIDGE
LIMITS : PAINTING AT MIAMI GARDENS DRIVE

FINPROJ NO(S): 41754435201 (*) FEDERAL AID NO: N/A WORK MIX: NOISE MITIGATION

TOTAL ROADWAY LENGTH: 0.000 MILES
TOTAL BRIDGE LENGTH: 0.000 MILES
TOTAL PROPOSAL LENGTH: 0.000 MILES

CONTRACT DAYS: 49
LETTING DATE : 06/09/09
CONTRACT EXECUTION DAYS: 10
SPECIAL START DATE: N/A
ACQUIS./FLEXIBLE START TIME : 157

PROPOSAL BUDGET ESTIMATE: $ 1,280,855.00

PROPOSAL PACKAGE FEE: $5.00

DESCRIPTION:
Work consists of providing all labor, materials, equipment and incidentals necessary for the extension of sound barrier walls on both sides of the "Spur" of Florida's Turnpike (SR 91) just north of the Golden Glades Mainline Toll Plaza in Miami-Dade County. The proposed improvements include installation of sound barrier walls located adjacent to the Limited Access Right-of-Way (LA R/W). Pattern, type, finish, etc. of the proposed sound barrier walls will match existing sound barrier walls. Minor utility adjustments to the existing ITS facilities will be necessary as a result of the wall improvements. No Pre-Bid Conference. Contractor must be prequalified. PLEASE NOTE: THE AWARD AND EXECUTION OF THIS PROJECT WILL BE ACCELERATED, AS PER THE SPECIFICATIONS PACKAGE FOR THIS PROJECT.

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<<		SECTION 0001 ROADWAY		>>>>>>>>>>>>
	0101 1	MOBILIZATION (41754435201)	LS	1.000
	0102 1	MAINTENANCE OF TRAFFIC (41754435201)	LS	1.000
	0102 60	WORK ZONE SIGN	ED	1,225.000
	0102 74 1	BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	ED	3,000.000
	0102 74 2	BARRICADE, TEMPORARY, TYPE III, 6'	ED	60.000
	0102 76	ADVANCE WARNING ARROW PANEL	ED	75.000
	0102 77	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	588.000
	0102 99	CHANGEABLE-VARIABLE MESSAGE SIGN, TEMPORARY	ED	189.000
	0102150 1	PORTABLE REGULATORY, SIGN	ED	60.000
	0102150 2	RADAR SPEED DISPLAY UNIT	ED	45.000
	0104 10 2	SYNTHETIC BALES	LF	400.000
	0104 13 1	STAKED SILT FENCE, TYPE III	LF	2,750.000
	0110 1 1	CLEARING & GRUBBING (41754435201)	LS	1.000
	0120 1	REGULAR EXCAVATION	CY	182.000
	0120 6	EMBANKMENT	CY	563.000
	0400 1 15	CONCRETE CLASS I, MISCELLANEOUS	CY	5.000
	0534 72101	SOUND BARRIER-INC FOUNDATION, PERMANENT	SF	41,140.000
	0550 10221	FENCING, TYPE B, 5.1-6.0, W/ BARB WIRE ATTMT	LF	40.000
	0570 1 2	PERFORMANCE TURF, SOD	SY	9,181.000
	0999 16	PARTNERING, DO NOT BID (41754435201)	LS	1.000
	0999 25	INITIAL CONTINGENCY AMOUNT, DO NOT BID (41754435201)	LS	1.000