BID SOLICITATIONENOTICENANDFAPPROXIMATETQUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 08101019 CALL ORDER: 002 PROPOSAL ID: E8K78 DISTRICT: 08
COUNTIES : ORANGE , , ,

ROAD NAME : PAVEMENT MARKINGS
LIMITS : ORANGE COUNTY

FINPROJ NO(S): 42233025201 (*) FEDERAL AID NO: N/A WORK MIX: SIGNING/PAVEMENT MARKINGS

TOTAL ROADWAY LENGTH: 0.000 MILES CONTRACT DAYS: 60
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 10/19/10
TOTAL PROPOSAL LENGTH: 0.000 MILES CONTRACT EXECUTION DAYS: 10
SPECIAL START DATE: N/A
ACQUIS./FLEXIBLE START TIME : 14

PROPOSAL BUDGET ESTIMATE: $ 115,000.00

PROPOSAL PACKAGE FEE(PLANS + PROPOSAL): $0.00 PLANS ONLY FEE: $0.00 SPECS ONLY FEE: $0.00

DESCRIPTION:
The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to: 1. Provide thermoplastic pavement markings; and 2. Remove, furnish and install single-post and overhead sign panels at several locations on the Beachline Express from Mile Post (MP) 4.345 to MP 8.36.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS CONTRACT.

The Contractor shall supply to the Department and keep in force at all times during the term of this contract, a Performance Bond provided by a surety authorized to do business in the State of Florida. It is a requirement of this contract that the Department of Transportation, Turnpike Enterprise, is to be an additional named insured on the Contractor's Public Liability and Property Damages Liability Insurance policies.

Bids for this project can be submitted via Bid Express or can be submitted to the address on the first page of this Advertisement/Bid Solicitation Notice.

| ALT | ITEM NO. | DESCRIPTION | UNITS | FA/NFA QUANTITY |
|---|---|---|---|---|
| <<<<<<<<<<<< | | SECTION 0001 PAVEMENT MARKINGS ORANGE COUNTY | | >>>>>>>>>>>> |
| | 0102 14 | TRAFFIC CONTROL OFFICER | MH | 80.000 |
| | 0700 20 60 | SINGLE POST SIGN, REMOVE | AS | 3.000 |
| | 0700 48 49 | SIGN PANELS RELOCATE, 16 - 100 | EA | 3.000 |
| | 0700 48 53 | SIGN PANELS, REPLACE, 201 - 300 | EA | 3.000 |
| | 0706 3 | RETRO-REFLECTIVE PAVEMENT MARKERS | EA | 160.000 |
| | 0711 11111 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 6" | NM | 10.000 |
| | 0711 11122 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" | LF | 13,000.000 |
| | 0711 11123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" | LF | 90.000 |
| | 0711 11124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" | LF | 3,100.000 |
| | 0711 11125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" | LF | 75.000 |
| | 0711 11131 | THERMOPLASTIC, STANDARD, WHITE, SKIP, 6" | GM | 17.000 |
| | 0711 11132 | THERMOPLASTIC, STANDARD, WHITE, 3-9 SKIP, 8" | GM | 1.000 |
| | 0711 11211 | THERMOPLASTIC, STANDARD,YELLOW, SOLID, 6" | NM | 10.500 |
| | 0711 11222 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 8" | LF | 500.000 |
| | 0711 11224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" | LF | 200.000 |
| | E706 1 32 | REFLECTIVE PAVEMENT MARKER (REMOVE)(CLASS B) | EA | 200.000 |