FLORIDA DEPARTMENT OF TRANSPORTATION
BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 08141014 CALL ORDER: 003 PROPOSAL ID: E8N90 (Construction)
DISTRICT : 08 COUNTIES : BROWARD , , ,

ROAD NAME : SAWGRASS CANAL REVETMENT - WALL 3 (MP 15.2)
LIMITS :

FINPROJ NO(S): FEDERAL AID NO(S):
42815425201 (*) N/A
42815435201 N/A

TOTAL ROADWAY LENGTH: 0.000 MILES CONTRACT DAYS: 845
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 10/14/14
TOTAL PROPOSAL LENGTH: 0.000 MILES CONTRACT EXECUTION DAYS: 10
SPECIAL START DATE: N/A
BUDGET AMOUNT: $ 10,478,750.00 ACQUIS./FLEXIBLE START TIME : 30 Days (Flex Time)

Please read the full advertisement

DESCRIPTION:

Work consists of providing all labor, materials, equipment and incidentals necessary for the improvements on SR 869 (Sawgrass Expressway) between the City of Parkland and the City of Coral Springs in Broward County, in Section 4, Township 48 South, Range 41 East. The project limits on SR 869 are between Sta. 830+53.95 (MP 14.624) to Sta. 918+30.00 (MP 16.286), a net length of 1.662 miles. The improvements under this Contract consist of addressing the overall stability of the embankment slopes behind existing noise walls throughout the reaches of the adjacent canals. These improvements are critical to protecting both the adjacent noise walls and roadway, and to provide a safe environment for maintenance operations. The project consists of repair of the canal slopes that have suffered severe erosion along some sections of Noise Wall 3 located between Pine Island Road and University Drive (Sta. 848+40 to Sta. 870+20) and Noise Wall 6 located east of University Drive (Sta. 888+40 to Sta. 918+30). No Pre-Bid Conference. Contractor must be prequalified.

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<<		SECTION 0001 ROADWAY		>>>>>>>>>>>>
	0000200 1	ROADWAY DESIGN GROUP- GENERIC PAY ITEM 1	ZZ	106,691.000
	0101 1	MOBILIZATION (42815425201)	LS	1.000
	0101 1	MOBILIZATION (42815435201)	LS	1.000
	0102 1	MAINTENANCE OF TRAFFIC (42815425201)	LS	1.000
	0102 1	MAINTENANCE OF TRAFFIC (42815435201)	LS	1.000
	0102 14	TRAFFIC CONTROL OFFICER	MH	160.000
	0102 60	WORK ZONE SIGN	ED	10,977.000
	0102 71 11	BARRIER WALL, TEMPORARY, F&I, CONCRETE	LF	1,204.000
	0102 74 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	24,955.000
	0102 74 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	40.000
	0102 77	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	4,832.000
	0102 89 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102 99	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	58.000
	0104 10 3	SEDIMENT BARRIER	LF	448.000
	0104 11	FLOATING TURBIDITY BARRIER	LF	6,387.000
	0104 18	INLET PROTECTION SYSTEM	EA	4.000
	0107 1	LITTER REMOVAL	AC	127.210
	0107 2	MOWING	AC	127.210
	0109 71 2	FIELD OFFICE, 600 SQ FT	DA	905.000
	0110 1 1	CLEARING & GRUBBING (42815435201)	LS	1.000
	0110 1 1	CLEARING & GRUBBING (42815425201)	LS	1.000
	0120 1	REGULAR EXCAVATION	CY	12,673.000
	0120 2 2	BORROW EXCAVATION, TRUCK MEASURE	CY	283.000
	0162 1 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	1,698.000
	0514 71 1	PLASTIC FILTER FABRIC, SUBSURFACE	SY	37,173.000
	0530 1	RIPRAP, SAND-CEMENT	CY	454.300
	0530 3 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	5,869.000
	0570 1 2	PERFORMANCE TURF, SOD	SY	6,440.000
	0580 1 1	LANDSCAPE COMPLETE- SMALL PLANTS (42815435201)	LS	1.000
	0580 1 1	LANDSCAPE COMPLETE- SMALL PLANTS (42815425201)	LS	1.000
	0999 25	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42815435201)	LS	1.000
	0999 25	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42815425201)	LS	1.000