FLORIDA DEPARTMENT OF TRANSPORTATION
BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 08150210 CALL ORDER: 004 PROPOSAL ID: E8P27 (Maintenance)
DISTRICT : 08 COUNTIES : SEMINOLE, , ,

ROAD NAME : PAVEMENT MARKINGS
LIMITS : SEMINOLE EXPRESSWAY MP 12.047 TO MP 17.414

FINPROJ NO(S): FEDERAL AID NO(S):
42902325201 (*) N/A

TOTAL ROADWAY LENGTH: 0.000 MILES CONTRACT DAYS: 60
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 02/10/15
TOTAL PROPOSAL LENGTH: 0.000 MILES CONTRACT EXECUTION DAYS: 10
SPECIAL START DATE: N/A
BUDGET AMOUNT: $ 225,000.00 ACQUIS./FLEXIBLE START TIME : 14

Please read the full advertisement

DESCRIPTION:
The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to provide thermoplastic pavement markings on the Seminole Expressway (SR 417), Milepost 12.047 to 17.414.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Pavement Marking. The Experience in Pavement Markings form (850-070-06) must be filled out and submitted with the bid to be reviewed by the Department. If a Contractor is presently prequalified with the Department in "Pavement Markings", it is not necessary to submit the form.

<<<<<<<<<<< SECTION 0001 PAVEMENT MARKINGS SEMINOLE EXPRESSWAY - MP 12.047 TO MP 17.414>>>>>>>>>>>

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
	0102 1	MAINTENANCE OF TRAFFIC	LS	1.000
	0102 14	TRAFFIC CONTROL OFFICER	MH	120.000
	0711 11123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	LF	10,250.000
	0711 11124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18"	LF	1,450.000
	0711 11125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	LF	200.000
	0711 11151	THERMOPLASTIC, STANDARD, WHITE, DOTTED/GUIDELINE/ 6-10 GAP EXTENSION, 6"	LF	120.000
	0711 11160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE	EA	39.000
	0711 11170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	52.000
	0711 11224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18"	LF	120.000
	0711 14123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12"	LF	750.000
	0711 14125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24"	LF	600.000
	0711 15111	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	NM	15.300
	0711 15112	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	NM	1.250
	0711 15131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	12.700
	0711 15133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.080
	0711 15211	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	NM	15.300