

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 08150714

Call Order: 001 Proposal: E8P57-R0

District:08

Counties: BROWARD, MIAMI-DADE, PALM BEACH, TURNPIKE



Road Name: DRAINAGE MAINTENANCE - ZONE 1

Limits:

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Project(s): 19276317209(\*) Federal Aid No: N/A

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	07/14/15
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14
Proposal Budget Estimate:	\$200,000.00		

Please read the full advertisement

Description: The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to perform maintenance, repair, and restoration of the drainage systems, pipes and inlets, stormwater management facilities, canals/waterways, retention areas, and roadside ditches, at various locations on the Homestead Extension Florida's Turnpike (MP) 0.0 to 46.5; Florida's Turnpike, Milepost (MP) 0.0X to 100.0, and Sawgrass Expressway, MP 0.0 to 22.5.

ATTENDANCE AT A MANDATORY PRE-BID CONFERENCE IS REQUIRED TO BID ON THIS WORK. THE PRE-BID CONFERENCE FOR THIS PROJECT WILL BE HELD ON June 30, 2015 AT 9:00 a.m. AT THE STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION, TURNPIKE ENTERPRISE OFFICE, MILE POST 65.0, FLORIDA'S TURNPIKE AT POMPANO BEACH SERVICE PLAZA, POMPANO BEACH, FLORIDA, IN THE AUDITORIUM.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Drainage Repair. The Experience in Drainage Repair form (850-070-05) must be filled out and submitted with the bid to be reviewed by the Department. If a Contractor is presently prequalified with the Department in Drainage Repair, it is not necessary to submit the form.

• **WORKING DAY**

Any calendar day, exclusive of Saturdays, Sundays, State-designated holidays, and special event days, on which the Contractor works, or is expected to work, in accordance with the Work Documents issued by the Department unless otherwise directed by the Engineer. The Contractor may submit a written request to work on excluded days. This request shall be submitted to the Engineer for approval twenty-four hours in advance.

• Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

• No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

• The Contractor shall perform all work during day and night hours in accordance with the Turnpike Lane Closure Policy.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 001 Proposal: E8P57-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 SODDING (SY)</b>				
	0104- 10- 3	SEDIMENT BARRIER	LF	50.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	200.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	100.000
	0120- 1-	REGULAR EXCAVATION	CY	700.000
	0120- 6-	EMBANKMENT	CY	150.000
	0160- 4-	TYPE B STABILIZATION	SY	200.000
	0400- 1- 11	CONCRETE CLASS I, RETAINING WALLS	CY	5.000
	0425- 11-	DRAINAGE STRUCTURE MODIFY	EA	2.000
	0425- 74- 1	MANHOLES & INLETS CLEANING & SEALING, <10'	EA	3.000
	0425- 74- 2	MANHOLES & INLETS CLEANING & SEALING, >10'	EA	2.000
	0425- 78-	INLET CAP, PRECAST	EA	3.000
	0425- 82-	REPLACE GRATE	EA	3.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	9,000.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	350.000
	0430- 94- 4	DESILTING PIPE, 49 - 60"	LF	350.000
	0430-173-118	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 18", GUTTER DRAIN	LF	25.000
	0430-173-124	PIPE CULVERT OPTIONAL MATERIAL, ROUND, 24", GUTTER DRAIN	LF	25.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	150.000
	0431- 1- 1	PIPE LINER, OPTIONAL MATERIAL, 0-24"	LF	50.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	50.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	10.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	500.000
	E102-100- 16	NECESSARY MAINT SERVICE (ROUND TRIP EXPENSE)	EA	15.000
	E110- 2-	CLEARING & GRUBBING	AC	7.000
	E120- 10- 1	CLEAN AND RESHAPE DITCH (SPREAD)	LF	6,500.000
	E120- 10- 5	CLEAN AND RESHAPE CANAL (> 7.0' DEPTH)	LF	5,000.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	170.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	5.000
	E425- 73- 3	FRAME AND GRATE (F&I)	EA	10.000
	E425- 73- 4	RESET EXISTING FRAME AND GRATE	EA	10.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	160.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	250.000
	E575- 1-	SODDING	SY	800.000
	E999- 3- 1	HYDRAULIC PUMP (4")	HR	10.000
	E999- 3- 2	HYDRAULIC PUMP (6")	HR	10.000