Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	08150915	Call Order: 004	Proposal: E8P73		District:08
Counties:	BROWARD				
Road Name:	DMS REPLACEMENT - SAWGRASS EXPWY				
Limits:	86472000				
Project(s):	43560515201(*)	Federal Aid No: N/A			
Total Roadway Length:	21.835 Miles			Contract Days:	100
Total Bridge Length:	0.000 Miles			Letting Date:	09/15/15
Total Proposal Length:	21.835 Miles			Contract Execution Days:	10
				Special Start Date:	N/A
				Aquis/Flexible Start Time:	14
Proposal Budget Estimate:		$1,000,000.00			

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to furnish and install all necessary components for fully functional Walk-In Dynamic Message Signs (DMS), including the removal of the existing Walk-In DMS at various locations on the Sawgrass Expressway, MP 0.0 to 21.5.

• WORKING DAY
Any calendar day, exclusive of Saturdays, Sundays, State-designated holidays, and special event days, on which the Contractor works, or is expected to work, in accordance with the Work Documents issued by the Department unless otherwise directed by the Engineer. The Contractor may submit a written request to work on excluded days. This request shall be submitted to the Engineer for approval twenty-four hours in advance.

• Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

• No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

• The Contractor shall perform all work during day and night hours in accordance with the Turnpike Lane Closure Policy.

• The Contractor shall perform all work during daylight hours and night time hours and in accordance with the Turnpike Lane Closure Policy.

• A license to do business as a certified or registered electrical contractor pursuant to Chapter 489, Part II, Florida Statutes is required. Submit a copy of the license with the bid proposal package.

ATTENDANCE AT A MANDATORY PRE-BID CONFERENCE IS REQUIRED TO BID ON THIS WORK. THE PRE-BID CONFERENCE FOR THIS PROJECT WILL BE HELD ON AUGUST 25, 2015 AT 2:00 P.M. AT THE STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION, TURNPIKE ENTERPRISE OFFICE, MILE POST 65.0, FLORIDAS TURNPIKE AT POMPANO BEACH SERVICE PLAZA, POMPANO BEACH, FLORIDA, IN THE AUDITORIUM.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Overhead Sign Installation. The Experience in Overhead Signs form (850-070-03) must be filled out and submitted with the bid to be reviewed by the Department. If a Contractor is presently prequalified with the Department in Roadway Signing, it is not necessary to submit the form.

Call Order: 004 Proposal: E8P73

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0102- 1-	MAINTENANCE OF TRAFFIC	DA	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	MH	160.000
	0102- 60-	WORK ZONE SIGN	ED	2,448.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,432.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	304.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	68.000
	0102- 77-	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	232.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	261.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	40.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	40.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	160.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	60.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	2,390.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	84.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	10.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	4.000
	0633- 8- 4	MULTI-CONDUCTOR COMMUNICATION CABLE, RELOCATE	LF	15.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0639- 1-420	ELECTRICAL POWER SERVICE, RELOCATE, UNDERGROUND	AS	7.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE	LF	760.000
	0639- 2- 4	ELECTRICAL SERVICE WIRE, RELOCATE	LF	10.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	635.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	8.000
	0639- 6- 2	ELECTRICAL POWER SERVICE- TRANSFORMER, REPLACE EXISTING	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	5.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	2.000
	0676- 2-500	ITS CABINET- ADJUST/MODIFY	EA	4.000
	0676- 2-600	ITS CABINET- REMOVE	EA	2.000
	0684- 1- 4	MANAGED FIELD ETHERNET SWITCH, RELOCATE	EA	2.000
	0685-106-	SYSTEM AUXILIARIES, F&I, UNINTERRUPTIBLE POWER SOURCE	EA	6.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	6.000
	0700- 9-600	WALK-IN DYNAMIC MESSAGE SIGN, REMOVE	EA	6.000