

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 08151110 Call Order: 001 Proposal: E8P76 District:08

Counties: OSCEOLA

Road Name: YEEHAW JUNCTION SUNPASS CONVERSION

Limits: Midpoint

Project(s): 43577315201(*) Federal Aid No: N/A

Total Roadway Length:	0.312 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	11/10/15
Total Proposal Length:	0.312 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: \$450,000.00

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment, and incidentals necessary to convert existing lane 3 to a SunPass only lane as well as widen the exit ramp and relocate the existing traffic separator to accommodate two full width approach lanes at the plaza located on the Floridas Turnpike (SR 91), Milepost (MP) 193.00. The improvements will also consist of milling and resurfacing the ramps and plaza approach, signing and pavement marking, and lighting.

WORKING DAY

Any calendar day, exclusive of Saturdays, Sundays, State-designated holidays, and special event days, on which the Contractor works, or is expected to work, in accordance with the Work Documents issued by the Department unless otherwise directed by the Engineer. The Contractor may submit a written request to work on excluded days. This request shall be submitted to the Engineer for approval twenty-four hours in advance.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

The Contractor shall perform all work during day and night hours in accordance with the Turnpike Lane Closure Policy.

ATTENDANCE AT A MANDATORY PRE-BID CONFERENCE IS REQUIRED TO BID ON THIS WORK. THE PRE-BID CONFERENCE FOR THIS PROJECT WILL BE HELD ON OCTOBER 20, 2015 AT 9:00 A.M. AT THE STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION, TURNPIKE ENTERPRISE OFFICE, MILE POST65.0, FLORIDAS TURNPIKE AT POMPANO BEACH SERVICE PLAZA, POMPANO BEACH, FLORIDA, IN THE AUDITORIUM.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Asphalt Paving, Drainage Repair and Pavement Markings. The Experience in Asphalt Paving form (850-070-01), Experience in Drainage Repair form (850-070-05) and Experience in Pavement Markings form (850-070-06) must be filled out and submitted with the bid to be reviewed by the Department. If a Contractor is presently prequalified with the Department in Asphalt Paving (Hot Plant Mix Bituminous Course), Drainage, and Pavement Markings, it is not necessary to submit the form.

Call Order: 001 Proposal: E8P76

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	DA	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	MH	360.000
	0102- 60-	WORK ZONE SIGN	ED	1,163.000
	0102- 71- 14	BARRIER WALL, TEMPORARY, F&I, TYPE K	LF	838.000

Call Order: 001 Proposal: E8P76

ALT	Item	Description	Unit	Quantity
	0102- 71- 24	BARRIER WALL, TEMPORARY, RELOCATE, TYPE K	LF	424.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,564.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	63.000
	0102- 77-	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	860.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	76.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	5.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	358.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	16.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	16.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,752.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	1.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0107- 1-	LITTER REMOVAL	AC	4.740
	0107- 2-	MOWING	AC	4.300
	0110- 1- 1	CLEARING & GRUBBING	AC	1.000
	0120- 1-	REGULAR EXCAVATION	CY	82.000
	0120- 6-	EMBANKMENT	CY	84.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	510.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	303.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	1,335.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	131.000
	0327- 70- 15	MILLING EXIST ASPH PAVT, 2 3/4" AVG DEPTH	SY	4,734.000
	0334- 1- 23	SUPERPAVE ASPH CONC, TRAFFIC C, PG76-22, PMA	TN	535.000
	0337- 7- 22	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22, PMA	TN	81.000
	0337- 7- 43	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22, PMA	TN	260.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	55.200
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	46.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	47.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	73.000
	0536- 1- 1	GUARDRAIL -ROADWAY	LF	554.000
	0536- 73-	GUARDRAIL REMOVAL	LF	285.000
	0536- 85- 22	GUARDRAIL END ANCHORAGE ASSEMBLY- FLARED	EA	3.000
	0536- 85- 25	GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE II	EA	1.000
	0550- 10-221	FENCING, TYPE B, 5.1-6.0', W/ BARB WIRE ATTMT	LF	281.000
	0550- 60-234	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 18.1-20.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,200.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	450.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	16.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	8.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	21.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000

Call Order: 001 Proposal: E8P76

ALT	Item	Description	Unit	Quantity
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	1.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	1.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	79.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.760
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.582
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	9.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	273.000
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.040
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	7.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	2.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.563
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.041
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	265.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.050
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	15.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	65.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	70.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.014
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.120
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.060
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS	SF	910.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,500.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	450.000
	0715- 4-400	LIGHT POLE COMPLETE, RELOCATE	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	3.000
	0735- 88-	TOLL PLAZA MODIFY EXISTING	LS	1.000
	E550- 9-	FENCE REMOVAL	LF	320.000