

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	08151020	Call Order: 004	Proposal: E8P78	District:08
Counties:	BROWARD, MIAMI-DADE, TURNPIKE			
Road Name:	PAVEMENT MARKINGS - MP 0 to 51			
Limits:	86470000			
Project(s):	41546245202(*)	Federal Aid No: N/A		
Total Roadway Length:	11.617 Miles	Contract Days:	60	
Total Bridge Length:	0.000 Miles	Letting Date:	10/20/15	
Total Proposal Length:	11.617 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	
Proposal Budget Estimate:	\$100,000.00			

Please read the full advertisement

Description:

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to provide thermoplastic pavement markings on Floridas Turnpike (SR 91), Milepost (MP) 0.0 X to 51.0.

NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.

CONTRACTOR EXPERIENCE DOCUMENTATION: Expertise and Experience is required in the performance of Pavement Markings. The Experience in Pavement Markings form (850-070-06) must be filled out and submitted with the bid to be reviewed by the Department.

WORKING DAY

Any calendar day, exclusive of Saturdays, Sundays, State-designated holidays, and special event days, on which the Contractor works, or is expected to work, in accordance with the Work Documents issued by the Department unless otherwise directed by the Engineer. The Contractor may submit a written request to work on excluded days. This request shall be submitted to the Engineer for approval twenty-four hours in advance.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

The Contractor shall perform all work during night hours in accordance with the Turnpike Lane Closure Policy.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 004 Proposal: E8P78

ALT	Item	Description	Unit	Quantity
Section 0001 MAINTENANCE SUPPORT SERVICES (MH)				
	0102- 14-	TRAFFIC CONTROL OFFICER	MH	60.000
	0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	95.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	8,600.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	630.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	180.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.008
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	11.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	9.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,000.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	5.510
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.650
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	7.950
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.960
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	5.150
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	0.430