

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	08161115	Call Order: 004	Proposal: E8Q29	District:08
Counties:	BROWARD			
Road Name:	THERMOPLASTIC MARKINGS - SAWGRASS EXPRESSWAY			
Limits:	86472000			
Project(s):	43128125201(*)	Federal Aid No: N/A		
Total Roadway Length:	21.835 Miles	Contract Days:	60	
Total Bridge Length:	0.000 Miles	Letting Date:	11/15/16	
Total Proposal Length:	21.835 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	
Proposal Budget Estimate:	\$175,000.00			

Please read the full advertisement

**Description:**

The work specified in this contract consists of providing all labor, materials, equipment and incidentals necessary to provide thermoplastic pavement markings on the Sawgrass Expressway (SR 869), Milepost (MP) 0.475 to 21.8.

Prior to beginning work under this Contract, the Contractor shall submit to the Engineer for approval, two copies of the Contractor's proposed plan and methods for performing the work, including a listing of equipment and personnel anticipated for use.

No U-turns shall be permitted as a condition of this Contract, except at Service Plazas.

The Contractor shall perform all work night hours in accordance with the Turnpike Lane Closure Policy.

All lane closures shall be during the hours of 9:00 P.M to 5:00 A.M. and in one direction for one lane only.

Pay Item 0711-1170 (Wrong Way) arrow with White-Red Reflective Markers shall meet Index 17345.

**NO PRE-BID CONFERENCE WILL BE HELD FOR THIS PROJECT.**

**CONTRACTOR EXPERIENCE DOCUMENTATION:** Expertise and Experience is required in the performance of Pavement Markings. The Experience in Pavement Markings form (850-070-06) must be filled out and submitted with the bid to be reviewed by the Department.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 004 Proposal: E8Q29**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 MAINTENANCE SUPPORT SERVICES (MH)</b>				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	100.000
	0706- 3-	RETRO-REFLECTIVE PAVEMENT MARKERS	EA	113.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	10,000.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	450.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	250.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.010
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	14.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	104.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	11.250
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.700
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	7.300
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.700
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	9.150
	E710- 17-	REMOVAL OF NON-CONFLICTING PAINT/LOGLINE STRIPE PRIOR TO REFURBISH	SF	200.000