

SECTION 705

OBJECT MARKERS AND DELINEATORS

705-1 Description.

Furnish and install object markers to mark obstructions within or adjacent to the roadway of the types and at the locations called for in the Design Standards or on the Plans.

Furnish and install delineators along the side of the roadway to indicate the alignment of the roadway as indicated in the Design Standards or in the Plans.

705-2 Materials.

705-2.1 General: Meet the following requirements:

Object Markers and Delineators..... Section 993

Retroreflective and Nonreflective

Sign Sheeting..... Section 994

705-2.2 Product Acceptance on the Project: Ensure that delineators, delineator posts, and markers used to delineate guardrail and barrier wall are listed on the Qualified Products List.

Provide to the Engineer a manufacturer's certification conforming to the requirements of Section 6, which confirms that each product meets the requirements of this Section.

705-3 Installation Requirements.

Install delineators, object markers, and reflector units for guardrail and barrier wall and in accordance with the MUTCD, Design Standards and Plans.

705-4 Method of Measurement.

The quantity to be paid for will be the number of delineators or object markers furnished, installed and accepted.

705-5 Basis of Payment.

Prices and payments will be full compensation for work specified in this Section, including the cost of labor, materials, and incidental items required to complete the work.

Payment will be made under:

Item No. 705- 10 Object Marker - each.

Item No. 705- 11 Delineator - each.