

713 PERMANENT TAPE ~~TRAFFIC STRIPES AND~~ PAVEMENT MARKINGS.
 (REV ~~1-8-15~~ 1-8-15 ~~282-24-15~~) (~~FA 1-13-15~~) (7-15) (~~FA 3-13-15~~) (7-15)

Section 713 is deleted and the following substituted:

SECTION 713
PERMANENT TAPE ~~TRAFFIC STRIPES AND~~ PAVEMENT MARKINGS

713-1 Description.

Apply permanent tape ~~traffic stripes and~~ pavement markings, in accordance with the Contract documents.

713-2 Materials.

Use only ~~permanent tape traffic stripes and markings~~ materials listed on the Department's Approved Product List (APL), meeting the following requirements: ~~of 971-1 and 971-7.~~

~~Permanent Tape~~ 971-1 and 971-7

~~The~~ The Engineer will take random samples of ~~the all~~ materials in accordance with the Department's Sampling, Testing and Reporting Guide schedule.

713-3 Equipment.

Use equipment that is mobile and maneuverable to the extent that straight lines can be followed and normal curves can be made in a true arc.

Ensure the mechanical applicator is equipped with film cut-off device and a measuring device that automatically and accumulatively measures the length of each line placed with an accuracy tolerance of plus or minus 2 percent. Tape may be placed by hand on short sections, 500 feet or less if the tolerances in dimensions and in alignment specified in 710-5 are met.

713-4 Application.

713-4.1 General: Remove existing ~~pavement traffic stripes and~~ markings, such that scars or traces of removed markings will not conflict with new ~~pavement stripes and~~ markings by a method approved by the Engineer.

Before applying ~~permanent tape traffic stripes and markings~~, remove any material by a method approved by the Engineer that would adversely affect the bond of the ~~tape traffic stripes~~.

Apply a primer, sealer or surface preparation adhesive of the type recommended by the manufacturer. Ensure the ~~permanent~~ tape ~~stripes and markings~~ adheres to the pavement surface.

Offset longitudinal lines at least 2 inches from construction joints on portland cement concrete pavement.

Apply ~~permanent tape traffic stripes or markings~~ only to dry surfaces only, and when the ambient air and surface temperature is at least 55°F and rising.

Apply ~~striping permanent tape~~ to the same tolerances in dimensions and in alignment specified in 710-5. ~~When applying permanent tape traffic stripes and marking over existing markings, ensure that no more than 2 inches on either end and not more than 1 inch on either side of the existing line is visible.~~

Apply ~~permanent tape~~~~traffic stripes and markings~~ to the pavement by means approved by the Engineer. ~~The stripes and markings shall be installed immediately following the paving operation.~~

Conduct field testing in accordance with FM 5-541. Take test readings representative of the ~~striping pavement marking~~ performance. Remove and replace ~~pavement stripes and markings~~~~permanent tape~~ not meeting the requirements of this Section at no additional cost to the Department.

Apply all ~~final~~ pavement markings prior to opening the road to traffic.

713-4.2 Thickness: Apply ~~permanent tape~~~~traffic stripes or markings~~ such that, the ~~pavement stripes or~~ markings ~~will that~~ have a thickness as designated on the APL for the particular product used.

Measure, record and certify on a Department approved form and submit to the Engineer, the thickness of white and yellow pavement markings in accordance with FM 5-541.

713-4.3 Retroreflectivity: Apply white and yellow ~~traffic stripes and pavement~~ markings that will attain an initial retroreflectivity of not less than 450 mcd/lx·m² for white markings and not less than 350 mcd/lx·m² for yellow markings. Black ~~pavement markings~~ ~~portions of contrast tapes and black masking tapes~~ must have a ~~retro~~reflectance of less than 5 mcd/lx m².

Measure, record and certify on Department approved form and submit to the Engineer, the retroreflectivity of white and yellow pavement markings in accordance with FM 5-541.

713-4.4 Color: Use material meeting the requirements of 971-1.

713-5 Contractor's Responsibility for Notification.

Notify the Engineer prior to the placement of ~~pavement stripes and marking~~~~the~~ material. Furnish the Engineer with the manufacturer's name and batch numbers of the material to be used. Ensure that the approved batch numbers appear on the material packages.

713-6 Protection of Newly Applied Stripes Pavement Markings.

Do not allow traffic onto or permit vehicles to cross ~~onto~~ newly applied ~~traffic stripes and pavement~~ markings until they are sufficiently bonded. Remove and replace any portion of the ~~traffic stripes and pavement~~ markings damaged by passing traffic or from any other cause, at no additional cost to the Department.

713-7 Observation Period.

Longitudinal pavement markings are subject to a 180 day observation period under normal traffic. The observation period shall begin with the satisfactory completion and acceptance of the work.

The longitudinal pavement markings shall show no signs of failure due to blistering, excessive cracking, chipping, discoloration, poor adhesion to the pavement, loss of ~~retro~~reflectivity or vehicular damage. The retroreflectivity shall meet the initial requirements of 713-4.3. The Department reserves the right to check the retroreflectivity any time prior to the end of the observation period.

Replace, at no additional expense to the Department, any longitudinal pavement markings that do not perform satisfactorily under traffic during the 180 day observation period.

713-8 Corrections for Deficiencies.

Correct all deficiencies by removal and reapplication ~~Remove and reapply aof a~~
~~1.0~~one mile section centered around ~~any the~~ deficiency, as determined by the Engineer, at no additional cost to the Department.

713-9 Submittals.

713-9.1 Submittal Instructions: Prepare a certification of quantities, using the Department's current approved form, for each project in the Contract. Submit the certification of quantities and daily worksheets to the Engineer. The Department will not pay for any disputed items until the Engineer approves the certification of quantities.

713-9.2 Contractor's Certification of Quantities: Request payment by submitting a certification of quantities no later than Twelve O clock noon Monday after the estimate cut-off date or as directed by the Engineer, based on the amount of work done or completed. Ensure the certification of quantities consists of the following:

~~(a)~~1. Contract Number, FPID Number, Certification Number, Certification Date and the period that the certification represents.

~~(b)~~2. The basis for arriving at the amount of the progress certification, less payments previously made and less any amount previously retained or withheld. The basis will include a detailed breakdown provided on the certification of items of payment.

713-10 Method of Measurement.

The quantities, authorized and acceptably applied, ~~to be paid for~~ under this Section will be paid as follows:

~~(a)~~1. The length, in grossnet miles, of 6 inch solid, 10'-30' skip, and 3'-9' dotted, and 6'-10' dotted lines, ~~traffic stripe, authorized and acceptably applied.~~

~~(b)~~ The total traversed distance in gross miles of 10-30 or 3-9 skip line. The actual applied line is 25% of the traverse distance, for a 1:3 ratio. This equates to 1,320 feet of marking per mile of single line.

~~(c)~~ The net length, in feet, of all other types of lines and stripes, authorized and acceptably applied.

~~(d)~~2. The area, in square feet, ~~for~~ removale of existing markings acceptably removed. Payment for removal of conflicting markings will be in accordance with 102-5.8. Payment for removal of non-conflicting markings will be paid separately.

The gross mile measurement will be taken as the distance from the beginning of the permanent tape line to the end of the permanent tape line and will include the unmarked gaps for skip and dotted lines. The gross mile measurement will not include designated unmarked lengths at intersections, turn lanes, etc. Final measurement will be determined by plan dimensions or stations, subject to 9-1.3.1.

~~(e)~~ The number of pavement messages, symbols and directional arrows, authorized and acceptably applied.

713-11 Basis of Payment.

Prices and payments will be full compensation for all work specified in this Section, including, all cleaning and preparing of surfaces, furnishing of all materials, application, curing and protection of all items, protection of traffic, furnishing of all tools, machines and equipment, and all incidentals necessary to complete the work. Final payment will be withheld until all deficiencies are corrected.

Payment will be made under:

Item No. 713-1 - Permanent Tape.

Solid – per gross mile.

Skip – per gross mile.

Dotted – per gross mile.

Remove – per square foot.