

EXPECTED IMPLEMENTATION JANUARY 2010

102 MAINTENANCE OF TRAFFIC. (REV 2-2-09) (FA 4-8-09) (1-10)

SUBARTICLE 102-9.5.2 (of the Supplemental Specifications) is deleted and the following substituted:

102-9.5.2 Barrier Wall (Temporary): Furnish, install, maintain, remove and relocate a temporary barrier wall in accordance with the plans. Ensure that temporary concrete barrier wall for use on roadway sections, complies with Section 521 and Index Nos. 412, 415 or 414 as specified in the plans. Ensure that temporary concrete barrier wall for use on bridge and wall sections, complies with Index No 414 as specified in the plans. Ensure that temporary water filled barrier wall used on roadway sections meets the NCHRP Report 350 criteria and is listed on the Qualified Products List (QPL). Barriers meeting the requirements of Index No. 412, 415 or temporary water filled barriers on the QPL will not be accepted as an alternate to barriers meeting the requirements of Index No. 414.

D

R

A

F

T