

EXPECTED IMPLEMENTATION JANUARY 2010

110 CLEARING AND GRUBBING. (REV 5-29-09) (FA 7-15-09) (1-10)

SUBARTICLE 110-6.2.1 (Page 148) is deleted and the following substituted:

110-6.2.1 General: Remove the structures in such a way so as to leave no obstructions to any proposed new structures or to any waterways. Pull, cut off, or break off pilings to the requirements of the permit or other Contract Documents, or if not specified, not less than 2 feet below the finish ground line. In the event that the plans indicate channel excavation to be done by others, consider the finish ground line as the limits of such excavation. For materials which are to remain the property of the Department or are to be salvaged for use in temporary structures, avoid damage to such materials, and entirely remove all bolts, nails, etc. from timbers to be so salvaged. Mark structural steel members for identification as directed.