

EXPECTED IMPLEMENTATION JANUARY 2010

120 EMBANKMENT CONSTRUCTION.

(REV 8-5-09) (FA 8-13-09) (1-10)

SUBARTICLE 120-8.1 (Page 167) is deleted and the following substituted:

120-8.1 General: Construct embankments in sections of not less than 300 feet in length or for the full length of the embankment. Perform work in accordance with an approved Quality Control Plan meeting the requirements of 105-3.

For construction of mainline pavement lanes, turn lanes, ramps, parking lots, concrete box culverts and retaining wall systems, a LOT is defined as a single lift of finished embankment not to exceed 500 feet.

For construction of shoulder-only areas, bike/shared use paths, and sidewalks areas, a LOT is defined as 2,000 feet or one Day's Production, whichever is greater.

Isolated compaction operations will be considered as separate LOTS. For multiple phase construction, a LOT shall not extend beyond the limits of the phase.

SUBARTICLE 120-10.1 (Pages 171-173) is expanded by the following:

120-10.1.7 Payment for Resolution Tests: If the Resolution laboratory results compare favorably with the Quality Control results, the Department will pay for Resolution testing. No additional compensation, either monetary or time, will be made for the impacts of any such testing.

If the Resolution laboratory results do not compare favorably with the Quality Control results, the costs of the Resolution testing will be deducted from monthly estimates. No additional time will be granted for the impacts of any such testing.