

EXPECTED IMPLEMENTATION JANUARY 2010

611 ACCEPTANCE PROCEDURES. (REV 8-3-09) (FA 8-4-09) (1-10)

SUBARTICLE 611-2.2 (Page 731) is deleted and the following substituted:

611-2.2 Final Acceptance: The Engineer will make inspection for final acceptance of signal installations as part of all work under the Contract in accordance with 5-11, only after satisfactory completion of all field tests of completed installations in accordance with the requirements of 611-4 and on the basis of a comprehensive final field inspection of all traffic signal installations. The Engineer will make the final inspection of all signal installations with a Contractor's representative and, when applicable, a representative of the agency designated to accept maintenance responsibility. Transfer to the Department any guarantees on equipment or materials furnished by the manufacturer and ensure that the manufacturer includes with such guarantees the provision that they are subject to such transfer, and proper validation of such fact.

SUBARTICLE 611-5.1 (Page 734) is deleted and the following substituted:

611-5.1 General Requirements-Warranty: After satisfactory completion of all field tests in accordance with 611-4, repair or replace any defective components or work of the signal installations for a 90 day period after final acceptance in accordance with 5-11.

D

R

A

F

T