

EXPECTED IMPLEMENTATION JANUARY 2013

D

700 HIGHWAY SIGNING – REMOVAL OR RELOCATION OF SIGNS. (REV 5-18-12) (FA 8-1-12) (1-13)

ARTICLE 700-9 (Page 786) is deleted and the following substituted:

700-9 Removal or Relocation of Signs.

Relocation of signs shall consist of removing the existing sign assembly and installing the sign on a new foundation.

When the plans call for existing ground-mounted signs to be relocated or removed, immediately remove supports and footings that project more than 6 inches above the ground surface after removing the sign panel from the assembly. Remove existing footings to a depth at least 12 inches below the ground surface. Restore the area of the sign removal or relocation to the condition of the adjacent area. The costs will be included in the Contract unit price of the item to which it is incidental.

Notify the Engineer a minimum of 30 days prior to removal of existing Logo sign structures.

R

A

F

T