



Florida Department of Transportation

RICK SCOTT
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

ANANTH PRASAD, P.E.
SECRETARY

July 2, 2013

Monica Gourdine
Program Operations Engineer
Federal Highway Administration
545 John Knox Road, Suite 200
Tallahassee, Florida 32303

Re: State Specifications and Estimates Office
Section **320**
Proposed Specification: **3200603 Hot Mix Asphalt – Plant Methods and Equipment.**

Dear Ms. Gourdine:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

These changes were proposed by Greg Sholar of the State Materials Office to add language to allow the first five loads of a day's production of warm mix asphalt to be produced at a hot mix asphalt temperature in order to heat the paving machine.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via email to SP965DS or daniel.scheer@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at 414-4130.

Sincerely,

Signature on file

Daniel Scheer, P.E.
State Specifications Engineer

DS/dt

Attachment

cc: Florida Transportation Builders' Assoc.
State Construction Engineer

HOT MIX ASPHALT – PLANT METHODS AND EQUIPMENT.
(REV 5-10-13)

SUBARTICLE 320-6.3.2 (Page 246 – 247) is deleted and the following substituted:

320-6.3.2 Test Frequency: The normal frequency for taking asphalt mix temperatures will be for each day, for each design mix on the first five loads and one out of every five loads thereafter. Take the temperature of the asphalt mix at the plant and at the roadway before the mix is placed at the normal frequency. Record the temperature on the front of the respective delivery ticket. The Engineer shall review the plant and roadway temperature readings and may take additional temperature measurements at any time.

If any single load at the plant or at the roadway is within the master range shown in Table 320-2 but does not meet the criteria shown in Table 320-3 (for single measurements or the average of five consecutive measurements), the temperature of every load will be monitored until the temperature falls within the specified tolerance range in Table 320-3; at this time the normal frequency may be resumed. **For warm mix asphalt, the Contractor may produce the first five loads of the production day at a hot mix asphalt temperature not to exceed 330°F for purposes of heating the asphalt paver. For this situation, the upper tolerances of Tables 320-2 and 320-3 as applied to the warm mix asphalt mix design do not apply.**

HOT MIX ASPHALT – PLANT METHODS AND EQUIPMENT.
(REV 5-10-13)

SUBARTICLE 320-6.3.2 (Page 246 – 247) is deleted and the following substituted:

320-6.3.2 Test Frequency: The normal frequency for taking asphalt mix temperatures will be for each day, for each design mix on the first five loads and one out of every five loads thereafter. Take the temperature of the asphalt mix at the plant and at the roadway before the mix is placed at the normal frequency. Record the temperature on the front of the respective delivery ticket. The Engineer shall review the plant and roadway temperature readings and may take additional temperature measurements at any time.

If any single load at the plant or at the roadway is within the master range shown in Table 320-2 but does not meet the criteria shown in Table 320-3 (for single measurements or the average of five consecutive measurements), the temperature of every load will be monitored until the temperature falls within the specified tolerance range in Table 320-3; at this time the normal frequency may be resumed. For warm mix asphalt, the Contractor may produce the first five loads of the production day at a hot mix asphalt temperature not to exceed 330°F for purposes of heating the asphalt paver. For this situation, the upper tolerances of Tables 320-2 and 320-3 as applied to the warm mix asphalt mix design do not apply.