

EXPECTED IMPLEMENTATION JANUARY 2014

521 CONCRETE BARRIERS, TRAFFIC RAILING BARRIERS, AND PARAPETS. (REV 6-4-13) (FA 6-18-13) (1-14)

ARTICLE 521-8 (Page 676) is deleted and the following substituted:

521-8 Method of Measurement.

The quantity to be paid for under this Section will be the plan quantity, in feet, completed and accepted. The quantity will be measured along the top of the barrier wall from the begin to end station, including transitional and end sections, with no deduction for expansion joints or open joints. Barrier wall on bridge structures and approach slabs to be removed shall be included in the cost of removal of existing structures. Barrier wall to be removed along roadways to be paid for as concrete barrier wall removal.

ARTICLE 521-9 (Page 677) is deleted and the following substituted:

521-9 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section, including all reinforcing steel, conduits, materials and incidentals necessary to complete the work.

Payment will be made under:

- | | |
|-------------------|--|
| Item No. 521- 1- | Median Concrete Barrier Wall - per foot. |
| Item No. 521- 5- | Concrete Traffic Railing Barrier - Bridge - per foot. |
| Item No. 521- 6- | Concrete Parapet - per foot. |
| Item No. 521- 7- | Concrete Traffic Railing Barrier - Retaining Wall System - per foot. |
| Item No. 521- 8- | Concrete Traffic Railing – with Junction Slab - per foot. |
| Item No. 521- 72- | Shoulder Concrete Barrier Wall - per foot. |
| Item No. 521- 73- | Concrete Barrier Wall Removal - per foot. |