

# EXPECTED IMPLEMENTATION JANUARY 2015

## MOBILIZATION.

(REV 2-17-14) (FA 7-2-14) (1-15)

SECTION 101 is deleted and the following substituted:

### SECTION 101 MOBILIZATION

#### 101-1 Description.

Perform preparatory work and operations in mobilizing for beginning work on the project, including, but not limited to, those operations necessary for the movement of personnel, equipment, supplies, and incidentals to the project site and for the establishment of temporary offices, buildings, safety equipment and first aid supplies, and sanitary and other facilities.

Include the costs of bonds and any required insurance and any other preconstruction expense necessary for the start of the work, excluding the cost of construction materials.

#### 101-2 Basis of Payment.

**101-2.1 General:** The work and incidental costs specified as being covered under this Section will be paid for at the lump sum prices for the items of Mobilization included in the Schedule of Values.

**101-2.2 Partial Payments:** When the Notice to Proceed has been issued, partial payments will be made in accordance with the following:

Partial payment will be made at 25% of the Mobilization amount shown in the Schedule of Values per month for the first four months until 100% of the Mobilization amount shown in the Schedule of Values is paid.. In no event shall more than 50% of the Mobilization amount shown in the Schedule of Values be paid prior to commencing construction on the project site.

Total partial payments for Mobilization on any project, including when more than one project or job is included in the Contract, will be limited to 10% of the original Contract amount for that project. Any remaining amount will be paid upon completion of all work on the Contract.

Retainage, as specified in 9-5, will be applied to all partial payments.

Partial payments made on this item will in no way act to preclude or limit any of the provisions for partial payments otherwise provided for by the Contract.