

ORIGINATION FORM

Date: **05/31/2014**

Originator: **Ezzeldin Benghuzzi**

Contact Information: **850- 414-4314**

Specification Title: **Maintenance of Traffic**

Specification Section, Article, or Subarticle Number:

102-5.9, 102-9.15

Why does the existing language need to be changed?

102-5.9 changed to clarify the requirements of warning lights

102-9.15 changed to match the requirements of the standard index

Summary of the changes:

102-5.9 The Warning lights shall be a high intensity amber or white rotating, flashing, oscillating or strobe light

102-9.15 When required, furnish, install, maintain, remove, and reinstall temporary raised rumble strip sets.

Are these changes applicable to all Department jobs? **Yes**

If not, what are the restrictions?

Will these changes result in an increase or decrease in project costs?

If yes, what is the estimated change in costs? **No substantial change in cost.**

With who have you discussed these changes? , Chester Henson, Gevin McDaniel, Stefanie Maxwell

What other offices will be impacted by these changes? **None**

Are changes needed to the PPM, Design Standards, SDG, CPAM or other manual? **PPM**

Are all references to external publications current? **Yes**

If not, what references need to be updated (please include changes in the redline)?

Is a Design Bulletin, Construction Memo, or Estimates Bulletin needed? **NO**

Contact the State Specifications Office for assistance in completing this form.

Daniel Scheer 850-414-4130 daniel.scheer@dot.state.fl.us

Frances Thomas 850-414-4101 frances.thomas@dot.state.fl.us

Debbie Toole 850-414-4114 deborah.toole@dot.state.fl.us

Andy Harper 850-414-4127 clifton.harper@dot.state.fl.us

Ray Haverty 850-414-4129 ray.haverty@dot.state.fl.us



Florida Department of Transportation

RICK SCOTT
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

ANANTH PRASAD, P.E.
SECRETARY

MEMORANDUM

DATE: June 20, 2014
TO: Specification Review Distribution List
FROM: Daniel Scheer, P.E., State Specifications Engineer
SUBJECT: Proposed Specification: **1020509 Maintenance of Traffic.**

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change.

This change was proposed by Ezzeldin Benghuzzi of the Department's Roadway Design Office to clarify the requirements for warning lights and modify the language for consistency with the Design Standards.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or online at

<http://www2.dot.state.fl.us/SpecificationsEstimates/Development/IndustryReview.aspx> .

Comments received after **July 18, 2014**, may not be considered. Your input is encouraged.

DS/dt
Attachment

MAINTENANCE OF TRAFFIC.
(REV 6-2-14)

SUBARTICLE 102-5.9 is deleted and the following substituted:

102-5.9 Vehicle and Equipment Visibility: Equip all pickups and automobiles used on the project with a minimum of one Class 2 ~~amber or white~~ warning light that meets the Society of Automotive Engineers Recommended Practice SAE J595, dated November 1, 2008, or SAE J845, dated December 1, 2007, and incorporated herein by reference. Existing lights that meet SAE J845, dated March, 1992, or SAE J1318, dated April, 1986, may be used to its end of service life. ~~The warning lights shall be a high intensity amber or white rotating, flashing, oscillating or strobe light.~~ Lights ~~should~~ shall be unobstructed by ancillary vehicle equipment such as ladders, racks or booms. If the light is obstructed, additional lights will be required. The lights shall be operating when a vehicle is in a work area where a potential hazard exists, when operating the vehicle at less than the average speed for the facility while performing work activities, making frequent stops or called for in the Plans or Design Standards.

Equip all other vehicles and equipment with a minimum of 4 square feet of retroreflective sheeting or ~~flashing~~ warning lights.

To avoid distraction to motorists, do not operate the lights on the vehicles or equipment when the vehicles are outside the clear zone or behind a barrier.

SUBARTICLE 102-9.1 is deleted and the following substituted:

102-9.1 Installation and Maintenance: Install and maintain temporary traffic control devices ~~as detailed in the Plans, Index 600 of the Design Standards and when applicable, in accordance with the approved vendor drawings, as provided on the Department's Qualified Products List (QPL) or the Department's~~ Approved Products List (APL). Erect the required temporary traffic control devices to prevent any hazardous conditions and in conjunction with any necessary traffic re-routing to protect the traveling public, workers, and to safeguard the work area. Use only those devices that are on the ~~QPL or the~~ APL. Immediately remove or cover any devices that do not apply to existing conditions.

All temporary traffic control devices must meet the requirements of National Cooperative Highway Research Program Report 350 (NCHRP 350) or the Manual for Assessing Safety Hardware 2009 (MASH) and current FHWA directives. Manufacturers seeking evaluation must furnish certified test reports showing that their product meets all test requirements set forth by NCHRP 350 or the MASH. Manufacturers seeking evaluation of Category I devices for inclusion on the ~~Q~~APL shall include the manufacturer's self-certification letter. Manufacturer's seeking evaluation of Category II and Category III devices for inclusion on the ~~Q~~APL shall include the FHWA WZ numbered acceptance letter with attachments and vendor drawings of the device in sufficient detail to enable the Engineer to distinguish between this and similar devices. For devices requiring field assembly or special site preparation, vendor drawings shall include all field assembly details and technical information necessary for proper application and installation and must be signed and sealed by a Professional Engineer registered in the State of Florida. Manufacturers seeking evaluation of Category IV devices for inclusion on the ~~QPL or~~ APL must comply with the requirements of Section 990 and include detailed vendor drawings of the device

along with technical information necessary for proper application, field assembly and installation.

Ensure that the ~~QPL~~ or APL number is permanently marked on the device at a readily visible location. Sheeting used on devices is exempt from this marking requirement.

Notify the Engineer of any scheduled operation which will affect traffic patterns or safety sufficiently in advance of commencing such operation to permit his review of the plan for the proposed installation of temporary traffic control devices.

Ensure an employee is assigned the responsibility of maintaining the position and condition of all temporary traffic control devices throughout the duration of the Contract. Keep the Engineer advised at all times of the identification and means of contacting this employee on a 24 hour basis.

Keep temporary traffic control devices in the correct position, properly directed, clearly visible and clean, at all times. Ensure that all traffic control devices meet acceptable standards as outlined in American Traffic Safety Services Association (ATSSA) "Quality Guidelines for Temporary Traffic Control Devices and Features". Immediately repair, replace or clean damaged, defaced or dirty devices.

SUBARTICLE 102-9.15 is deleted and the following substituted:

102-9.15 Temporary Raised Rumble Strip Sets: When ~~called for in the Plans~~ *required*, furnish, install, maintain, remove, and reinstall temporary raised rumble strip sets.

Install the temporary raised rumble strip sets per the manufacturer's recommendations and in accordance with Design Standards, Index No. 600.

The temporary raised rumble strip may be either a removable polymer striping tape or a molded engineered polymer material.