

EXPECTED IMPLEMENTATION JANUARY 2015

102 MAINTENANCE OF TRAFFIC. (REV 3-11-14) (FA 4-28-14) (1-15)

SUBARTICLE 102-9.5.3 is deleted and the following substituted:

102-9.5.3 Glare Screen (Temporary): Use temporary glare screens listed on the QPL that meet the requirements of Section 990. Furnish, install, maintain, remove and relocate glare screen systems in conjunction with temporary barrier wall at locations identified in the Plans.

Ensure the anchorage of the glare screen to the barrier is capable of safely resisting an equivalent tensile load of 600 pounds per foot of glare screen, with a requirement to use a minimum of three fasteners per barrier section.

When glare screen is utilized on temporary barrier wall, barrier delineators will not be required.

SUBARTICLE 102-11.10 is deleted and the following substituted:

102-11.10 Barrier Delineators: The number of barrier delineators, installed on top of barrier wall, used on the project, meeting the requirements of the Design Standards and Section 705.

SUBARTICLE 102-13.10 is deleted and the following substituted:

102-13.10 Barrier Delineators: No separate payment will be made for barrier delineators installed on top of temporary barrier wall. The cost of furnishing, installing and maintaining the barrier delineators will be included in the cost of the temporary barrier wall.

SUBARTICLE 102-13.23 is deleted and the following substituted:

102-13.23 Payment Items: Payment will be made under:

Item No. 102- 1-	Maintenance of Traffic - lump sum.
Item No. 102- 2-	Special Detour - lump sum.
Item No. 102- 3-	Commercial Material for Driveway Maintenance - per cubic yard.
Item No. 102- 14-	Traffic Control Officer - per hour.
Item No. 102- 60-	Work Zone Sign - per each per day.
Item No. 102- 61-	Business Sign - each.
Item No. 102- 71-	Barrier Wall - per foot.
Item No. 102- 75-	Temporary Lane Separator - per foot
Item No. 102- 94-	Glare Screen - per foot.
Item No. 102- 73-	Guardrail (Temporary) - per foot.
Item No. 102- 74-	Barricade (Temporary) - per each per day.

EXPECTED IMPLEMENTATION JANUARY 2015

D

Item No. 102- 76- Arrow Board - per each per day.
Item No. 102- 77- High Intensity Flashing Lights (Temporary - Type B) - per each per day.
Item No. 102- 78- Temporary Retroreflective Pavement Markers - each.
Item No. 102- 81- Crash Cushion (Gating) (Temporary) - per location.
Item No. 102- 89- Crash Cushion (Redirective) (Temporary) - per location.
Item No. 102- 99- Portable Changeable Message Sign (Temporary) - per each per day.

Item No. 102-104- Temporary Signalization and Maintenance - per intersection per day.

Item No. 102-107- Temporary Traffic Detection and Maintenance - per intersection per day.

Item No. 102-150- Portable Regulatory Sign - per each per day.

Item No. 102-150- Radar Speed Display Unit - per each per day.

Item No. 102-909- Temporary Raised Rumble Strips - per day.

Item No. 102-911- Removable Tape (White/Black) - per foot.

Item No. 102-912- Removable Tape (Yellow) - per foot.

Item No. 710- Painted Pavement Markings.

Item No. 711- Thermoplastic Traffic Stripes and Markings.

R

A

F

T