

.....

Kandarappallil Jose  
772-429-4936  
Kandarappallil.Jose@dot.state.fl.us

Comment: (7-8-14) Suggest the highlighted changes.

1. 556-4.3.1 Testing Requirements Methods: Ensure all casing, pipes, and joints meet the Department's pressure requirements. Testing may consist of one of the following methods but must always meet or exceed Department testing requirements. (a) Follow the Product Manufacturer's pressure testing recommendations. (b) Ensure that the product carrier pipes installed without a casing meet the pressure requirements set by the owner **Department**. If the owner **manufacturer** does not require pressure testing, the Engineer may require at least one test.

Response:

2.556-4.3.2 Damaged Product Testing: When there is any indication that the installed product has sustained damage and may leak, stop the work, notify the Engineer and investigate damage. The Engineer may require a pressure test and reserves the right to be present during the test. Perform pressure test within 24 hours unless otherwise approved by the Engineer. Furnish a copy of the test results to the Engineer for review and **approval-acceptance**. The Engineer shall be allowed up to 72 hours to **approve acceptance** or determine if the product installation is not in compliance with specifications. The Engineer may require non-compliant installations to be filled with excavatable flowable fill **at no cost to department**.

Response:

\*\*\*\*\*